

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	**	*	196	82
STA. 420+00.00 TO STA. 454+00.00				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

* BROWN & SCHUYLER CONTRACT NO. 72432
** 9RS-4, (10,11) RS-3; (10B-1) R
SHEET 10 OF 123

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS 70105			
LOCATION	OFFSET FT	LT/RT	QUANTITY EACH
STA. 418+50.00	59.81	RT	1
STA. 419+29.12	85.55	LT	1
STA. 419+50.00	115.00	RT	1
STA. 420+00.00	95.00	LT	1
STA. 420+12.00	115.00	RT	1
STA. 420+35.08	135.59	RT	1
STA. 420+42.91	126.80	RT	1
STA. 421+10.00	155.00	RT	1
STA. 421+50.00	95.00	LT	1
STA. 421+50.00	125.00	LT	1
STA. 421+50.00	95.00	RT	1
STA. 421+50.00	125.00	RT	1
STA. 422+71.52	125.59	LT	1
STA. 423+52.42	135.70	LT	1
STA. 423+87.95	85.00	RT	1
STA. 425+11.82	70.00	LT	1
STA. 425+23.67	69.28	RT	1
STA. 427+00.00	70.00	LT	1
STA. 430+00.00	100.00	LT	1
STA. 433+00.00	120.00	LT	1
STA. 439+00.00	55.00	LT	1
STA. 441+00.00	135.00	LT	1
STA. 442+35.00	165.00	LT	1
STA. 444+00.00	175.00	LT	1
STA. 445+30.00	120.00	LT	1
STA. 450+48.71	57.19	LT	1
TOTAL			26

TRAFFIC CONTROL AND PROTECTION	70100200 QUANTITY EACH	70100460 QUANTITY L SUM	70100500 QUANTITY L SUM	70101835 QUANTITY L SUM	70103815 QUANTITY CAL DA
TRAFFIC CONTROL AND PROTECTION, STANDARD 701331	2				
TRAFFIC CONTROL AND PROTECTION, STANDARD 701306		1			
TRAFFIC CONTROL AND PROTECTION, STANDARD 701326			1		
TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22				1	
TRAFFIC CONTROL SURVEILLANCE					13
TOTAL	2	1	1	1	13

SHORT-TERM PAVEMENT MARKING				70300100 QUANTITY FOOT
LOCATION STATION TO STATION	NO. OF APPLICATIONS	APPLIED		
STA. 419+60.00 TO STA. 454+40.00	3	CENTERLINE		1044
TOTAL				1044

TRANSVERSE DRAINS COMPLETE		QUANTITY EACH
LOCATION		
STA 423+00 (NO SKEW)		1
STA 428+00		1
STA 431+00		1
STA 445+50		1
ONE VARIOUS PER DISTRICT 6		1
TOTAL		5

RAISED REFLECTIVE PAVEMENT MARKERS 78100100			
LOCATION STATION TO STATION	APPLIED	QUANTITY EACH	
STA. 419+60.00 TO STA. 454+40.00	CENTERLINE	44	
TOTAL			44

WORK ZONE PAVEMENT MARKING REMOVAL 70301000		QUANTITY SQ FT
LOCATION		
SHORT TERM PAVEMENT MARKING (TOP LIFT)		145
TOTAL		145

FENCE REMOVAL					Z0022800 QUANTITY FOOT
LOCATION STATION TO STATION					
STA. 418+69.00	LT	TO	STA. 419+06.00	LT	37
STA. 420+91.00	LT	TO	STA. 421+36.00	LT	45
STA. 425+11.00	LT	TO	STA. 425+27.00	LT	22
STA. 430+09.00	LT	TO	STA. 430+24.00	LT	21
STA. 438+93.00	LT	TO	STA. 440+83.00	LT	199
STA. 440+94.00	LT	TO	STA. 441+04.00	LT	27
STA. 445+33.00	LT	TO	STA. 445+45.00	LT	17
STA. 450+14.00	LT	TO	STA. 450+50.00	LT	36
TOTAL					404

GUARDRAIL MARKERS, TYPE A 78200410			
LOCATION	LT/RT	QUANTITY EACH	
STA. 430+83.88 TO 434+14.53	RT	4	
STA. 431+90.46 TO 434+33.61	LT	4	
STA. 439+03.71 TO 441+46.86	RT	4	
STA. 439+22.79 TO 442+53.44	LT	4	
TOTAL			16

THE FOLLOWING ARE ESTIMATED QUANTITIES FOR CORRECTING GEOTECHNICAL PROBLEMS. THESE QUANTITIES MAY BE REDUCED, INCREASED, OR DELETED BY THE ENGINEER BASED ON ACTUAL FIELD CONDITIONS. NO WORK INVOLVING THESE QUANTITIES SHALL BE PERFORMED WITHOUT THE DIRECTION AND APPROVAL OF THE ENGINEER.		
PAY ITEM	ESTIMATED LIMITS	ESTIMATED QUANTITY
ROCKFILL-SUBGRADE (Z0054530)	444+25 TO 445+50 & VARIOUS	350 TONS
EARTH EXCAVATION (ROCKFILL) (X2020500)	444+25 TO 445+50 & VARIOUS	670 CU YD
TRANSVERSE DRAINS COMPLETE	445+50 & VARIOUS	2 EACH

TERMINAL MARKER - DIRECT APPLIED 78201000		
LOCATION	LT/RT	QUANTITY EACH
STA. 431+44.03	RT	1
STA. 432+50.33	LT	1
STA. 439+24.51	RT	1
STA. 439+43.27	LT	1
TOTAL		4

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL 70300200			
LOCATION STATION TO STATION		QUANTITY EACH	
STA. 419+60.00 TO STA. 427+00.00		10	
STA. 447+00.00 TO STA. 454+40.00		10	
TOTAL			20

MOBILIZATION		67100100 QUANTITY L SUM
LOCATION/DESCRIPTION		
ENTIRE PROJECT (STA. 420+00.00 TO STA. 454+00.00)		1
TOTAL		1

CONSTRUCTION LAYOUT		Z0013798 QUANTITY L SUM
LOCATION		
ENTIRE PROJECT		1
TOTAL		1

PAINT PAVEMENT MARKING - LINE 5" 78001120			
LOCATION STATION TO STATION	LT/RT	APPLIED	QUANTITY FOOT
STA. 419+60.00 TO STA. 423+62.00	LT	EDGE LINE	402.00
STA. 424+42.00 TO STA. 452+89.00	LT	EDGE LINE	2847.00
STA. 453+91.00 TO STA. 454+40.00	LT	EDGE LINE	49.00
STA. 419+60.00 TO STA. 454+40.00	RT	EDGE LINE	3480.00
STA. 419+60.00 TO STA. 454+40.00	CL	CENTERLINE	870.00
STA. 419+60.00 TO STA. 420+50.00	RT	EDGE LINE	90.00
TOTAL			7738

RELOCATE SIGN PANEL - TYPE I 72400710		
LOCATION	LT/RT	QUANTITY SQ FT
STA. 430+65.30	RT	5
STA. 430+65.30	RT	5
STA. 453+41.24	RT	5
STA. 453+28.53	LT	5
TOTAL		20

TEMPORARY PAVEMENT MARKING - LINE 5" 70300230			
LOCATION STATION TO STATION	LT/RT	APPLIED	QUANTITY FOOT
STA. 419+60.00 TO STA. 423+62.00	LT	EDGE LINE	402.00
STA. 424+42.00 TO STA. 452+89.00	LT	EDGE LINE	2847.00
STA. 453+91.00 TO STA. 454+40.00	LT	EDGE LINE	49.00
STA. 419+60.00 TO STA. 454+40.00	RT	EDGE LINE	3480.00
STA. 419+60.00 TO STA. 454+40.00	CL	CENTERLINE	870.00
STA. 419+60.00 TO STA. 420+50.00	RT	EDGE LINE	90.00
TOTAL			7738

RELOCATE SIGN PANEL ASSEMBLY - TYPE B 72400840		
LOCATION	LT/RT	QUANTITY EACH
STA. 433+46.46	RT	1
TOTAL		1

RELOCATE SIGN PANEL ASSEMBLY - TYPE C 72400840		
LOCATION	LT/RT	QUANTITY EACH
STA. 438+40.99	RT	1
TOTAL		1

SCHEDULE OF QUANTITIES
SHEET 3 OF 3
US 24 OVER LAMOINE RIVER
F.A.P. RTE 317 (US RTE 24)
SECTION 9RS-4, (10,11) RS-3; (10B-1) R
BROWN & SCHUYLER COUNTY