

CODE NO	SUMMARY OF QUANTITIES ITEM	UNIT	TOTAL	ROADWAY	STRUCTURE BOX	STRUCTURE BRIDGE
			100% STATE	1000	Y007	SFTY-2A
20100500	TREE REMOVAL, ACRES	ACRE	6.8	6.8		
20200100	EARTH EXCAVATION	CU YD	18541	18541		
20200200	ROCK EXCAVATION	CU YD	130	100	30	
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	14	14		
25000200	SEEDING, CLASS 2	ACRE	4.8	4.8		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	429	429		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	429	429		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	429	429		
25000700	AGRICULTURAL GROUND LIMESTONE	TON	9.5	9.5		
25100115	MULCH, METHOD 2	ACRE	4.8	4.8		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1000	1000		
28000400	PERIMETER EROSION BARRIER	FOOT	2600	2600		
28000500	INLET AND PIPE PROTECTION	EACH	3	3		
28001000	AGGREGATE EROSION CONTROL	TON	300	300		
28100809	STONE DUMPED RIPRAP, CLASS A5	TON	3455	3455		
28200200	FILTER FABRIC	SQ YD	4606	4606		
35800100	PREPARATION OF BASE	SQ YD	150	150		
35800200	AGGREGATE BASE REPAIR	TON	30	30		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	81	81		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	64	64		
40600300	AGGREGATE (PRIME COAT)	TON	325	325		
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	2,525	2525		
40600895	CONSTRUCTING TEST STRIP	EACH	2	2		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,796	1796		
40600990	TEMPORARY RAMP	SQ YD	163	163		
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	2,352	2352		
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	6,620	6620		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	341	341		
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	81,029	81029		
44200150	PAVEMENT PATCHING, TYPE IV, 12 INCH	SQ YD	200	200		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2,296	2296		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1,982	1982		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	523	523		
50102400	CONCRETE REMOVAL	CU YD	11.3		6.8	4.5
50105220	PIPE CULVERT REMOVAL	FOOT	105	105		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	4.5			4.5
50300300	PROTECTIVE COAT	SQ YD	21			21

UNIT	100% STATE	ROADWAY	STRUCTURE BOX	STRUCTURE BRIDGE	
		I000	Y007	SFTY-2A	
50800105	REINFORCEMENT BARS	POUND	49,470	49,470	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,920		1,330 590
52000110	PREFORMED JOINT STRIP SEAL	FOOT	35		35
54002020	EXPANSION BOLTS 3/4 INCH	EACH	48		48
54003000	CONCRETE BOX CULVERTS	CU YD	170		170
542D0223	PIPE CULVERTS, CLASS D, TYPE 1 18"	FOOT	218	218	
54390170	INSERTION CULVERT LINER 22"	FOOT	144	144	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	2,212.5	2,212.5	
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1(SPECIAL) TANGENT	EACH	8	8	
63200310	GUARDRAIL REMOVAL	FOOT	1,768	1,768	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	17	17	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	16	16	
67100100	MOBILIZATION	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1	1	
70101835	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 22	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8,935	8,935	
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	93,251	93,251	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	40	40	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	35	35	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	993	993	
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	1,310	1,310	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	40	40	
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	91,941	91,941	
* 78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B LINE 24" (INLAID -)	FOOT	35	35	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	373	373	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	35	35	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	8	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	373	373	
X0301424	SILICONE JOINT SEALER	FOOT	35		35
X0323665	RIP RAP SLURRY	SQ YD	1,500	1,500	
X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1	1	
Z0015500	DEBRIS REMOVAL	L SUM	1	1	
Z0041500	PLUG EXISTING CULVERTS	EACH	1	1	
Z0073400	TEMPORARY SUPPORT SYSTEM	EACH	2		2
Y020010	SLOPE STABILIZATION	L SUM	1		1

* SPECIALTY ITEM

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 550	SECTION (9,10)I; 11(RS-1,B)	COUNTY SCHUYLER	TOTAL SHEETS 86	SHEET NO. 3		
	672802-SHT-500.DGN	DRAWN -	REVISED -			SCALE:	SHEET NO. OF SHEETS STA. TO STA.	CONTRACT NO. 72802				
	PLOT SCALE = 100,0000 ' / IN.	CHECKED -	REVISED -			[ILLINOIS] FED. AID PROJECT						
	PLOT DATE = Apr-06-2010 12:00:34PM	DATE -	REVISED -									