

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES				100% STATE IL 100	SUMMARY OF QUANTITIES				100% STATE IL 100
SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE I000-2A	SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE I000-2A
CODE NO.	ITEM	UNIT	TOT. QUAN.		CODE NO.	ITEM	UNIT	TOT. QUAN.	
X0321203	TERMINAL MARKER POSTS	EACH	1	1	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,909	1,909
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	*78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	171,466	171,466
20400800	FURNISHED EXCAVATION	CU YD	22	22	*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	799	799
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	70	70	*78200410	GUARDRAIL MARKERS, TYPE A	EACH	121	121
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	73	73	*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	54	54
40600300	AGGREGATE (PRIME COAT)	TON	366	366	*78202000	TERMINAL MARKER - POST MOUNTED	EACH	1	1
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	7,432	7,432	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	813	813
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	3,986	3,986					
40600990	TEMPORARY RAMP	SO YD	138	138					
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	14,748	14,748					
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	471	471					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	1,390	1,390					
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, (VARIABLE DEPTH)	SO YD	175,848	175,848					
44200168	PAVEMENT PATCHING, TYPE II, 14 INCH	SO YD	280	280					
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SO YD	160	160					
44200174	PAVEMENT PATCHING, TYPE IV, 14 INCH	SO YD	25	25					
48101200	AGGREGATE SHOULDERS, TYPE B	TON	4,404	4,404					
48203100	HOT-MIX ASPHALT SHOULDERS	TON	216	216					
*63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	287.50	287.50		<i>*Specialty Items</i>			
*63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9 FOOT POSTS	FOOT	225	225					
*63000025	STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	12.5	12.5					
*63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1					
*63100167	TRAFFIC BARRIER TERMINAL TYPE 1 SPECIAL (TANGENT)	EACH	54	54					
63200310	GUARDRAIL REMOVAL	FOOT	2,687.5	2,687.5					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12					
67100100	MOBILIZATION	L SUM	1	1					
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	17,180	17,180					
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	171,466	171,466					

FILE NAME =	USER NAME = coxjw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
at:\pml\work\pml\dot\coxjw\dms25489\shstocq.dgn	DRAWN - JWC	REVISED -	558				PIKE	77	3	
PLOT SCALE = 100.0000 ' / IN.	CHECKED - RSC	REVISED -	CONTRACT NO. 72814							
PLOT DATE = Mar-18-2018 01:47:29PM	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
					SCALE:	SHEET NO. 1 OF 1 SHEETS		STA.	TO STA.	