

**PAINT PAVEMENT MARKING - LINE**

TYP. SEC. #	LOCATION	5"			
		YELLOW			WHITE
		DBL-SOLID ( FOOT)	SOLID ( FOOT)	SKIP-DASH ( FOOT)	SOLID ( FOOT)
	PEARL TO CALHOUN CNTY LINE. ( AREA B) F. A. P. 558 ( IL 100)				
(1-14)	STA. 639+76.40 TO STA. 754+40.09				22,927.38
(1-5)	STA. 639+76.40 TO STA. 653+90.00	2,827.20			
(5-6)	STA. 653+90.00 TO STA. 659+70.00		580.00		
(5-14)	STA. 653+90.00 TO STA. 754+40.09			2,512.52	
	( STA. EQN #5) STA. 754+40.09 ( BK) = STA. 558+85.13 ( BK)				
	( AREA C) F. A. P. 558 ( IL 100)				
(1-8)	STA. 558+85.13 TO STA. 410+77.63			3,701.88	29,615.00
(7-8)	STA. 417+70.00 TO STA. 410+77.63		692.37		
	( STA. EQN #6) STA. 410+77.63 ( BK) = STA. 410+61.80 ( AH)				
(9-11)	STA. 410+61.80 TO STA. 365+29.00				9,065.60
(9)	STA. 410+77.63 TO STA. 407+90.00			71.91	
(9)	STA. 410+61.80 TO STA. 407+90.00		271.80		
(9)	STA. 407+90.00 TO STA. 405+30.00	520.00			
(9-10)	STA. 405+30.00 TO STA. 395+50.00		980.00		
(9-11)	STA. 405+30.00 TO STA. 365+29.00			1,000.25	
(11)	STA. 374+20.00 TO STA. 365+29.00		891.00		
	SUBTRACT ( 21 SIDE ROADS ) ( APPROX. 32' EA)				-1,050.00
	SUBTOTAL ( B & C)	3,347.20	3,415.17	7,286.56	60,557.98
	SUBTOTAL ( A-C)	14,577.20	17,012.78	14,042.19	125,833.04
	PROJECT TOTAL				171,466

**TERMINAL MARKER POSTS**

LOCATION	QUANTITY ( EACH)
( AREA C) F. A. P. 558 ( IL 100) Sta. 435+28.53 LT	1
PROJECT TOTAL	1

**AGGREGATE SURFACE COURSE, TYPE B**

LOCATION	QUANTITY ( TON)
F. A. P. 558 ( IL 100) Quantity for HMA PE's and CE's	70
PROJECT TOTAL	70

• 118RS-2, 119RS-2, 123RS-3