

PAVEMENT SCHEDULE

TYP SEC #	LOCATION		LENGTH FOOT	PAVEMENT WIDTH FOOT	LEVELING BINDER THICKNESS INCH	HMA SURF THICKNESS INCH	HMA SURF REM. BUTT JOINT SQ YD	HMA SURF REMOVAL VAR DPTH SQ YD	HMA SURF REMOVAL 2 1/4" SQ YD	HMA SURF CSE, "C" N50 TON	LEV BINDER (MM), N50 TON	BIT MAT PRIME COAT TON	AGG PRIME COAT TON
	STATION TO STATION												
	DETROIT TO MILTON		-	-	-	-	-	-	-	-	-	-	-
	( AREA A )		-	-	-	-	-	-	-	-	-	-	-
	F. A. P. 757 ( IL 106 )		-	-	-	-	-	-	-	-	-	-	-
	STA. 370+70.20	TO STA. 370+90.20	20.00	26' to 31.50'	-	1.5	63.89	-	-	-	-	0.02	0.13
	STA. 370+90.20	TO STA. 371+05.20	15.00	26	0 to 0.75	-	-	-	-	0.91	-	-	-
	STA. 370+70.20	TO STA. 372+44.90	174.70	26	0.75	1.5	-	-	42.39	-	-	-	-
	STA. 370+90.20	TO STA. 372+24.90	134.70	26	0.75	-	389.13	-	-	-	0.15	0.78	-
	STA. 371+05.20	TO STA. 372+09.90	104.70	26	0.75	-	-	-	-	12.70	-	-	-
	STA. 372+09.90	TO STA. 372+24.90	15.00	26	0.75 to 0	-	-	-	-	0.91	-	-	-
	STA. 372+24.90	TO STA. 372+44.90	20.00	26' to 28.50'	-	-	60.56	-	-	-	0.02	0.12	-
	TR 14 ( AREA A )		-	-	-	-	-	-	-	-	-	-	-
	STA. 10+12.25	TO STA. 10+37.89	25.64	26	0.75	1.5	-	-	6.22	-	-	-	-
	STA. 10+12.25	TO STA. 10+32.89	20.64	26	0.75	-	-	59.63	-	-	0.02	0.12	-
	STA. 10+12.25	TO STA. 10+17.89	5.64	26	0.75	+	-	-	-	0.68	-	-	-
	STA. 10+17.89	TO STA. 10+32.89	15.00	26	0.75 to 0	+	-	-	-	0.91	-	-	-
	STA. 10+32.89	TO STA. 10+52.89	20.00	26	-	-	57.78	-	-	-	0.02	0.12	-
	Intersection of IL 106/IL 100 ( AREA A )		( Measured Using CADD )		-	-	-	-	-	-	-	-	-
	NW Quadrant		-	-	0.75	1.5	-	9.95	-	0.84	0.42	0.004	0.02
	NE Quadrant		-	-	0.75	1.5	-	16.44	-	1.38	0.69	0.01	0.03
	SW Quadrant		-	-	0.75	1.5	-	130.34	-	10.95	5.47	0.05	0.26
	SE Quadrant		-	-	0.75	1.5	-	123.29	-	10.36	5.18	0.05	0.25
	F. A. P. 558 ( IL 100 ) ( AREA A )		-	-	-	-	-	-	-	-	-	-	-
(1-6)	STA. 0+12.14	TO STA. 63+73.00	6,360.86	26	0.75	1.5	-	-	1,543.57	-	-	-	-
(1)	STA. 0+12.14	TO STA. 7+73.00	760.86	30	0.75	-	-	2,536.20	-	106.52	0.96	5.07	-
(2)	STA. 7+73.00	TO STA. 44+80.00	3,707.00	26	0.75	-	-	10,709.11	-	449.78	4.07	21.42	-
(3)	STA. 44+80.00	TO STA. 47+22.00	242.00	30	0.75	-	-	806.67	-	33.88	0.31	1.61	-
(4)	STA. 47+22.00	TO STA. 47+57.00	35.00	26	0.75	-	-	101.11	-	-	0.04	0.20	-
(4-10)	STA. 47+22.00	TO STA. 99+70.00	5,248.00	26	0.75	-	-	-	-	636.76	-	-	-
(4-6)	STA. 47+57.00	TO STA. 63+38.00	1,581.00	26	0.75	-	-	4,567.33	-	-	1.74	9.13	-
(6)	STA. 63+38.00	TO STA. 63+73.00	35.00	26	0.75	-	-	101.11	-	-	0.04	0.20	-
(7)	STA. 63+73.00	TO STA. 65+73.00	200.00	30	0.75	1.5	-	-	666.67	56.00	0.25	1.33	-
(8-15)	STA. 65+73.00	TO STA. 169+42.43	10,369.43	26	0.75	1.5	-	-	-	2,516.32	-	-	-
(8)	STA. 65+73.00	TO STA. 66+08.00	35.00	26	0.75	-	-	101.11	-	-	0.04	0.20	-
(8-10)	STA. 66+08.00	TO STA. 99+70.00	3,362.00	26	0.75	-	-	9,712.44	-	-	3.69	19.42	-
(11)	STA. 99+70.00	TO STA. 101+20.00	150.00	30	0.75	-	-	500.00	-	21.00	0.19	1.00	-
(12-15)	STA. 101+20.00	TO STA. 169+42.43	6,822.43	26	0.75	-	-	19,709.24	-	-	7.49	39.42	-
	( STA. EQN. #1 ) 169+42.43 ( BK ) = 171+72.56 ( AH )												
(16-29)	STA. 171+72.56	TO STA. 243+70.65	7,198.09	26	0.75	1.5	-	-	-	1,746.74	-	-	-
(16-19)	STA. 171+72.56	TO STA. 189+50.00	1,777.44	26	0.75	-	-	5,134.83	-	215.66	1.95	10.27	-
(20)	STA. 189+50.00	TO STA. 191+36.00	186.00	30	0.75	-	-	620.00	-	26.04	0.24	1.24	-
(21)	STA. 191+36.00	TO STA. 198+20.00	684.00	26	0.75	-	-	1,976.00	-	82.99	0.75	3.95	-
(22)	STA. 198+20.00	TO STA. 200+65.00	245.00	30	0.75	-	-	816.67	-	34.30	0.31	1.63	-
(23-24)	STA. 200+65.00	TO STA. 215+96.00	1,531.00	26	0.75	-	-	4,422.89	-	185.76	1.68	8.85	-
(25)	STA. 215+96.00	TO STA. 217+96.00	200.00	30	0.75	-	-	666.67	-	28.00	0.25	1.33	-
(26-29)	STA. 217+96.00	TO STA. 243+70.65	2,574.65	26	0.75	-	-	7,437.88	-	312.39	2.83	14.88	-
	( STA. EQN. #2 ) 243+70.65 ( BK ) = 245+88.11 ( AH )												
(30-31)	STA. 245+88.11	TO STA. 259+39.45	1,351.34	26	0.75	1.5	-	3,903.87	-	327.93	1.48	7.81	-
	( STA. EQN. #3 ) 259+39.45 ( BK ) = 255+19.60 ( AH )												

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. 9 OF 11 SHEETS STA. TO STA.

F.A.P. RTE. 558	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		PIKE	77	20
CONTRACT NO. 72814			ILLINOIS FED. AID PROJECT	

FILE NAME =	USER NAME = coxjw	DESIGNED - JWC	REVISED -
or\pwwork\pwwdot\coxjw\dms25489\shstsch.dgn		DRAWN - BSH	REVISED -
PLOT SCALE = 100.0000' / IN.		CHECKED - RSC	REVISED -
PLOT DATE = Mar-18-2010 01:44:46PM		DATE -	REVISED -