

**PAVEMENT SCHEDULE**

TYP SEC #	LOCATION		LENGTH FOOT	PAVEMENT WIDTH FOOT	LEVELING BINDER THICKNESS INCH	HMA SURF THICKNESS INCH	HMA SURF REM. BUTT JOINT SQ YD	HMA SURF REMOVAL VAR DPTH SQ YD	HMA SURF REMOVAL 2 1/4" SQ YD	HMA SURF CSE, "C" N50 TON	LEV BINDER (MM), N50 TON	BIT MAT PRIME COAT TON	AGG PRIME COAT TON	
	STATION TO STATION													
	F. A. P. 558 (IL 100) (AREA C)		-	-	-	-	-	-	-	-	-	-	-	
(1-8)	STA. 410+77.63	TO STA. 558+85.13	14,807.50	24	0.75	1.5	-	39,486.67	-	3,316.88	1,658.44	15.00	78.97	
	(STA. EQN. #6) 410+77.63 (AH) = 410+61.80 (BK)													
(9-10)	STA. 388+31.56	TO STA. 410+61.80	2,230.24	24	-	1.5	-	-	-	499.57	-	-	-	
(8-10)	STA. 388+51.56	TO STA. 410+61.80	2,210.24	24	0.75	-	-	5,893.97	-	-	-	2.24	11.79	
(8-10)	STA. 388+66.56	TO STA. 410+61.80	2,195.24	24	0.75	-	-	-	-	-	245.87	-	-	
(10)	STA. 388+51.56	TO STA. 388+66.56	15.00	24	0.75 to 0	-	-	-	-	-	0.84	-	-	
(10)	STA. 388+31.56	TO STA. 388+51.56	20.00	24	-	-	53.33	-	-	-	-	0.02	0.11	
	BRIDGE OMISSION #2 STA. 388+31.56 TO STA. 386+11.90													
(11)	STA. 385+91.90	TO STA. 386+11.90	20.00	24	-	-	53.33	-	-	-	-	0.02	0.11	
(11)	STA. 385+76.90	TO STA. 385+91.90	15.00	24	0 to 0.75	-	-	-	-	-	0.84	-	-	
(11)	STA. 365+49.00	TO STA. 385+91.90	2,042.90	24	0.75	1.5	-	5,447.73	-	457.61	-	2.07	10.90	
(11)	STA. 365+64.00	TO STA. 385+76.90	2,012.90	24	0.75	-	-	-	-	-	225.44	-	-	
(11)	STA. 365+49.00	TO STA. 365+64.00	15.00	24	0.75 to 0	-	-	-	-	-	0.84	-	-	
(11)	STA. 365+29.00	TO STA. 365+49.00	20.00	24	-	-	53.33	-	-	-	-	0.02	0.11	
	INCIDENTAL HMA SURF. HMA ENT & SIDE ROADS		-	-	-	-	-	3,425.59	-	-	-	4.88	6.85	
	HMA SHOULDERS (SQ YD)		-	-	1,474	-	-	-	-	-	-	0.56	2.95	
	SUB TOTAL C							3,585.59	50,828.37	0.00	4,274.06	2,132.27	24.82	111.78
	PROJECT TOTAL							3,986	175,848	1,390	14,748	7,432	73	366

FILE NAME =	USER NAME = leughlunr1	DESIGNED - JWC	REVISED -
ca:\pwwork\PM1007\LAUGHLINRL\dms28409\tech.dgn		DRAWN - BSH	REVISED -
PLOT SCALE = 100.0000' / IN.		CHECKED - RSC	REVISED -
PLOT DATE = May-07-2010 10:27:22AM		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

F.A.P. RTE. 558	SECTION -	COUNTY PIKE	TOTAL SHEETS 77	SHEET NO. 22
SCALE:			CONTRACT NO. 72814	
SHEET NO. 11 OF 11 SHEETS		STA.	TO STA.	
ILLINOIS FED. AID PROJECT				