

DESCRIPTION	STATION	FROM E. O. P. (FOOT)	WIDTH (FOOT)	THICKNESS (INCH)	AGGR. ENTR.		HMA ENTR.		SIDE RD.		TOTAL (TON)	Aggr. Shldr AREA (SQ FT)	
					AREA	TOTAL	AREA	TOTAL	AREA	TOTAL			
					(SQ FT)	(TON)	(SQ FT)	(TON)	(SQ FT)	(TON)			
PEARL TO CALHOUN CO. LINE													
(Hazel St.) LT	697+01.67 LT	9	40	1.875					441.00	5.15	5.15	165.00	
HMA CE (LT)	697+68.00 LT	9	36	1.875				405.00	4.73		4.73	153.00	
HMA CE (LT)	699+47.00 LT	9	50	1.875				531.00	6.20		6.20	195.00	
HMA CE (LT)	700+84.00 LT				VACANT (NO WORK)								
(East St.) LT	702+26.48 LT	9	33	1.875					378.00	4.41	4.41	144.00	
(Old Pearl Rd.) RT	702+29.01 RT	9	31	1.875					360.00	4.20	4.20	138.00	
BRIDGE OMISSION #1:	704+70.82												
S.N. 075-0140	707+00.59												
HMA (AGG) PE (w / MBT) (RT)	709+10.00 RT	7	12	1.875				409.50	4.78		4.78	203.79	
HMA (AGG) CE (LT)	709+45.00 LT	9	35	1.875				396.00	4.62		4.62	150.00	
(Pilot Bluff) RT	710+28.15 RT	9	22	1.875					279.00	3.26	3.26	111.00	
(Pilot Bluff) LT	710+36.39 LT	9	39	1.875					432.00	5.04	5.04	162.00	
HMA (AGG) PE (LT)	711+25.00 LT	7	30	1.875				259.00	3.02		3.02	123.00	
HMA (AGG) PE (RT)	715+69.00 RT	7	35	1.875				294.00	3.43		3.43	138.00	
(Unknown St.) LT	726+00.70 LT	9	44	1.875					477.00	5.57	5.57	177.00	
(Unknown St.) RT	726+17.54 RT	9	57	1.875					594.00	6.93	6.93	216.00	
HMA (AGG) PE (w / MBT) (RT)	739+43.00 RT	7	20	1.875				465.50	5.43		5.43	227.79	
HMA MBT (no entr) (LT)	739+50.00 LT	7	20	1.875				294.00	3.43		3.43	163.71	
AGG PE (RT)	740+36.00 RT	7	36	3.5	1,548.00	33.71					33.71	141.00	
HMA CE (LT) Power Plant Ent.	753+54.00 LT	9	70	1.875				711.00	8.30		8.30	255.00	
STA. EQUATION #5	754+40.09 (BK)												
(Sta. Increasing North)	558+85.13 (BK)												
	(AREA C)												
HMA (AGG) PE (LT)	550+00.00 LT	7	50	1.875				399.00	4.66		4.66	183.00	
HMA (AGG) PE (LT)	548+88.00 LT	7	38	1.875				315.00	3.68		3.68	147.00	
HMA (AGG) PE (RT)	543+86.00 RT	7	34	1.875				287.00	3.35		3.35	135.00	
HMA (AGG) PE (LT)	543+16.00 LT	7	37	1.875				308.00	3.59		3.59	144.00	
HMA (AGG) PE (RT)	536+08.00 RT	7	24	1.875				217.00	2.53		2.53	105.00	
(130th Ave.) LT	534+95.11 LT	9	37	1.875					414.00	4.83	4.83	156.00	
HMA (AGG) PE (RT)	533+52.00 RT				VACANT (NO WORK)								
HMA (AGG) PE (w / MBT) (LT)	508+66.00 LT	7	12	1.875				409.50	4.78		4.78	203.79	
AGG PE (LT)	508+08.00 LT				VACANT (NO WORK)								
HMA (AGG) PE (w / MBT) (LT)	497+78.00 LT	7	17	1.875				444.50	5.19		5.19	218.79	
HMA (AGG) PE (RT)	472+78.00 RT	7	33	1.875				280.00	3.27		3.27	132.00	
(118th Ave.) RT	470+75.73 RT	9	25	1.875					306.00	3.57	3.57	120.00	
HMA MBT (no entr) (LT)	470+65.00 LT	7	20	1.875				294.00	3.43		3.43	163.71	
Subtotal (pg 4) =					1,548.00	33.71	6,719.00	78.39	3,681.00	42.95	155.05	4,571.58	

• 118RS-2, 119RS-2, 123RS-3