

44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD
LOCATION	AREA (SQ. FT.)	AREA (SQ. YD.)
SIDEROADS		
15th Street	1779	197.7
Sangamon Ctr.	2914.9	323.9
19 th Street	3059.3	339.9
20 th Street	1185.5	131.7
Arrowhead Dr.	2061.7	229.1
21 st Street	1238.1	137.6
22 nd Street	1098.9	122.1
23 rd Street	1603.7	178.2
Cahokia	1362.3	151.4
24 th Street	1309.3	145.5
Piper Road	2930.2	325.6
Henley Road	4428.1	492.0
Farrington Road	1973.6	219.3
Hedge Lane Road	1213.2	134.8
Hastings Road	1969.8	218.9
TOTAL		3,347.5

44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	
STATION	LENGTH (FT)	WIDTH (FT)	AREA (SQ. YD.)
PEORIA ROAD			
52+30.82	116.4	53	727.4
51+14.44		60	
STA EQN 51+14.44(AH) = 100+98.45(BK)			
100+98.45	82.2	60	575.4
100+16.25		66	
NW QUAD			29.4
NE QUAD			70.6
99+57.52	115.3	59	801.0
98+42.18		67	
SW QUAD			145.6
SE QUAD			236.8
TOTAL			2,586.1

44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	
STATION	LENGTH (FT)	WIDTH (FT)	AREA (SQ. YD.)
MAINLINE			
8+26.56	73.4	55	450.8
9+00.	100.0	55.5	613.9
10+00.	400.0	55	2,433.3
14+00.	100.0	54.5	593.3
15+00.	100.0	52.3	562.8
15+50.	50.0	49	255.6
16+00.	100.0	43	472.2
17+00.	400.0	42	1,911.1
21+00.	50.0	44	244.4
21+50.	50.0	44	250.0
22+00.	50.0	46	269.4
22+50.	50.0	51	300.0
23+00.	50.0	57	325.0
23+50.	50.0	60	333.3
24+00.	100.0	60	666.7
25+00.	500.0	60	3,333.3
30+00.	500.0	60	3,333.3
35+00.	500.0	60	3,333.3
40+00.	500.0	60	3,333.3
45+00.	500.0	60	3,333.3
50+00.	500.0	60	3,333.3
55+00.	500.0	60	3,333.3
60+00.	500.0	60	3,333.3
65+00.	500.0	60	3,333.3
70+00.	393.5	60	2,623.3
73+93.5		60	
TOTAL			42,305.3

44200156	PAVEMENT PATCHING, TYPE II, 13 INCH					SQ YD
LOCATION	STATION	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)	TYPE	REMARKS
Mainline EBDL	21+00	6.0	11.0	7.33	II	Full Lane
Mainline EBPL	21+00	6.0	11.0	7.33	II	Full Lane
Mainline WBDL	21+00	6.0	11.0	7.33	II	Full Lane
Mainline WBPL	21+00	6.0	11.0	7.33	II	Full Lane
Mainline WBPL	26+50	20.0	6.0	13.33	II	Half Lane
Mainline EBDL	41+50	6.0	12.0	8.00	II	Full Lane
Mainline EBPL	41+50	6.0	12.0	8.00	II	Full Lane
Mainline WBDL	49+17	6.0	12.0	8.00	II	Full Lane
TOTAL				66.67		

60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH
LOCATION	STATION	EACH
Mainline	17+07	1.0
Mainline	27+54	1.0
Mainline	38+04	1.0
Mainline	49+17	1.0
Mainline	51+00	1.0
Mainline	55+00	1.0
Hedge Lane Road	100+35	1.0
Peoria Road	100+75	1.0
TOTAL		8.0

56109210	WATER VALVES TO BE ADJUSTED	EACH
LOCATION	STATION	EACH
Sangamon Ctr.	27+67	1.0
Peoria Road	51+80	1.0
Peoria Road	51+75	1.0
TOTAL		1.0