

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-12	CHRISTIAN	284	26
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

FINAL STRIPING / DELINEATOR SCHEDULE CONTINUED

LOCATION			78001120		78001150	X7800620 & X7030070		X7800600	X7800630	X7800650	X7800680	78004200	78004220	78004230		78004250	78004280	78100100	63500105				
			PAINT PAVEMENT MARKING					GROOVED URETHANE PAVEMENT MARKING		URETHANE PAVEMENT MARKING				PERFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID						RAISED REFLECTIVE PAVEMENT MARKER	DELINEATORS		
			LINE 5"		LINE 12"	LINE 5"		LETTERS & SYMBOLS	LINE 6"	LINE 12"	LINE 24"	LETTERS & SYMBOLS	LINE 5"	LINE 6"		LINE 12"	LINE 24"	WAY CRYSTAL	SINGLE WHITE		DOUBLE WHITE	DOUBLE AMBER	
			WHITE SOLID FOOT	YELLOW SOLID FOOT	YELLOW SOLID FOOT	WHITE SOLID FOOT	YELLOW SOLID FOOT		WHITE SOLID FOOT	WHITE SOLID FOOT	WHITE SOLID FOOT		WHITE SKIP FOOT	WHITE SOLID FOOT	WHITE SKIP FOOT	YELLOW SOLID FOOT	WHITE SOLID FOOT		EACH	EACH	EACH		
FAP 322	783+00 to 798+00	NB	OUTSIDE			60.0																	
			☺										75.0						4				
			MEDIAN			395.0																	
	798+00 to 813+00	SB	☺										375.0						19				
TR 229A	17+78.6 to 20+00	LT		199.1																			
			☺																				
		RT			240.9																	23.4	
	20+00 to 22+16.3	LT		235.8																			
			☺																				
		RT		194.1																		22.8	
ASSUMPTION SOUTH CONNECTOR	2+50 to 6+00	LT		371.1																			
			☺																			22.0	
		RT		326.0																			
	6+00 to 495+00	LT		818.9																			
			☺																				
		RT		875.1																			
ILLINOIS ST	44+70 to 50+82	☺				821.7 **	31.2	101.0	202.9	42.5													
TR 209	50+82 to 55+00	LT		473.0																			
			☺																			26.1	
		RT		392.0		151.2																	
CH 6	47+58.2 to 50+00	LT		210.0																			
			☺																			16.4	
		RT		261.8																			
	50+00 to 52+41.8	LT		261.8																			
			☺																			16.4	
		RT		210.0																			
TR 193	12+53.8 to 15+13.6	LT		259.8																			
			☺																			519.6	
		RT		195.2																			
	17+57.8 to 20+00	LT		210.7																			
			☺																			15.2	
		RT		262.5																			
	20+00 to 22+42.2	LT		262.5																			
			☺																			14.9	
		RT		210.7																			
TR 306	8+55 to 10+00	LT		110.2																			
			☺																			20.0	
		RT		110.2																			
SUB-TOTALS:				6,964	5,774	151	45,063	48,704	32	101	203	43	1,186	11,365	6,663	380	916	202	731	93	54	72	
TOTALS:				12,738 *		151	93,767		32	101	203	43	1,186	11,365	7,043		916	202	731	219			

\* - SEE STAGE CONSTRUCTION PAVEMENT MARKING SCHEDULE FOR ADDITIONAL QUANTITIES  
 \*\* - URETHANE PAVEMENT MARKING ONLY (NO GROOVING)

LIGHTING SCHEDULE

PAY ITEM	DESCRIPTION	UNIT	CROSSOVER "A" / TR 229A INTERSECTION	ASSUMPTION SOUTH CON. INTERSECTION	ILLINOIS ST/ TR 209 INTERSECTION	CH 6 INTERSECTION	TR 193 INTERSECTION	PROJECT TOTAL
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1	1	1	1	5
83057280	LIGHT POLE, WOOD, 50 FOOT, CLASS 3	EACH	9					9
81021330	CONDUIT PUSHED, 2" DIA., PVC	FOOT	265	200	265	270	270	1270
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1504	1150	1345	1340	1644	6983
81603000	UNIT DUCT, 600V, 2-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	985				1025	2010
81603010	UNIT DUCT, 600V, 2-1C NO.10, 1/C NO.10 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT		1445	1715	1715	919	5794
81603065	UNIT DUCT, 600V, 2-1C NO.2, 1/C NO.2 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	1184					1184
81800200	AERIAL CABLE, 2-1/C NO. 4 WITH MESSENGER WIRE	FOOT	1655					1655
82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	9					9
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	10	9	10	10	10	49
82500300	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 30AMP	EACH	1	1	1	1	1	4
82500310	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 60AMP	EACH	1					1
83003600	LIGHT POLE, ALUMINUM, 45 FT. 15 FT. DAVIT ARM	EACH	10	9	10	10	10	49
83600355	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 6"	EACH	10	9	10	10	10	49
83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	40	36	40	40	40	196

REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE

LOCATION	84200600 NUMBER
US 51 771+50 LT	1
US 51 773+00 LT	1
US 51 774+50 LT	1
US 51 776+00 LT	1
US 51 777+50 LT	1
US 51 777+50 RT	1
US 51 779+00 RT	1
US 51 781+50 RT	1
TOTAL:	8

REVISED SHEET

REVISIONS	
NAME	DATE
SEB	5/24/06

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF QUANTITIES  
 FINAL STRIPING & LIGHTING  
 FAP 322 (US 51)  
 SECTION 11-12  
 CHRISTIAN COUNTY

SCALE: NONE DRAWN BY SEB  
 DATE: 8/22/06 CHECKED BY TLD

5-25-10

5/24/2008