72932

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-12	CHRISTIAN	284	6
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SUMMARY OF QUANTITIES

CODE NO.	ITEM	SP. PROV.	UNIT	80% FED. 20% STATE TOTAL QUANTITIES	80 % FEDERAL 20 % STATE CONSTRUCTION AND SAFETY TYPE CODE I000-2A ROADWAY	Y030-1E LIGHTING
40701956	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 3/4"	•	SQ YD	125983	125983	
40702700	FURNISH PROFILOGRAPH		L SUM	1	1	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING		TON	33	33	
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)		SQ YD	2499	2499	
42001300	PROTECTIVE COAT		SQ YD	2499	2499	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH		SQ YD	459	459	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH		SQ FT	142	142	
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH		SQ FT	2754	2754	
42400800	DETECTABLE WARNINGS		SQ FT	32	32	
44000100	PAVEMENT REMOVAL	•	SQ YD	32978	32978	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	•	SQ YD	5288	5288	
44000200	DRIVEWAY PAVEMENT REMOVAL	•	SQ YD	498	498	
44000500	COMBINATION CURB AND GUTTER REMOVAL	•	FOOT	962	962	
44000600	SIDEWALK REMOVAL	•	SQ FT	3153	3153	
44004250	PAVED SHOULDER REMOVAL	•	SQ YD	553	553	
48101200	AGGREGATE SHOULDERS, TYPE B		TON	11718	11718	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	•	SQ YD	67658	67658	
48203034	HOT-MIX ASPHALT SHOULDERS, 9¼"	•	SQ YD	2563	2563	
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	•	EACH	1	1	
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	•	EACH	1	1	
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	•	EACH	1	1	
50105220	PIPE CULVERT REMOVAL	•	FOOT	888	888	
50200100	STRUCTURE EXCAVATION		CU YD	763	763	
50800105	REINFORCEMENT BARS		POUND	1880	1880	
54001001	BOX CULVERT END SECTION, CULVERT NO.1		EACH	2	2	
54001002	BOX CULVERT END SECTION, CULVERT NO.2		EACH	2	2	
54010603	PRECAST CONCRETE BOX CULVERT 6' X 3'		FOOT	160	160	

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
SHEET 3 OF 9
FAP 322 (US 51)
SECTION 11-12
CHRISTIAN COUNTY

SCALE: NONE DRAWN BY SEB
DATE 8/22/06 CHECKED BY TLD

Mar-15-2010 09:21:24AM
$FILE$