

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-12	CHRISTIAN	284	11
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

80% FEDERAL 20% STATE
CONSTRUCTION AND SAFETY TYPE CODE

CODE NO.	ITEM	SP. PROV.	UNIT	80% FED. 20% STATE TOTAL QUANTITIES	CONSTRUCTION AND SAFETY TYPE CODE										
					I000-2A ROADWAY	Y030-1E LIGHTING									
80400100	ELECTRIC SERVICE INSTALLATION		EACH	5		5									
81021330	CONDUIT PUSHED, 2" DIA., PVC		FOOT	1270		1270									
81603000	UNIT DUCT, 600V, 2-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE		FOOT	2055		2055									
81603010	UNIT DUCT, 600V, 2-1C NO.10, 1/C NO.10 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE		FOOT	5940		5940									
81603065	UNIT DUCT, 600V, 2-1C NO.2, 1/C NO.2 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE		FOOT	1220		1220									
81800200	AERIAL CABLE, 2-1/C NO. 4 WITH MESSENGER WIRE		FOOT	1655		1655									
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK		FOOT	7265		7265									
82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT		EACH	67		67									
82500300	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 30AMP		EACH	4		4									
82500310	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 60AMP		EACH	1		1									
83055300	LIGHT POLE, 45 FT. M.H., TENON MOUNT		EACH	40		40									
83055310	LIGHT POLE, 45 FT. M.H., TENON MOUNT - TWIN		EACH	9		9									
83057280	LIGHT POLE, WOOD, 50 FOOT, CLASS 3		EACH	9		9									
83600355	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 6'		EACH	40		40									
83600357	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 8'		EACH	9		9									
83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN		EACH	196		196									
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE		EACH	8		8									
Z0005010	HOT-MIX ASPHALT FOR PATCHING POTHOLES (COLD MIX)		• TON	75	75										
Z0007601	BUILDING REMOVAL NO. 1		• L SUM	1	1										
Z0007602	BUILDING REMOVAL NO. 2		• L SUM	1	1										
Z0007603	BUILDING REMOVAL NO. 3		• L SUM	1	1										
Z0007604	BUILDING REMOVAL NO. 4		• L SUM	1	1										
Z0007605	BUILDING REMOVAL NO. 5		• L SUM	1	1										
Z0007606	BUILDING REMOVAL NO. 6		• L SUM	1	1										
Z0013798	CONSTRUCTION LAYOUT		• L SUM	1	1										
Z0038506	REMOVE PERMANENT BARRICADES		• L SUM	1	1										
Z0054530	ROCK FILL - SUBGRADE		• TON	2000	2000										

* SPECIALTY ITEM

* SPECIALTY ITEM

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
SHEET 8 OF 9
FAP 322 (US 51)
SECTION 11-12
CHRISTIAN COUNTY

SCALE: NONE
DATE 8/22/06

DRAWN BY SEB
CHECKED BY TLD