

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-12	CHRISTIAN	284	14
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PAVEMENT, SIDEWALK, AND CURB & GUTTER REMOVAL SCHEDULE

LOCATION	4400100		4400200	4400500	4400600	44004250
	PAVEMENT REMOVAL	DRIVEWAY PAVEMENT REMOVAL	COMB. CURB AND GUTTER REMOVAL	SIDEWALK REMOVAL	PAVED SHOULDER REMOVAL	
	SQ YD	SQ YD	FOOT	SQ FT	SQ YD	
EXISTING REMOVAL						
FAP 322	429+77 to 558+00					
	558+00 to 573+00	138.3		56		
	573+00 to 588+00	4163.7				
	588+00 to 603+00	4158.9				
	753+00 to 768+00	3752.2				
	768+00 to 783+00	3476.4				
	783+00 to 783+60	6308.2				
	783+60 to 786+95	40.0				
	788+17 to 793+12				223.3	
EX US 51	485+00 to 495+00					330.0
	606+20 to 610+00	2766.0				
	610+00 to 622+00	1164.8				
ILLINOIS ST	44+70.0 to 49+51.0	3675.4				
	LT	1489.4	409.3	481.0	3045	
	RT		88.6	481.0	52	
STAGE CONSTRUCTION REMOVAL						
	TEMPORARY ACCESS FOR TR 229A	273.8				
	CROSSOVER "B"	1570.4				
TOTALS:		32,978	498	962	3,153	553

PIPE CULVERT REMOVAL

LOCATION	DESCRIPTION	PIPE CULVERT REMOVAL FOOT
FAP 322	561+50 19' LT 24" CMP	38
	567+91 78' LT 18" CMP	29
	571+22 78' LT 18" CMP	32
	574+77 91' LT 18" CMP	36
	574+82 8' LT 18" CMP	36
	581+95 21' LT 15" CMP	33
	587+96 79' LT 15" CMP	34
	594+59 93' LT 15" CMP	41
	595+43 48' LT 15" CMP	27
	723+00 C 18" PIPE	36
	758+91 C 18" PIPE	36
	759+20 97' LT 30" PIPE	60
	759+38 156' LT 18" PIPE	38
	767+37 10' LT 30" PIPE	50
	768+00 6.3' LT 12" PIPE	22
	772+04 16' RT 18" PIPE	46
TR 229A	20+78 15' RT 15" CMP	29
TR 209	54+52 17' RT 12" CMP	60
CH 6	49+20 16' RT 12" CMP	20
	53+56 15' RT 15" CMP	27
TR 193	54+80 16' RT 15" CMP	25
EX US 51	14+25 C 54" CMP	30
	475+02 28' RT 15" CMP	33
	613+88 58' LT 18" CMP	70
TOTALS:		888

REMOVAL OF EXISTING STRUCTURES

LOCATION	SIZE	STRUCTURE *	PAY ITEM
FAP 322	559+25 LT 4' W x 2' H x 45' L	1	50100300
TR 229A	16+17 RT 15" W x 6" H x 14' L	2	50100400
EX US 51	607+55 8' W x 4' H x 75' L	3	50100500

REMOVING INLETS

LOCATION	REMOVING INLETS EACH
FAP 322	768+00 6' LT 1
	46+93.5 19.5' LT 1
ILLINOIS ST	46+93.5 20.6' RT 1
	49+29.7 23.6' RT 1
TOTALS:	4

SEALING ABANDONED WATER WELLS

LOCATION	SEALING ABANDONED WATER WELLS EACH
FAP 322	594+46 88' RT 1
TOTALS:	1

DEWATERING STRUCTURE NO. 1

LOCATION	DEWATERING STRUCTURE NO. 1 EACH
FAP 322	559+28 LT 1
TOTAL:	1

STRIPING REMOVAL SCHEDULE

LOCATION / DESCRIPTION	78300100		78300200
	PAVEMENT MARKING REMOVAL FT	PAVEMENT MARKING REMOVAL SQ FT	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL EACH
(EXISTING) EX US 51	423+70.0 to 430+50.0		
	LT	680.0	
	C	170.0	10
	RT	680.0	
FAP 322 SB LANE	788+87.0 to 793+12.0	425.0	
	791+00.0 to 813+00.0	550.0	29
TR 193	17+57.8 to 22+42.2		
	LT	484.4	
	C	120.0	
	RT	484.4	
(STAGING) CROSSOVER "B"	11+60.0 to 12+46.1	187.0	
	17+67.6 to 21+41.1	346.5	
FAP 322 SB LANE	793+11.8 to 813+00.0	1614.7	62.4
	LT 5"		
	6"	435.0	
TEMPORARY RAISED MARKERS			926
SUBTOTALS:	6,177	62.4	965
TOTALS:	2636.2		965

* - WIDTH ESTIMATED TO BE 5"

TREE REMOVAL SCHEDULE

LOCATION	20100110		20100210
	TREE REMOVAL (6 TO 15 UNITS DIAMETER) UNIT	TREE REMOVAL (OVER 15 UNITS DIAMETER) SQ YD	
FAP 322	570+86.3 98.0' LT	30	
	594+30.4 14.3' RT	16	
	594+53.7 16.6' RT	13	
	594+58.6 68.9' RT	14	
	594+96.2 2.2' RT	15	
	595+27.1 43.8' RT	13	
	595+27.6 4.9' RT	36	
TOTALS:	55	82	

REMOVE RIGHT-OF-WAY MARKERS

LOCATION	REMOVE RIGHT-OF-WAY MARKERS EACH
FAP 322	574+51.3 10.6' RT 1
	575+03.1 10.0' RT 1
TOTALS:	2

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT

LOCATION	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT SQ YD
EX US 51	423+06.98 to 423+26.98 55.5
TOTALS:	56

HOT-MIX ASPHALT SURFACE REMOVAL 2"

LOCATION	HOT-MIX ASPHALT SURFACE REMOVAL 2" SQ YD
FAP 322	775+00.0 to 783+60.0 RT 2293.3
	788+00.0 to 788+10.0 LT 2714.4
EX US 51	473+74.0 to 474+75.0 280.3
TOTALS:	5,288

REMOVE PERMANENT BARRICADES

LOCATION	REMOVE PERMANENT BARRICADES NUMBER
FE STA 714+45	8
FE STA 723+00	8
FE STA 772+04	4
FE STA 758+80	8
TR 193 INTERSECTION	28
TOTALS:	56*

*-PROVIDED FOR INFORMATION ONLY. TO BE PAID FOR AS A LUMP SUM. NO ADDITIONAL COMPENSTATION WILL BE GIVEN FOR THE REMOVAL OF ADDITIONAL BARRICADES.

STORM SEWER REMOVAL 15"

LOCATION	STORM SEWER REMOVAL 15" FOOT
ILLINOIS ST	46+93.5 LT 3
	46+93.5 CL 30
TOTAL:	33

BUILDING REMOVAL SCHEDULE

STATION	SIDE	BUILDING *	DESCRIPTION	PAY ITEM
574+11	70' RT	1	METAL GRAIN BIN	20007601
574+11	90' RT	2	METAL GRAIN BIN	20007602
574+11	117' RT	3	METAL GRAIN BIN	20007603
595+00	RT	4	RESIDENCE & MISC.	20007604
602+53	134' RT	5	WOOD BARN	20007605
658+15	167' RT	6	METAL MACHINE SHED	20007606

CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED

LOCATION	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED FOOT
ILLINOIS ST	46+01 to 47+77 LT 176
TOTAL:	176

REVISIONS	
NAME	DATE
PVMT MARK REM	3/30/2010

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
REMOVAL ITEMS
FAP 322 (US 51)
SECTION 11-12
CHRISTIAN COUNTY
 SCALE: NONE DRAWN BY: SEB
 DATE: 8/22/06 CHECKED BY: TLD