

SIDE ROAD PAVEMENT SCHEDULE

ROUTE	LOCATION	35100500	35100900	40300200	40300400	40300500	40300600	48101200
		AGGREGATE BASE COURSE, TYPE A 6"	AGGREGATE BASE COURSE, TYPE A 10"	BITUMINOUS MATERIALS (PRIME COAT)	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	COVER COAT AGGREGATE	SEAL COAT AGGREGATE	AGGREGATE SHOULDERS, TYPE B
		SQ YD	SQ YD	TON	TON	TON	TON	TON
TR 229A	15+00.0 to 17+78.6		742.9	1.02	3.07	14.37	7.2	61.5
	22+16.3 to 24+75.0		689.9	0.95	2.85	13.35	6.7	58.2
SERVICE DRIVE 614	485+00.0 to 4+21.9		1174.9	1.71	5.12	23.95	12.0	119.9
CH 6	46+25.6 to 47+58.2		353.6	0.40	1.21	5.66	2.8	28.2
	52+41.8 to 54+60.0		581.9	0.82	2.45	11.48	5.7	47.2
TR 193	15+13.6 to 16+25.0		297.1	0.42	1.27	5.94	3.0	29.8
PD 574	45+90.0 to 50+00.0	819.8		1.17	2.34	8.20	8.20	
TOTALS:		820	3,840	6.5	18.3	83	46	345

*- SEE BIT CONC PAVEMENT SCHEDULE FOR ADDITIONAL "AGGREGATE SHOULDER, TYPE B"

ENTRANCE SCHEDULE

ROUTE	STATION	SIDE	TYPE	WIDTH FT	40200100	40800050	42300400
					AGGREGATE SURF COURSE, TYPE A 6"	INCIDENTAL HOT-MIX ASPHALT SURF	PCC DRIVEWAY PAVEMENT 8"
					TON	TON	SQ YD
FAP 322 (US 51)							
	561+45.0	RT	FE	24	148.9		
	567+91.0	LT	FE	24	46.8		
	589+10.0	RT	FE	24	65.6		
	595+04.5	LT	PD 595	18	174.6		
	595+04.5	RT	PE	16	47.2		
	602+60.0	RT	FE	24	68.3		
	614+65.0	RT	FE	24	52.0		
	626+00.0	RT	FE	24	49.2		
	637+00.0	RT	FE	24	60.4		
	637+00.0	LT	FE	24	61.3		
	647+00.0	RT	FE	24	94.8		
	714+45.0	LT	FE	24	38.1		
	714+45.0	RT	FE	24	45.9		
	723+00.0	LT	FE	24	21.0		
	723+00.0	RT	FE	24	22.5		
	758+80.0	RT	FE	24	34.8		
	772+04.0	RT	FE	24	30.6		
TR 229A							
	15+25.0	RT	FE	24	25.2		
	16+00.0	LT	FE	24	24.9		
	24+00.0	LT	FE	24	24.9		
	24+00.0	RT	FE	24	26.6		
ASSUMPTION SOUTH CONNECTOR							
	493+70.0	RT	FE	24	40.1		
ILLINOIS STREET							
	46+14.3	RT	CE	35.9			92.9
	46+21.3	LT	CE	36			88.2
	48+09.9	LT	MATCH EX		8.8		
	48+66.0	LT	CE	35			277.9
	54+50.0	LT	FE	24	27.6		
	54+53.1	RT	CE	45	23.0	32.2	
CH 6							
	46+35.0	RT	FE	24	34.3		
	53+57.5	RT	PE	16	25.5		
	54+00.0	LT	FE	24	34.3		
	54+40.0	RT	FE	24	34.5		
TR 193							
	15+00.0	LT	FE	24	35.3		
	15+00.0	RT	FE	24	27.5		
EX US 51							
	475+90.0	RT	FE	24	48.7		
	605+50.0	LT	FE	24	45.8		
TOTALS:					1,549	33	459

RIPRAP SCHEDULE

LOCATION	28100725	28100707	28200200
	STONE DUMPED RIPRAP, CLASS B3	STONE DUMPED RIPRAP, CLASS A4	FILTER FABRIC
	SQ YD	SQ YD	SQ YD
FAP 322			
	559+28 LT		58.3
	559+28 RT		58.7
	559+36 LT to 561+03 LT	241.9	
	565+55 RT	21.4	
	573+85 LT to 18+50 RT (TR 229A)	164.7	
	573+85 RT to 21+45 RT (TR 229A)	149.5	
	18+50 LT (TR 229A) to 576+05 LT	193.6	
	21+45 RT (TR 229A) to 576+05 RT	187.8	
	594+05 RT	12.9	
	606+55 RT		60.0
	613+60 LT to 4+00 LT (A.S.C.)	172.6	
	4+00 LT (A.S.C.) to 616+00 LT	199.6	
	658+45 LT to 49+40 RT (ILL. ST)	148.1	
	658+40 RT to 658+55 RT	21.7	
	49+40 LT (ILL. ST.) to 660+50 LT	112.5	
	52+25 RT (TR 209) to 660+50 RT	118.0	
	671+25 RT	15.2	
	673+07 RT		53.9
	676+10 RT	15.1	
	685+60 LT to 48+20 RT (CH 6)	323.0	
	685+60 RT to 51+80 RT (CH 6)	193.8	
	48+20 LT (CH 6) to 688+80 LT	211.9	
	51+80 LT (CH 6) to 688+30 RT	253.8	
	773+00 RT	28.9	
	7+90 LT to 3+90 RT (SD 614)	62.7	
TR 209			
	53+50 RT	14.4	
	53+50 LT	14.4	
ASSUMPTION SOUTH CONNECTOR	12+53 RT to 606+28 LT (EX US 51)		437.6
TR 193	606+37 RT (EX US 51) to 14+77 RT	243.7	
TOTALS:		3,121	669

PORTLAND CEMENT CONCRETE SIDEWALK

LOCATION		42400100	42400410	42400800
		4 INCH	8 INCH	DET. WARNINGS
		SQ FT	SQ FT	SQ FT
ILLINOIS ST				
	45+80.4 RT	56.4		11.4
	45+81.1 LT	53.5		12.2
	45+97.6 LT	31.9		8.2
	46+42.3 to 48+36.6 LT		2753.4	
TOTALS:		142	2,754	32

MATERIAL TRANSFER DEVICE

ITEM	TON
POLY HOT-MIX ASPHALT SURFACE, MIX D, N 70	561
HOT-MIX ASPHALT PAVEMENT (FD), 13 3/4" - 2 LIFTS	25006
TOTALS:	25,567

MAINLINE SURFACE COURSE ONLY (NO TURN LANES)

TEMPORARY RAMP

LOCATION		40600990
		SQ YD
FAP 322		
	734+78.29 RT	88.9
	749+00.36 RT	88.9
	775+00.00 RT	88.9
EX US 51	423+06.98	18.5
ILLINOIS ST	50+21	99.5
TOTALS:		385

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 PAVING, ENTRANCES, RIPRAP
 FAP 322 (US 51)
 SECTION 11-12
 CHRISTIAN COUNTY

SCALE: NONE
 DATE: 8/22/06

DRAWN BY: SEB
 CHECKED BY: TLD

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-12	CHRISTIAN	284	16
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		