

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-12	CHRISTIAN	284	18
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

DRAINAGE SCHEDULE

STRUCTURE NUMBER	LOCATION	DESCRIPTION	PRECAST CONCRETE BOX CULVERTS		STRUCTURE EXCAVATION	INLETS			PIPE CULVERTS														REINFORCED CONCRETE PIPE TEES			END SECTIONS		GRATING FOR CONCRETE END SECTION, 24" STD 542311	MH TYPE A, 5' Ø WITH MED INLET STD 604101	TRENCH BACKFILL	GRANULAR CULVERT BACKFILL													
			6' x 3'	8' x 2'		BOX STD 542501	BOX STD 542506	MED INLET STD 604101	TYPE 1							TYPE 2							24" RISER	36" RISER	48" RISER	END SECTIONS																		
			FT	FT		EACH	EACH	EACH	CLASS D							CLASS A							CU YD	LB	EACH	EACH	CU YD					CU YD												
			FAP 322 (US 51)																																									
			FT	FT		CU YD	EACH	EACH	EACH	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT					FT	EACH	EACH	EACH	CU YD	LB	EACH	EACH	CU YD	CU YD			
1	555+50	RT	PIPE CULVERT																																16.9									
2	559+28	CL	BOX CULVERT	160	421.4																					2									161.9									
3	561+45	RT	PIPE CULVERT									82																																
4	565+55	RT	INLET BOX, PIPE CULVERT						1																		1								1.9									
5	567+91	LT	PIPE CULVERT											72																														
6	576+00	RT	INLET BOX, PIPE CULVERT			1																						1							6.4									
7	589+10	RT	PIPE CULVERT																																									
8	594+05	RT	MANHOLE, PIPE CULVERT																															1	45.7									
9	595+21.6	RT	PIPE CULVERT																																									
10	602+60	RT	PIPE CULVERT																																									
11	606+09	CL	MEDIAN INLET, DOUBLE PIPE CULVERT						1																										181.2									
12	613+60	RT	MEDIAN INLET, PIPE CULVERT						1																										19.1									
13	614+65	RT	PIPE CULVERT																																									
14	622+51	RT	INLET BOX, PIPE CULVERT						1																																			
15	626+00	RT	PIPE CULVERT																																									
16	638+00	RT	MEDIAN INLET, PIPE CULVERT						1																																			
17	647+00	RT	PIPE CULVERT																																									
18	658+50	RT	MANHOLE, PIPE CULVERT																																									
19	671+25	RT	INLET BOX, PIPE CULVERT																																									
20	673+24	CL	BOX CULVERT	160	341.9																																							
21	676+10	RT	INLET BOX, PIPE CULVERT																																2.6									
22	686+00	CL	PIPE CULVERT																																64.4									
23	688+37	CL	MEDIAN INLET, PIPE CULVERT						1																										45.3									
24	714+45	RT	PIPE CULVERT																																									
25	714+45	LT	PIPE CULVERT																																									
26	723+00	LT	PIPE CULVERT																																									
27	723+00	RT	PIPE CULVERT																																									
28	758+80	RT	PIPE CULVERT																																									
29	767+50	LT	MANHOLE, PIPE CULVERT																																									
30	772+04	RT	PIPE CULVERT																																									
31	773+00	RT	INLET BOX, PIPE CULVERT																																									
SUB-TOTALS:			160	160	763	2	3	4	0	0	286	172	90	8	0	0	356	0	0	0	0	0	0	0	78	8	416	318	350	2	1	1	2	2	12	4	0	0	18.6	40	2	3	471.8	316

FILE# 08-15-2018 09:45:16 AM

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES DRAINAGE FAP 322 (US 51) SECTION 11-12 CHRISTIAN COUNTY
NAME	DATE	
SCALE:	NONE	DRAWN BY: EBB
DATE:	8/22/06	CHECKED BY: SEB