

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-12	CHRISTIAN	284	21
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PIPE UNDERDRAINS 4" SCHEDULE

60107600		60108100		60100060		78001110	
NORTHBOUND OUTSIDE EDGE OF PAVEMENT							
PIPE UNDERDRAINS 4"			PIPE UNDERDRAINS 4" (SPECIAL)			CONCRETE HEADWALL FOR PIPE DRAINS	PAINT PVT MARKING 4"
BEGINNING STATION	ENDING STATION	LENGTH	OUTLET STATION	LENGTH	CONNECT TO STRUCT NO.		
		FOOT		FOOT		EACH	FOOT
555+00	560+00	500.0	560+00	16.4		1	2.0
560+00	563+10	310.0	563+10	16.4		1	2.0
563+10	565+55	245.0	565+55		4		
565+55	567+50	195.0	565+55		4		
567+50	570+00	250.0	567+50	16.4		1	2.0
570+00	573+97	397.0	570+00	11.2		1	2.0
576+00	581+00	500.0	576+00		6		
581+00	586+00	500.0	581+00	16.4		1	2.0
586+00	589+67	367.0	586+00	16.4		1	2.0
589+67	592+17	250.0	592+17	16.2		1	2.0
592+17	594+67	250.0	594+67	16.2		1	2.0
594+67	598+50	383.0	598+50	16.2		1	2.0
598+50	603+50	500.0	603+50	16.2		1	2.0
603+50	607+50	400.0	607+50	16.2		1	2.0
607+50	612+50	500.0	612+50	16.4		1	2.0
612+50	617+50	500.0	617+50	16.4		1	2.0
617+50	620+00	250.0	620+00	16.4		1	2.0
620+00	622+51	251.0	622+51		14		
622+51	625+00	249.0	622+51		14		
625+00	627+50	250.0	625+00	16.4		1	2.0
627+50	632+50	500.0	627+50	16.4		1	2.0
632+50	637+50	500.0	632+50	16.4		1	2.0
637+50	642+50	500.0	637+50	16.4		1	2.0
642+50	645+10	260.0	642+50	16.4		1	2.0
645+10	647+54	249.0	645+10	16.4		1	2.0
647+54	650+00	246.0	650+00	13.1		1	2.0
650+00	652+50	250.0	652+50	13.7		1	2.0
652+50	655+50	300.0	655+50	9.2		1	2.0
655+50	658+50	300.0	658+50	9.5		1	2.0
658+50	665+80	517.0	665+80	13.5		1	2.0
665+80	671+00	520.0	671+00	13.5		1	2.0
671+00	673+50	250.0	673+50	15.6		1	2.0
673+50	676+10	260.0	676+10		21		
676+10	678+60	250.0	678+60		21		
678+60	682+50	390.0	682+50	14.1		1	2.0
682+50	686+51	401.0	686+51	9.2		1	2.0
686+51	692+50	413.0	688+37	13.4		1	2.0
688+37	695+00	250.0	692+50	13.7		1	2.0
692+50	697+36	236.0	695+00	13.5		1	2.0
695+00	699+85	249.0	699+85	13.5		1	2.0
699+85	702+50	265.0	702+50	13.5		1	2.0
702+50	707+50	500.0	707+50	13.5		1	2.0
707+50	710+60	310.0	710+60	8.7		1	2.0
710+60	713+60	300.0	713+60	8.7		1	2.0
713+60	717+50	205.0	717+50	12.3		1	2.0
717+50	722+50	500.0	722+50	13.5		1	2.0
722+50	727+50	500.0	727+50	13.5		1	2.0
727+50	732+50	500.0	732+50	13.5		1	2.0
732+50	734+78	228.0	734+78	13.5		1	2.0
734+78	753+00	400.0	753+00	13.5		1	2.0
749+00	757+00	400.0	757+00	16.2		1	2.0
753+00	761+00	400.0	761+00	16.2		1	2.0
761+00	764+00	300.0	764+00	16.2		1	2.0
764+00	766+50	250.0	766+50	16.2		1	2.0
766+50	769+00	250.0	769+00	16.2		1	2.0
769+00	771+00	200.0	769+00	16.2		1	2.0
771+00	773+00	200.0	771+00	16.2		1	2.0
773+00	775+00	200.0	773+00		31		
SUBTOTALS:		17,971.0		692.4		43	86.0

PIPE UNDERDRAINS 4" SCHEDULE - CONTINUED

60107600		60108100		60100060		78001110	
NORTHBOUND MEDIAN EDGE OF PAVEMENT							
PIPE UNDERDRAINS 4"			PIPE UNDERDRAINS 4" (SPECIAL)			CONCRETE HEADWALL FOR PIPE DRAINS	PAINT PVT MARKING 4"
BEGINNING STATION	ENDING STATION	LENGTH	OUTLET STATION	LENGTH	CONNECT TO STRUCT NO.		
		FOOT		FOOT		EACH	FOOT
567+63	570+50	287.0	567+63	14.3		1	2.0
570+50	574+01	351.0	570+50	8.8		1	2.0
576+00	581+00	500.0	576+00		6		
581+00	586+00	500.0	581+00	13.5		1	2.0
586+00	588+50	250.0	586+00	13.5		1	2.0
588+50	590+50	200.0	590+50	9.3		1	2.0
590+50	591+60	110.0	590+50	9.3		1	2.0
608+60	613+60	500.0	613+60		12		
615+65	620+00	435.0	620+00	13.5		1	2.0
620+00	622+51	251.0	622+51		14		
622+51	625+00	249.0	622+51		14		
625+00	627+50	250.0	625+00	13.5		1	2.0
627+50	632+50	500.0	627+50	13.5		1	2.0
632+50	636+20	370.0	632+50	9.1		1	2.0
638+00	642+50	450.0	638+00	12.3	16		
642+50	645+05	255.0	642+50	13.5		1	2.0
645+05	647+54	249.0	645+05	13.5		1	2.0
647+54	650+00	246.0	650+00	13.1		1	2.0
650+00	652+50	250.0	652+50	13.7		1	2.0
652+50	655+50	300.0	655+50	9.2		1	2.0
655+50	658+50	300.0	658+50	9.5		1	2.0
660+63	665+80	517.0	665+80	13.5		1	2.0
665+80	671+00	520.0	671+00	13.5		1	2.0
671+00	673+50	250.0	673+50	15.6		1	2.0
673+50	676+10	260.0	676+10		21		
676+10	678+60	250.0	678+60		21		
678+60	682+50	390.0	682+50	14.1		1	2.0
682+50	686+51	401.0	686+51	9.2		1	2.0
686+51	692+50	413.0	688+37	13.4		1	2.0
688+37	695+00	250.0	692+50	13.7		1	2.0
692+50	697+36	236.0	695+00	13.5		1	2.0
695+00	699+85	249.0	699+85	13.5		1	2.0
699+85	702+50	265.0	702+50	13.5		1	2.0
702+50	707+50	500.0	707+50	13.5		1	2.0
707+50	710+60	310.0	710+60	8.7		1	2.0
710+60	713+60	300.0	713+60	8.7		1	2.0
713+60	717+50	205.0	717+50	12.3		1	2.0
717+50	722+50	500.0	722+50	13.5		1	2.0
722+50	727+50	500.0	727+50	13.5		1	2.0
727+50	732+50	500.0	732+50	13.5		1	2.0
732+50	734+78	228.0	734+78	13.5		1	2.0
734+78	753+00	400.0	753+00	13.5		1	2.0
749+00	757+00	400.0	757+00	16.2		1	2.0
753+00	761+00	400.0	761+00	16.2		1	2.0
761+00	764+00	300.0	764+00	16.2		1	2.0
764+00	766+50	250.0	766+50	16.2		1	2.0
766+50	769+00	250.0	769+00	16.2		1	2.0
769+00	771+00	200.0	769+00	16.2		1	2.0
771+00	773+00	200.0	773+00		31		
773+00	775+00	200.0	773+00				
SUBTOTALS:		15,307.0		473.7		37	72.0

CONTINUED ON NEXT SHEET

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 PIPE UNDERDRAINS
 FAP 322 (US 51)
 SECTION 11-12
 CHRISTIAN COUNTY
 SCALE: NONE
 DATE 8/22/06
 DRAWN BY SEB
 CHECKED BY TLD

M0-15-2018 0144522AH

SHEET 21