72932

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-12	CHRISTIAN	284	22
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PIPE UNDERDRAINS 4" SCHEDULE - CONTINUED

		60107600		60108100		60100060	78001110
SOUTHBOUND MEDIAN EDGE OF PAVEMENT							
PIPE UNDERDRAINS 4"			PIPE UNDERDRAINS 4" (SPECIAL)			CONCRETE HEADWALL FOR PIPE DRAINS	PAINT PVMT MARKING 4"
BEGINNING STATION	ENDING STATION	LENGTH	OUTLET STATION	LENGTH	CONNECT TO STRUCT NO.		
		FOOT		FOOT		EACH	FOOT
564+66	565+55	89.0	565+55	13.5		1	2.0
565+55	567+63	208.0	565+55	13.5		1	
567+63	570+50	287.0	567+63	13.5		1	2.0
570+50	573+86	336.0	570+50	12.3		1	2.0
576+00	581+00	500.0	576+00	8.7		1	2.0
581+00	586+00	500.0	581+00	10.7		1	2.0
586+00	589+67	367.0	586+00	13.5		1	2.0
589+67	592+17	250.0	592+17	12.3		1	2.0
592+17	594+05	188.0	594+05	12.3		1	2.0
595+99	598+50	251.0	598+50	8.7		1	2.0
598+50	603+50	500.0	603+50	13.4		1	2.0
603+50	608+50	500.0	608+50	13.4		1	2.0
608+50	613+65	515.0	613+65	12.3		1	2.0
615+45	620+00	455.0	620+00	9.0		1	2.0
620+00	622+51	251.0	622+51	13.5		1	2.0
622+51	625+00	249.0	622+51	13.5		1	2.0
625+00	627+50	250.0	625+00	13.5		1	2.0
627+50	632+50	500.0	627+50	13.5		1	2.0
632+50	636+00	350.0	632+50	12.7		1	2.0
638+00	642+50	450.0	638+00	8.8	16		
642+50	645+10	260.0	642+50	13.2		1	2.0
667+05	671+00	395.0	671+00	13.5		1	2.0
671+00	673+55	255.0	673+55	15.6		1	2.0
673+55	676+10	255.0	676+10	13.5		1	2.0
676+10	678+60	250.0	676+10	13.5		1	
678+60	682+50	390.0	678+60	14.1		1	2.0
682+50	685+99	349.0	682+50	12.6		1	2.0
688+35	692+50	415.0	688+35	8.7		1	2.0
692+50	695+00	250.0	692+50	12.7		1	2.0
695+00	697+36	236.0	695+00	13.5		1	2.0
697+36	699+85	249.0	699+85	13.5		1	2.0
699+85	702+50	265.0	702+50	13.5		1	2.0
702+50	707+50	500.0	707+50	13.5		1	2.0
707+50	710+60	310.0	710+60	12.3		1	2.0
710+60	713+45	285.0	713+45	12.3		1	2.0
715+25	717+50	225.0	717+50	8.7		1	2.0
717+50	722+50	500.0	722+50	13.5		1	2.0
722+50	727+50	500.0	727+50	13.5		1	2.0
727+50	732+50	500.0	732+50	13.5		1	2.0
732+50	734+78	228.0	734+78	13.5		1	2.0
749+00	753+00	400.0	753+00	13.4		1	2.0
753+00	757+00	400.0	757+00	13.4		1	2.0
757+00	761+00	400.0	761+00	13.4		1	2.0
761+00	764+00	300.0	764+00	13.4		1	2.0
764+00	766+50	250.0	766+50	13.4		1	2.0
766+50	769+00	250.0	769+00	12.3		1	2.0
769+00	771+03	203.0	769+00	12.3		1	
773+00	775+50	250.0	773+00	8.7		1	2.0
775+50	778+00	250.0	775+50	8.7		1	2.0
SUBTOTALS:		16,316.0		610.3		48	90.0

PIPE UNDERDRAINS 4" SCHEDULE - CONTINUED

		60107600		60108100		60100060	78001110
SOUTHBOUND OUTSIDE EDGE OF PAVEMENT							
PIPE UNDERDRAINS 4"			PIPE UNDERDRAINS 4" (SPECIAL)			CONCRETE HEADWALL FOR PIPE DRAINS	PAINT PVMT MARKING 4"
BEGINNING STATION	ENDING STATION	LENGTH	OUTLET STATION	LENGTH	CONNECT TO STRUCT NO.		
		FOOT		FOOT		EACH	FOOT
564+66	565+55	89.0	565+55	16.4		1	2.0
565+55	567+50	195.0	565+55	16.4		1	
567+50	570+00	250.0	567+50	16.4		1	2.0
570+00	573+68	368.0	570+00	16.4		1	2.0
575+68	581+00	532.0	575+68	11.2		1	2.0
581+00	586+00	500.0	581+00	14.4		1	2.0
586+00	589+67	367.0	586+00	16.4		1	2.0
611+00	613+54	254.0	613+54	16.4		1	2.0
615+55	620+00	445.0	620+00	11.5		1	2.0
620+00	622+51	251.0	622+51	16.4		1	2.0
622+51	625+00	249.0	622+51	16.4		1	
625+00	627+50	250.0	625+00	16.4		1	2.0
627+50	632+50	500.0	627+50	16.4		1	2.0
632+50	637+50	500.0	632+50	16.4		1	2.0
637+50	642+50	500.0	637+50	16.4		1	2.0
642+50	645+05	255.0	642+50	16.4		1	2.0
645+05	647+54	249.0	645+05	16.4		1	2.0
647+54	650+00	246.0	650+00	15.5		1	2.0
650+00	652+50	250.0	652+50	15.5		1	2.0
652+50	655+50	300.0	655+50	15.5		1	2.0
655+50	658+00	250.0	658+00	15.5		1	2.0
660+56	665+50	494.0	665+50	11.3		1	2.0
665+50	670+50	500.0	670+50	16.4		1	2.0
670+50	673+55	305.0	673+55	16.4		1	2.0
673+55	676+10	255.0	676+10	16.4		1	2.0
676+10	678+60	250.0	676+10	16.4		1	
678+60	682+50	390.0	678+60	16.4		1	2.0
682+50	686+30	380.0	682+50	16.4		1	2.0
688+39	692+50	411.0	688+39	11.2		1	2.0
692+50	695+00	250.0	692+50	11.2		1	2.0
695+00	697+36	236.0	695+00	16.4		1	2.0
697+36	699+85	249.0	699+85	16.4		1	2.0
699+85	702+50	265.0	702+50	16.4		1	2.0
702+50	707+50	500.0	707+50	16.4		1	2.0
707+50	712+50	500.0	712+50	16.4		1	2.0
712+50	717+50	500.0	717+50	16.4		1	2.0
717+50	722+50	500.0	722+50	16.4		1	2.0
722+50	727+50	500.0	727+50	16.4		1	2.0
727+50	732+50	500.0	732+50	16.4		1	2.0
732+50	734+78	228.0	734+78	16.4		1	2.0
749+00	753+00	400.0	753+00	16.4		1	2.0
772+76	775+50	274.0	772+76	16.4		1	2.0
775+50	778+00	250.0	775+50	16.4		1	2.0
SUBTOTALS:		14,937		674.0		43	80.0
TOTALS:		64,531		2,451		171	328

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
PIPE UNDERDRAINS
FAP 322 (US 51)
SECTION 11-12
CHRISTIAN COUNTY

SCALE: NONE — DRAWN BY SEB
DATE 8/22/06 — CHECKED BY TLD

Mar-15-2010 @94:52PAM

$FILE$