

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-12	CHRISTIAN	284	26
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

FINAL STRIPING / DELINEATOR SCHEDULE CONTINUED

LOCATION	78001120		78001150	X7800620 & X7030070		X7800600	X7800630	X7800650	X7800680	78004200	78004220	78004230		78004250	78004280	78100100	63500105					
	PAINT PAVEMENT MARKING						GROOVED URETHANE PAVEMENT MARKING		URETHANE PAVEMENT MARKING				PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID					RAISED REFLECTIVE PAVEMENT MARKER	DELINEATORS			
	LINE 5"		LINE 12"		LINE 5"		LETTERS & SYMBOLS	LINE 6"	LINE 12"	LINE 24"	LETTERS & SYMBOLS	LINE 5"	LINE 6"		LINE 12"	LINE 24"	WAY CRYSTAL		SINGLE	DOUBLE	DOUBLE	
	WHITE SOLID	YELLOW SOLID	YELLOW SOLID	WHITE SOLID	YELLOW SOLID	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	WHITE SKIP	WHITE SOLID	WHITE SKIP	YELLOW SOLID	WHITE SOLID		EACH	EACH	WHITE	WHITE	AMBER
		FOOT	FOOT	FOOT	FOOT	FOOT		FOOT	FOOT	FOOT		FOOT	FOOT	FOOT	FOOT							
FAP 322	783+00 to 798+00	NB	OUTSIDE			60.0										4						
			☺								75.0											
			☺			395.0																
			☺								375.0											
TR 229A	17+78.6 to 20+00	LT		199.1																		
			☺		282.4																	
			☺	240.9																	23.4	
	20+00 to 22+16.3	LT		235.8																		
			☺		272.6																	
			☺	194.1																		
ASSUMPTION SOUTH CONNECTOR	2+50 to 6+00	LT		371.1																		
			☺		538.0																	
			☺	326.0																		
	6+00 to 495+00	LT		818.9																		
			☺		1774.6																	
			☺	875.1																		
ILLINOIS ST	44+70 to 50+82	☺					821.7 **	31.2	101.0	202.9	42.5											
TR 209	50+82 to 55+00	LT		473.0																		
			☺		716.3	151.2																
			☺	392.0																		
CH 6	47+58.2 to 50+00	LT		210.0																		
			☺		327.0																	
			☺	261.8																		
	50+00 to 52+41.8	LT		261.8																		
			☺		327.0																	
			☺	210.0																		
TR 193	12+53.8 to 15+13.6	LT		259.8																		
			☺		519.6																	
			☺	195.2																		
	17+57.8 to 20+00	LT		210.7																		
			☺		320.2																	
			☺	262.5																		
	20+00 to 22+42.2	LT		262.5																		
			☺		320.2																	
			☺	210.7																		
TR 306	8+55 to 10+00	LT		110.2																		
			☺		132.0																	
			☺	110.2																		
SUB-TOTALS:				6,964	5,774	151	45,063	48,704	32	101	203	43	1,186	11,365	6,663	380	916	202	731	93	54	72
TOTALS:				12,738 *		151	93,767		32	101	203	43	1,186	11,365	7,043	916	202	731				219

* - SEE STAGE CONSTRUCTION PAVEMENT MARKING SCHEDULE FOR ADDITIONAL QUANTITIES
 ** - URETHANE PAVEMENT MARKING ONLY (NO GROOVING)

LIGHTING SCHEDULE

PAY ITEM	DESCRIPTION	UNIT	CROSSOVER "A" / TR 229A INTERSECTION	ASSUMPTION SCOUTH CON. INTERSECTION	ILLINOIS ST/ TR 209 INTERSECTION	CH 6 INTERSECTION	TR 193 INTERSECTION	PROJECT TOTAL
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1	1	1	1	1	5
83057280	LIGHT POLE, WOOD, 50 FOOT, CLASS 3	EACH	9					9
81021330	CONDUIT PUSHED, 2" DIA., PVC	FOOT	265	200	265	270	270	1270
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1640	1185	1380	1375	1685	7265
81603000	UNIT DUCT, 600V, 2-1C NO.8, 1/C NO.8 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	985				1070	2055
81603010	UNIT DUCT, 600V, 2-1C NO.10, 1/C NO.10 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT		1480	1750	1750	960	5940
81603065	UNIT DUCT, 600V, 2-1C NO.2, 1/C NO.2 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	1520					1520
81800200	AERIAL CABLE, 2-1/C NO. 4 WITH MESSENGER WIRE	FOOT	1655					1655
82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	21	10	12	12	12	67
82500300	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 30AMP	EACH	1	1	1	1	1	4
82500310	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 60AMP	EACH	1					1
83055300	LIGHT POLE, 45 FT. M.H., TENON MOUNT	EACH	8	8	8	8	8	40
83055310	LIGHT POLE, 45 FT. M.H., TENON MOUNT - TWIN	EACH	2	1	2	2	2	9
83600355	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 6'	EACH	8	8	8	8	8	40
83600357	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 8'	EACH	2	1	2	2	2	9
83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	40	36	40	40	40	196

REMOVAL OF EXISTING LIGHTING UNIT, NO SALVAGE

LOCATION	84200600 NUMBER
US 51 771+50 LT	1
US 51 773+00 LT	1
US 51 774+50 LT	1
US 51 776+00 LT	1
US 51 777+50 LT	1
US 51 777+50 RT	1
US 51 779+00 RT	1
US 51 781+50 RT	1
TOTAL:	8

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 FINAL STRIPING & LIGHTING
 FAP 322 (US 51)
 SECTION 11-12
 CHRISTIAN COUNTY

SCALE: NONE
 DATE: 8/22/06

DRAWN BY: SEB
 CHECKED BY: TLD

FILE: 8/15/2010 8:14:53 AM