72932

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-12	CHRISTIAN	284	27
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SIGNAGE SCHEDULE

ROUTE	STATION	LANE	SIDE	FACING	SIGN * MUTCD	SIZE IN X IN W	SIZE IN X IN H	SIGN PANEL TYPE 1 (72000100) SQ FT	SIGN PANEL TYPE 2 (72000200) SQ FT	SIGN PANEL TYPE 3 (72000300) SQ FT	MESSAGE	* OF POSTS	TELESCOPING STEEL SIGN SUPPORT (72800100) FOOT	WOOD SIGN SUPPORT (73000100) FOOT	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY (72700100) POUND	CONCRETE FOUNDATIONS (73400100) CU YD
EX US 51	417+75		RT	SOUTH	W6-1	36	36	9.0			DIVIDED HIGHWAY SYMBOL	1	18.6			
	418+25		LT	SOUTH	W14-3	48	36	6.0			NO PASSING ZONE	2	34.0			
	473+70		℄	NORTH	OM4-1	18	18	2.3			RED END OF ROADWAY MARKER	1	14.2			
			℄	NORTH	R11-I100	36	24	6.0			ROAD ENDS	1	14.0			
			℄	NORTH	OM4-1	18	18	2.3			RED END OF ROADWAY MARKER	1	14.2			
	606+00		RT	SOUTH	M4-5	24	12	2.0			TO	1	16.4			
					M1-4	24	24	4.0			US ROUTE 51					
					M6-1R	24	12	2.0			ARROW RT					
	607+35		RT	SOUTH	R1-1	36		9.0			STOP		17.2			
CROSSOVER "A"	103+00 TO 111+00		LT	SOUTH	W1-8	24	30	45.0			CHEVRON	9	130.5			
	104+50		LT	SOUTH	R4-7	36	48		12.0		KEEP RIGHT SYMBOL	1	16.0			
SB TRANSITION	200+55		LT	NORTH	W6-3	36	36	9.0			TWO WAY TRAFFIC SYMBOL	1	18.6			
			RT	NORTH	W6-3	36	36	9.0			TWO WAY TRAFFIC SYMBOL	1	18.6			
FAP 322	564+84	NB	MEDIAN	SOUTH	W2-1	36	36	9.0			SIDE ROAD SYMBOL	1	18.9			
			OUTSIDE	SOUTH	W2-1	36	36	9.0			SIDE ROAD SYMBOL	1	18.6			
	565+00 TO 574+00	SB	MEDIAN	NORTH	W1-8	24	30	50.0			CHEVRON	10	145.0			
	566+86	NB	MEDIAN	SOUTH	R3-I100L	36	36	9.0			LEFT TURN LANE	1	19.0			
					M6-2L	21	15	2.2			ARROW LT					
	567+07	NB	OUTSIDE	SOUTH	R3-I100R	36	36	9.0			RIGHT TURN LANE	1	18.7			
					M6-2R	21	15	2.2			ARROW RT					
	578+50	NB	MEDIAN	NORTH	R5-1a	36	24	6.0			WRONG WAY	1	16.7			
			OUTSIDE	NORTH	R5-1a	36	24	6.0			WRONG WAY	1	16.4			
	574+00	NB	MEDIAN	NORTH	R5-1	36	36	9.0			DO NOT ENTER	1	17.7			
			OUTSIDE	NORTH	R5-1	36	36	9.0			DO NOT ENTER	1	17.4			
	574+30		MEDIAN	WEST	R6-1L	36	12	3.0			ONE WAY LT	1	17.4			
					R1-2	36		3.9			YIELD					
	575+30		MEDIAN	EAST	R6-1L	36	12	3.0			ONE WAY LT	1	17.4			
					R1-2	36		3.9			YIELD					
	575+75	SB	MEDIAN	SOUTH	R5-1	36	36	9.0			DO NOT ENTER	1	17.7			
			OUTSIDE	SOUTH	R5-1	36	36	9.0			DO NOT ENTER	1	17.4			
	577+75	NB	OUTSIDE	SOUTH	R2-1	48	60		20.0		SPEED LIMIT 65 MPH	1		19.4		
	578+50	SB	MEDIAN	SOUTH	R5-1a	36	24	6.0			WRONG WAY	1	16.7			
			OUTSIDE	SOUTH	R5-1a	36	24	6.0			WRONG WAY	1	16.4			
	580+66	SB	MEDIAN	NORTH	R2-1	48	60		20.0		SPEED LIMIT 55 MPH	1		19.7		
			OUTSIDE	NORTH	R2-1	48	60		20.0		SPEED LIMIT 55 MPH	1		19.4		
	582+46	SB	OUTSIDE	NORTH	R3-I100R	36	36	9.0			RIGHT TURN LANE	1	18.7			
					M6-2R	21	15	2.2			ARROW RT					
	582+95	SB	MEDIAN	NORTH	R3-I100L	36	36	9.0			LEFT TURN LANE	1	19.0			
					M6-2L	21	15	2.2			ARROW LT					
	584+84	SB	MEDIAN	NORTH	W2-1	36	36	9.0			SIDE ROAD SYMBOL	1	18.9			
			OUTSIDE	NORTH	W2-1	36	36	9.0			SIDE ROAD SYMBOL	1	18.6			
	589+10	NB	MEDIAN	EAST	R6-1R	36	12	3.0			ONE WAY RT	1	15.7			
	589+66	SB	MEDIAN	NORTH	W4-2L	48	48		16.0		LT LANE ENDS SYMBOL	2	37.4			
			OUTSIDE	NORTH	W4-2L	48	48		16.0		LT LANE ENDS SYMBOL	2	36.8			
	591+25	NB	MEDIAN	NORTH	R5-1a	36	24	6.0			WRONG WAY	1	16.7			
			OUTSIDE	NORTH	R5-1a	36	24	6.0			WRONG WAY	1	16.4			
	592+50	SB	MEDIAN	NORTH	R2-5a	48	60		20.0		REDUCE SPEED AHEAD	1		21.7		
					R2-I101	24	24	4.0			55 MPH					
			OUTSIDE	NORTH	R2-5a	48	60		20.0		REDUCE SPEED AHEAD	1		21.4		
					R2-I101	24	24	4.0			55 MPH					
	594+25	NB	MEDIAN	NORTH	R5-1	36	36	9.0			DO NOT ENTER	1	17.7			
			OUTSIDE	NORTH	R5-1	36	36	9.0			DO NOT ENTER	1	17.4			
	594+61		MEDIAN	WEST	R6-1L	36	12	3.0			ONE WAY LT	1	17.4			
					R1-2	36		3.9			YIELD					
	595+60		MEDIAN	EAST	R6-1L	36	12	3.0			ONE WAY LT	1	17.4			
					R1-2	36		3.9			YIELD					
	596+00	SB	MEDIAN	SOUTH	R5-1	36	36	9.0			DO NOT ENTER	1	17.7			
			OUTSIDE	SOUTH	R5-1	36	36	9.0			DO NOT ENTER	1	17.4			
	598+75	SB	MEDIAN	SOUTH	R5-1a	36	24	6.0			WRONG WAY	1	16.7			
			OUTSIDE	SOUTH	R5-1a	36	24	6.0			WRONG WAY	1	16.4			
	599+66	SB	MEDIAN	NORTH	W9-2R	48	48		16.0		LANE ENDS MERG RT	2	37.4			
			OUTSIDE	NORTH	W9-2R	48	48		16.0		LANE ENDS MERG RT	2	36.8			
	602+60	NB	MEDIAN	EAST	R6-1R	36	12	3.0			ONE WAY RT	1	15.7			
	602+75	NB	OUTSIDE	SOUTH	SIGN001	114	24		19.0		ARROW ASSUMPTION	2			189	1.4
	604+00	SB	OUTSIDE	NORTH	SIGN002	102	36			25.5	ILLINOIS 16 8 PANA 10	2			189	1.4

CONTINUED ON NEXT SHEET

REVISIONS NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
SIGNAGE
FAP 322 (US 51)
SECTION 11-12
CHRISTIAN COUNTY

SCALE: NONE — DRAWN BY SEB
DATE 8/22/06 — CHECKED BY TLD

Mar-15-2010 @9:45:36AM
$FILE$