

SIGNAGE SCHEDULE - CONTINUED

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
322	11-12	CHRISTIAN	284	28
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

ROUTE	STATION	LANE	SIDE	FACING	SIGN * MUTCD	SIZE		SIGN PANEL			MESSAGE	# OF POSTS	72800100	73000100	72700100	73400100
						W	H	TYPE 1	TYPE 2	TYPE 3			TELESCOPING STEEL SIGN SUPPORT	WOOD SIGN SUPPORT	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	CONCRETE FOUNDATIONS
						SQ FT	SQ FT	SQ FT	FOOT	FOOT			POUND	CU YD		
FAP 322	604+65	NB	MEDIAN	SOUTH	W2-2	36	36				SIDE ROAD SYMBOL (SINGLE)	1				
			OUTSIDE	SOUTH	W2-2	36	36				SIDE ROAD SYMBOL (SINGLE)	1				
	606+70	NB	MEDIAN	SOUTH	R3-1100L	36	36				LEFT TURN LANE	1				
					M6-2L	21	15				ARROW LT					
	609+00	SB	MEDIAN	NORTH	R2-1	48	60		20.0		SPEED LIMIT 65 MPH	1		19.4		
	611+00	NB	MEDIAN	NORTH	R5-1a	36	24				WRONG WAY	1		16.7		
			OUTSIDE	NORTH	R5-1a	36	24				WRONG WAY	1		16.4		
	612+00	SB	OUTSIDE	NORTH	M3-3	24	12				SOUTH	1		17.4		
					M1-4	24	24				US ROUTE 51					
	613+75	NB	MEDIAN	NORTH	R5-1	36	36				DO NOT ENTER	1		17.7		
			OUTSIDE	NORTH	R5-1	36	36				DO NOT ENTER	1		17.4		
	614+15		MEDIAN	WEST	R6-1L	36	12				ONE WAY LT	1		17.4		
					R1-2	36					YIELD					
	615+15		MEDIAN	EAST	R6-1L	36	12				ONE WAY LT	1		17.4		
					R1-2	36					YIELD					
	615+50	SB	MEDIAN	SOUTH	R5-1	36	36				DO NOT ENTER	1		17.7		
			OUTSIDE	SOUTH	R5-1	36	36				DO NOT ENTER	1		17.4		
	616+00	NB	OUTSIDE	SOUTH	M3-1	24	12				NORTH	1		17.4		
					M1-4	24	24				US ROUTE 51					
	618+25	SB	MEDIAN	SOUTH	R5-1a	36	24				WRONG WAY	1		16.7		
			OUTSIDE	SOUTH	R5-1a	36	24				WRONG WAY	1		16.4		
	622+45	SB	OUTSIDE	NORTH	R3-1100R	36	36				RIGHT TURN LANE	1		18.7		
					M6-2R	21	15				ARROW RT					
	624+65	SB	MEDIAN	NORTH	W2-2	36	36				SIDE ROAD SYMBOL (SINGLE)	1		18.9		
			OUTSIDE	NORTH	W2-2	36	36				SIDE ROAD SYMBOL (SINGLE)	1		18.6		
	626+00	NB	MEDIAN	EAST	R6-1R	36	12				ONE WAY RT	1		15.7		
	633+25	NB	MEDIAN	NORTH	R5-1a	36	24				WRONG WAY	1		16.7		
			OUTSIDE	NORTH	R5-1a	36	24				WRONG WAY	1		16.4		
	636+00	NB	MEDIAN	NORTH	R5-1	36	36				DO NOT ENTER	1		17.7		
			OUTSIDE	NORTH	R5-1	36	36				DO NOT ENTER	1		17.4		
	636+40		MEDIAN	WEST	R6-1L	36	12				ONE WAY LT	1		17.4		
					R1-2	36					YIELD					
	637+60		MEDIAN	EAST	R6-1L	36	12				ONE WAY LT	1		17.4		
					R1-2	36					YIELD					
	638+00	SB	MEDIAN	SOUTH	R5-1	36	36				DO NOT ENTER	1		17.7		
			OUTSIDE	SOUTH	R5-1	36	36				DO NOT ENTER	1		17.4		
	640+75	SB	MEDIAN	SOUTH	R5-1a	36	24				WRONG WAY	1		16.7		
			OUTSIDE	SOUTH	R5-1a	36	24				WRONG WAY	1		16.4		
	647+00	NB	MEDIAN	EAST	R6-1R	36	12				ONE WAY RT	1		15.7		
	649+90	NB	MEDIAN	SOUTH	W2-1	36	36				SIDE ROAD SYMBOL	1		20.2		
W16-8					36	15				ILLINOIS STREET						
W2-1					36	36				SIDE ROAD SYMBOL	1		19.9			
651+60	NB	MEDIAN	SOUTH	R3-1100L	36	36				LEFT TURN LANE	1		19.0			
				M6-2L	21	15				ARROW LT						
				R3-1100R	36	36				RIGHT TURN LANE	1		18.7			
656+00	NB	MEDIAN	NORTH	R5-1a	36	24				WRONG WAY	1		16.7			
		OUTSIDE	NORTH	R5-1a	36	24				WRONG WAY	1		16.4			
657+00	SB	OUTSIDE	NORTH	M3-3	24	12				SOUTH	1		17.4			
				M1-4	24	24				US ROUTE 51						
658+75	NB	MEDIAN	NORTH	R5-1	36	36				DO NOT ENTER	1		17.7			
		OUTSIDE	NORTH	R5-1	36	36				DO NOT ENTER	1		17.4			
659+18		MEDIAN	WEST	R6-1L	36	12				ONE WAY LT	1		17.4			
				R1-2	36					YIELD						
660+14		MEDIAN	EAST	R6-1L	36	12				ONE WAY LT	1		17.4			
				R1-2	36					YIELD						
660+50	SB	MEDIAN	SOUTH	R5-1	36	36				DO NOT ENTER	1		17.7			
		OUTSIDE	SOUTH	R5-1	36	36				DO NOT ENTER	1		17.4			
662+00	NB	OUTSIDE	SOUTH	M3-1	24	12				NORTH	1		17.4			
				M1-4	24	24				US ROUTE 51						
663+25	SB	MEDIAN	SOUTH	R5-1a	36	24				WRONG WAY	1		16.7			
		OUTSIDE	SOUTH	R5-1a	36	24				WRONG WAY	1		16.4			

CONTINUED ON NEXT SHEET

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES
 SIGNAGE
 FAP 322 (US 51)
 SECTION 11-12
 CHRISTIAN COUNTY

SCALE: NONE
 DATE: 8/22/06

DRAWN BY: SEB
 CHECKED BY: TLD

Mo-15-2018 01445384M

FILE#