| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 322 | 11-12 | CHRISTIAN | 284 | 31 |
| STA. | | TO STA. | | |
| FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT | | |

## SIGNAGE SCHEDULE - CONTINUED

| ROUTE | STATION | LANE | SIDE | FACING | SIGN * MUTCD | SIZE IN X IN W | SIZE IN X IN H | 72000100 SIGN PANEL TYPE 1 SQ FT | 72000200 SIGN PANEL TYPE 2 SQ FT | 72000300 SIGN PANEL TYPE 3 SQ FT | MESSAGE | * OF POSTS | 72800100 TELESCOPING STEEL SIGN SUPPORT FOOT | 73000100 WOOD SIGN SUPPORT FOOT | 72700100 STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY POUND | 73400100 CONCRETE FOUNDATIONS CU YD |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| CH 6 | 49+21 | | RT | EAST | R6-1L | 36 | 12 | 3.0 | | | ONE WAY LT | 2 | 38.6 | | | |
| | | | | WEST | R6-1R | 36 | 12 | 3.0 | | | ONE WAY RT | | | | | |
| | | | | WEST | R1-1 | 36 | 36 | 9.0 | | | STOP | | | | | |
| | | | | WEST | R6-3a | 24 | 18 | 3.0 | | | DIVIDED HIGHWAY | | | | | |
| | 50+77 | | LT | WEST | R6-1L | 36 | 12 | 3.0 | | | ONE WAY LT | 2 | 38.6 | | | |
| | | | | EAST | R6-1R | 36 | 12 | 3.0 | | | ONE WAY RT | | | | | |
| | | | | EAST | R1-1 | 36 | 36 | 9.0 | | | STOP | | | | | |
| | | | | EAST | R6-3a | 24 | 18 | 3.0 | | | DIVIDED HIGHWAY | | | | | |
| TR 193 | 13+60 | | LT | SOUTH | W1-7 | 48 | 24 | 8.0 | | | DOUBLE ARROW | 2 | 32.8 | | | |
| | 16+00 | | LT | EAST | SIGN007 | 67 | 18 | 8.4 | | | ARROW ASSUMPTION | 2 | 32.8 | | | |
| | 19+18 | | RT | EAST | R6-1L | 36 | 12 | 3.0 | | | ONE WAY LT | 2 | 38.6 | | | |
| | | | | WEST | R6-1R | 36 | 12 | 3.0 | | | ONE WAY RT | | | | | |
| | | | | WEST | R1-1 | 36 | 36 | 9.0 | | | STOP | | | | | |
| | | | | WEST | R6-3a | 24 | 18 | 3.0 | | | DIVIDED HIGHWAY | | | | | |
| | 20+80 | | LT | WEST | R6-1L | 36 | 12 | 3.0 | | | ONE WAY LT | 2 | 38.6 | | | |
| | | | | EAST | R6-1R | 36 | 12 | 3.0 | | | ONE WAY RT | | | | | |
| | | | | EAST | R1-1 | 36 | 36 | 9.0 | | | STOP | | | | | |
| | | | | EAST | R6-3a | 24 | 18 | 3.0 | | | DIVIDED HIGHWAY | | | | | |
| TR 306 | 9+20 | | RT | EAST | R6-1L | 36 | 12 | 3.0 | | | ONE WAY LT | 2 | 38.6 | | | |
| | | | | WEST | R6-1R | 36 | 12 | 3.0 | | | ONE WAY RT | | | | | |
| | | | | WEST | R1-1 | 36 | 36 | 9.0 | | | STOP | | | | | |
| | | | | WEST | R6-3a | 24 | 18 | 3.0 | | | DIVIDED HIGHWAY | | | | | |
| TOTALS: | | | | | | | | 1,597.0 | 255.0 | 102.5 | | | 3,757.0 | 140.4 | 1,134.0 | 8.4 |

| REVISIONS NAME | DATE |
|---|---|
| | |

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
SIGNAGE
FAP 322 (US 51)
SECTION 11-12
CHRISTIAN COUNTY

SCALE: NONE DRAWN BY SEB
DATE 8/22/06 CHECKED BY TLD

Mar-15-2010 @9:45:45AM
$FILE$