

SUMMARY OF QUANTITIES				ROADWAY FAP 662 80% FEDERAL 20% STATE	ROADWAY RESURFACING PARKING LANES 50% STATE 50% VILLAGE
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 1000-2A	CONSTRUCTION TYPE CODE 1000-2A
20200100	EARTH EXCAVATION	CU. YD.	419	419	
20800150	TRENCH BACKFILL	CU. YD.	32	32	
25000200	SEEDING, CLASS 2	ACRE	0.2	0.2	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	18	18	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	18	18	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	18	18	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.4	0.4	
25100125	MULCH, METHOD 3	ACRE	0.2	0.2	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	50	50	
31100500	SUB-BASE GRANULAR MATERIAL, TYPE A 6"	SQ. YD.	383	383	
35300700	PORTLAND CEMENT CONCRETE BASE COURSE 12"	SQ. YD.	446	446	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	14.31	12.55	1.76
40600300	AGGREGATE (PRIME COAT)	TON	75.31	66.09	9.22
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1455	1261	194
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ. YD.	537	537	
40600990	TEMPORARY RAMP	SQ. YD.	269	269	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2910	2523	387
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	431	431	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ. FT.	1986	1986	
42400800	DETECTABLE WARNINGS	SQ. FT.	20	20	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ. YD.	37119	32511	4608
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	410	410	
44000600	SIDEWALK REMOVAL	SQ. FT.	1617	1617	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1144	1144	
44003800	MEDIAN SURFACE REMOVAL	SQ. FT.	1998	1998	
44003900	MEDIAN SURFACE REMOVAL AND REPLACEMENT	SQ. FT.	1260	1260	
44200172	PAVEMENT PATCHING, TYPE III, 14 INCH	SQ. YD.	81	81	
44201407	CLASS C PATCHES, TYPE III, 14 INCH	SQ. YD.	80	80	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	33	33	
54200100	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	20	20	
54213657	PRECAST REINFORCED CONCRETE END SECTIONS 12"	EACH	1	1	
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	132	132	
56109210	WATER VALVES TO BE ADJUSTED	EACH	9	9	
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	1	1	
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	1	1	

SUMMARY OF QUANTITIES				ROADWAY FAP 662 80% FEDERAL 20% STATE	ROADWAY RESURFACING PARKING LANES 50% STATE 50% VILLAGE
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 1000-2A	CONSTRUCTION TYPE CODE 1000-2A
60240366	INLETS, TYPE B, WITH MEDIAN INLET - (604106)	EACH	2	2	
60255500	MANHOLES TO BE ADJUSTED	EACH	23	23	
60262900	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	1	1	
60500305	FILLING INLETS	EACH	3	3	
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	598	598	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL. MO	8	8	
67100100	MOBILIZATION	L. SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L. SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L. SUM	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L. SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L. SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L. SUM	1	1	
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L. SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L. SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L. SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL. DAY	10	10	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2352	2352	
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	13813	13813	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4322	4322	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	454	454	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	371	371	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ. FT.	776	776	
78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	12113	12113	
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4322	4322	
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	454	454	
78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SO. FT.	252	252	
78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	1700	1700	
78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	371	371	
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	257	257	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	257	257	
X5510100	STORM SEWER REMOVAL	FOOT	20	20	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L. SUM	1	1	
66900200	NON-SPECIAL WASTE DISPOSAL	CU. YD.	24	24	
66900450	SPECIAL WASTE PLANS AND REPORTS	L. SUM	1	1	
66900530	SOIL DISPOSAL AND ANALYSIS	EACH	1	1	