

# SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	100%	I-72			SCOTT I-72		MORGAN I-72			
			STATE	SCOTT CO. FAI 72 (I-72) ROADWAY 1000	MORGAN CO. FAI 72 (I-72) ROADWAY 1000	MORGAN CO. BL-72/US 67 ROADWAY 1000	STRUCTURE SN 086-0023 SFTY-2A	STRUCTURE SN 086-0024 SFTY-2A	STRUCTURE SN 069-0054 SFTY-2A			
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	264	264								
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	525	525								
28200200	FILTER FABRIC	SQ YD	300	300								
35501332	HOT-MIX ASPHALT BASE COURSE, 12"	SQ YD	2127	2127								
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	148.2	51.7	66	30.5						
40600300	AGGREGATE (PRIME COAT)	TON	782	273	348	161						
40600895	CONSTRUCTING TEST STRIP	EACH	2	1		1						
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL-BUTT JOINT	SQ YD	280			280						
40600990	TEMPORARY RAMP	SQ YD	240	120	40	80						
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	29678	10423	13305	5950						
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	19634	6895	8802	3937						
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	370	46	46	278						
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	87230	47810	39420							
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	37517	7033	30484							
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	129634	71109	58525							
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	56276	10549	45727							
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	15596			15596						
44004250	PAVED SHOULDER REMOVAL	SQ YD	2127	2127								
44200529	CLASS A PATCHES, TYPE II, 8 INCH	SQ YD	38.7			38.7						
44200533	CLASS A PATCHES, TYPE III, 8 INCH	SQ YD	16			16						
44200535	CLASS A PATCHES, TYPE IV, 8 INCH	SQ YD	53.3			53.3						
44200577	CLASS A PATCHES, TYPE II, 12 INCH	SQ YD	370.2	266.8	103.4							
44200581	CLASS A PATCHES, TYPE III, 12 INCH	SQ YD	137.4	62.7	74.7							
44200583	CLASS A PATCHES, TYPE IV, 12 INCH	SQ YD	320	97.3	222.7							
44212899	PAVEMENT PATCHING (FULL DEPTH)	SQ YD	150			150						
44212900	PAVEMENT PATCHING (PARTIAL DEPTH)	SQ YD	800			800						
44213000	PATCHING REINFORCEMENT	SQ YD	861.5	373.4	380.1	108						
44213200	SAW CUTS	FOOT	3836	2048	1386	402						
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1677	372	475	830						
48203100	HOT-MIX ASPHALT SHOULDERS	TON	20970	6109	7799	7062						

• 86-10RS-3, 69-6RS-2, 69-1RS  
 \*\* SCOTT, MORGAN **SHEET NO. 1 OF 3**

FILE NAME: c:\pwwork\pwwork\WIDOT\LAUGH\INRL\dms24453\0672A16-shl-500.DGN <b>Johnson, Depp &amp; Outenberry</b> CONSULTING ENGINEERS Springfield, Illinois	USER NAME: laughlrrr1 PLOT SCALE: 28.0000' / IN. PLOT DATE: Apr-06-2010 09:56:16AM	DESIGNED: - DRAWN: - CHECKED: - DATE: -	REVISED: - REVISED: - REVISED: - REVISED: -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b> SCALE: SHEET NO. OF SHEETS STA. TO STA.	F.A.I. RTE. 72 SECTION . COUNTY ** TOTAL SHEETS 48 SHEET NO. 3 CONTRACT NO. 72A16 FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT
---	--	--	--	---	---	---