

HOT-MIX ASPHALT SURFACE REMOVAL, 4''

LOCATION	SQ YD
FAI-72 (SCOTT COUNTY)	
WB STA. 191+75 TO STA. 207+65	3664
EB STA. 189+84.28 TO STA. 217+84 (MORGAN COUNTY)	6885
WB STA. 343+79 TO STA. 427+15.94	22,232
EB STA. 338+77 TO STA. 426+87.44	23,495
TOTAL = 56,276	

HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH

LOCATION	SQ YD
BL-72/US 67 (MORGAN COUNTY)	
NB LANES	
STA. 356+25 TO STA. 368+95	5644
STA. 388+96 TO STA. 396+60	3396
SB LANES	
STA. 372+50 TO STA. 387+25	6556
TOTAL = 15,596	

PAVED SHOULDER REMOVAL

LOCATION	SIDE	SQ YD
FAI-72 (SCOTT COUNTY)		
RT. STA. 195+82 TO RT. STA. 199+10	OUTSIDE	364
RT. STA. 195+84 TO RT. STA. 199+25	INSIDE	227
LT. STA. 197+07 TO LT. STA. 199+64	INSIDE	171
LT. STA. 197+10 TO LT. STA. 199+79	OUTSIDE	299
RT. STA. 200+21 TO RT. STA. 202+91	OUTSIDE	300
RT. STA. 200+36 TO RT. STA. 202+99	INSIDE	175
LT. STA. 200+74 TO LT. STA. 204+14	INSIDE	227
LT. STA. 200+88 TO LT. STA. 204+16	OUTSIDE	364
TOTAL = 2127		

PAVEMENT PATCHING (PARTIAL DEPTH)

(PROVIDED BY DISTRICT)

LOCATION	SQ YD
BL-72/US 67 (MORGAN COUNTY)	
192	
TOTAL = 192	

AGGREGATE SHOULDERS, TYPE B

LOCATION	TON
FAI-72 (SCOTT COUNTY)	
WB STA. 107+16.06 TO STA. 199+17.81	112
EB STA. 106+86.47 TO STA. 198+64.60	111
WB STA. 201+33.78 TO STA. 262+29.22	74
EB STA. 200+82.53 TO STA. 262+29.22 (MORGAN COUNTY)	75
WB STA. 262+29.22 TO STA. 443+19.48	220
EB STA. 262+29.22 TO STA. 443+19.48	220
EQUATION STA. 443+19.48 BK.= STA. 10+03.94 AH	
WB STA. 10+03.94 TO STA. 22+74.37	15
EB STA. 10+03.94 TO STA. 26+47.25	20
BL-72/US 67	
NB STA. 356+25 TO STA. 453+98	464
SB STA. 372+50 TO STA. 449+60	366
TOTAL = 1677	

HOT-MIX ASPHALT SHOULDERS

LOCATION	TON
FAI-72 (SCOTT COUNTY)	
WB STA. 107+16.06 TO STA. 199+17.81	1836
EB STA. 106+86.47 TO STA. 198+64.60	1831
WB STA. 201+33.78 TO STA. 262+29.22	1216
EB STA. 200+82.53 TO STA. 262+29.22 (MORGAN COUNTY)	1226
WB STA. 262+29.22 TO STA. 443+19.48	3609
EB STA. 262+29.22 TO STA. 443+19.48	3609
EQUATION STA. 443+19.48 BK.= STA. 10+03.94 AH	
WB STA. 10+03.94 TO STA. 22+74.37	253
EB STA. 10+03.94 TO STA. 26+47.25	328
BL-72/US 67	
NB STA. 356+25 TO STA. 453+98	4184
SB STA. 372+50 TO STA. 449+60	2878
TOTAL = 20,970	

STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS

LOCATION	FOOT
BL-72/US 67 (MORGAN COUNTY)	
RT. STA. 323+35.71 TO RT. STA. 326+88.21	362.50
LT. STA. 326+12.79 TO LT. STA. 329+75.29	362.50
RT. STA. 400+92.71 TO RT. STA. 403+30.21	237.50
LT. STA. 403+89.79 TO LT. STA. 406+27.29	237.50
TOTAL = 1200.00	

TRAFFIC BARRIER TERMINAL, TYPE 2

LOCATION	EACH
BL-72/US 67 (MORGAN COUNTY)	
RT. STA. 326+88.21 TO RT. STA. 327+03.00	1
LT. STA. 325+98.00 TO LT. STA. 326+12.79	1
RT. STA. 403+30.21 TO RT. STA. 403+45.00	1
LT. STA. 403+75.00 TO LT. STA. 403+89.79	1
TOTAL = 4	

TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT

LOCATION	EACH
BL-72/US 67 (MORGAN COUNTY)	
RT. STA. 322+75.71 TO RT. STA. 323+25.71	1
LT. STA. 329+75.29 TO LT. STA. 330+25.29	1
RT. STA. 400+42.71 TO RT. STA. 400+92.71	1
LT. STA. 406+27.29 TO LT. STA. 406+77.29	1
TOTAL = 4	

SHOULDER RUMBLE STRIP

LOCATION	FOOT
FAI-72 (SCOTT COUNTY)	
WB STA. 107+16.06 TO STA. 262+29.22	30,594
EB STA. 106+86.47 TO STA. 262+29.22 (MORGAN COUNTY)	30,650
WB STA. 262+29.22 TO STA. 443+19.48	36,180
EB STA. 262+29.22 TO STA. 443+19.48	36,180
EQUATION STA. 443+19.48 BK.= STA. 10+03.94 AH	
WB STA. 10+03.94 TO STA. 22+74.37	2540
EB STA. 10+03.94 TO STA. 26+47.25	3286
BL-72/US 67	
NB STA. 356+25 TO STA. 453+98	19,546
SB STA. 372+50 TO STA. 449+60	15,420
TOTAL = 174,306	

ENGINEER'S FIELD OFFICE, TYPE A

LOCATION	CAL MO
FAI 72 & (BL-72/US 67)	16
TOTAL = 16	

MOBILIZATION

LOCATION	L SUM
FAI-72 (SCOTT COUNTY)	0.34
(MORGAN COUNTY)	0.33
BL-72/US 67	0.33
TOTAL = 1.0	

TRAFFIC CONTROL AND PROTECTION, STANDARD 701402

LOCATION	EACH
FAI-72 (SCOTT COUNTY)	
STA. 200+00.00	
EB SN 086-0023	1
WB SN 086-0024	1
TOTAL = 2	

TRAFFIC CONTROL AND PROTECTION, STANDARD 701411

LOCATION	EACH
(MORGAN COUNTY)	
I-72 INTERCHANGE WITH BL-72/US 67	
NB I-72 ENTRANCE RAMP	1
NB BL-72/US 67 RAMP	1
BL-72/US 67 INTERCHANGE WITH OLD IL 36	
SB BL-72/US 67 RAMP	1
TOTAL = 3	

TRAFFIC CONTROL AND PROTECTION, STANDARD 701201

LOCATION	L SUM
FAI 72 (SCOTT COUNTY)	0.34
(MORGAN COUNTY)	0.33
BL-72/US 67	0.33
TOTAL = 1.0	

TRAFFIC CONTROL AND PROTECTION, STANDARD 701406

LOCATION	L SUM
FAI 72 (SCOTT COUNTY)	0.34
(MORGAN COUNTY)	0.33
BL-72/US 67	0.33
TOTAL = 1.0	

TRAFFIC CONTROL AND PROTECTION, STANDARD 701401

LOCATION	L SUM
FAI 72 (SCOTT COUNTY)	0.34
(MORGAN COUNTY)	0.33
BL-72/US 67	0.33
TOTAL = 1.0	

TRAFFIC CONTROL SURVEILLANCE

LOCATION	CAL DA
FAI 72 (SCOTT COUNTY)	17
(MORGAN COUNTY)	19
BL-72/US 67	3
TOTAL = 39	

CHANGEABLE MESSAGE SIGN

LOCATION	CAL MO
FAI-72 & BL-72/US 67	6
TOTAL = 6	

SHORT-TERM PAVEMENT MARKING

LOCATION	FOOT
FAI-72 (SCOTT COUNTY)	
WB STA. 107+16.06 TO STA. 262+29.22	5218
EB STA. 106+86.47 TO STA. 262+29.22 (MORGAN COUNTY)	5231
WB STA. 262+29.22 TO STA. 443+19.48	6167
EB STA. 262+29.22 TO STA. 443+19.48	6167
EQUATION STA. 443+19.48 BK.= STA. 10+03.94 AH	
WB STA. 10+03.94 TO STA. 22+74.37	452
EB STA. 10+03.94 TO STA. 26+47.25	576
BL-72/US 67	
NB STA. 356+25 TO STA. 453+98	2160
SB STA. 372+50 TO STA. 449+60	1712
TOTAL = 27,684	

TEMPORARY PAVEMENT MARKING - LINE 5''

LOCATION	EDGE LINE SOLID WHITE FOOT	CENTERLINE SKIP-DASH WHITE FOOT	EDGE LINE SOLID YELLOW FOOT
FAI-72 (SCOTT COUNTY)			
WB STA. 107+16.06 TO STA. 262+29.22	15,513	3874	15,513
EB STA. 106+86.47 TO STA. 262+29.22 (MORGAN COUNTY)	15,543	3881	15,543
WB STA. 262+29.22 TO STA. 443+19.48	18,090	4522	18,090
EB STA. 262+29.22 TO STA. 443+19.48	18,090	4522	18,090
EQUATION STA. 443+19.48 BK.= STA. 10+03.94 AH			
WB STA. 10+03.94 TO STA. 22+74.37	1270	318	1270
EB STA. 10+03.94 TO STA. 26+47.25	1643	411	1643
BL-72/US 67			
NB STA. 356+25 TO STA. 453+98	9773	2443	9773
SB STA. 372+50 TO STA. 449+60	7710	1927	7710
SUB TOTALS =	87,632	21,898	87,632
TOTAL = 197,162			

• 86-10RS-3, 69-6RS-2, 69-1RS
•• SCOTT, MORGAN