

CODE NO.	ITEM	UNIT	SUMMARY OF QUANTITIES		Y031-1F		
			TOTAL QUANTITY	1000	100% STATE		
					ROADWAY	5TH ST & COLLEGE SIGNALS	WOODLAWN & COLLEGE SIGNALS
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	32.4	32.4			
40600300	AGGREGATE (PRIME COAT)	TON	46.7	46.7			
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	1634	1634			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	3565.8	3565.8			
40600990	TEMPORARY RAMP	SQ YD	1395.5	1395.5			
40800340	HOT-MIX ASPHALT SURFACE COURSE, MIX D, N 70	TON	2451	2451			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	492	492			
42400100	PORTLAND CEMENT CONCRETE SIDEWALK, 4"	SQ FT	4774.4	4774.4			
42400800	DETECTABLE WARNINGS	SQ FT	80	80			
44000600	SIDEWALK REMOVAL	SQ FT	4774.4	4774.4			
44000159	HOT-MIX ASPHALT SURFACE REMOVAL - 2 1/2"	SQ YD	32739.3	32739.3			
44200116	PAVEMENT PATCHING, TYPE I, 10 INCH	SQ YD	20	20			
44200120	PAVEMENT PATCHING, TYPE II, 10 INCH	SQ YD	300	300			
60255500	MAN HOLES TO BE ADJUSTED	EACH	28	28			
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	9	9			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MD	12	12			
67100100	MOBILIZATION	L SUM	1	1			
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			

CODE NO.	ITEM	UNIT	QUANTITY TOTAL	100% STATE		
				Y031-1F		
				ROADWAY 1000'	5TH ST & COLLEGE SIGNALS	WOODLAWN & COLLEGE SIGNALS
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2099	2099		
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	6204	6204		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1477	1477		
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	15	15		
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	169	169		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	292	292		
72000100	SIGN PANEL, TYPE I	SQ FT	17.5		17.5	
72000200	SIGN PANEL, TYPE II	SQ FT	75		22.5	52.5
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	4280	4280		
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	15	15		
* 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	1924	1924		
* 78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"	FOOT	1477	1477		
* 78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	169	169		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	98	98		
78300200	RAISED RELECTIVE PAVEMENT MARKER REMOVAL	EACH	98	98		
* 80500100	SERVICE INSTALLATION, TYPE A	EACH	1		1	
* 81012200	CONDUIT IN TRENCH, 3/4" DIA., PVC	FOOT	39		39	
* 81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	63		63	

\* SPECIALTY ITEM