

ILLINOIS DEPARTMENT OF TRANSPORTATION						
SUMMARY OF QUANTITIES						
LOCATION OF WORK				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	1000 100% STATE		
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	1,075	1,075		
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	6	6		
63200310	GUARDRAIL REMOVAL	FOOT	1,300	1,300		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6,660	6,660		
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	77,070	77,070		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	925	925		
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	4,437	4,437		
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	77,070	77,070		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	334	334		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	37	37		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6	6		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	334	334		

* SPECIALTY ITEM

FILE NAME =	USER NAME = laughtlrv1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
or:\pwork\PWIDOT\LAUGHLINRL\dms26879\672886-Sht-500.dgn	PLOT SCALE = 100.0000 "/ IN.	DRAWN -	REVISED -					745	105RS-7, 106RS-5	ADAMS	47	5
PLOT DATE = Apr-02-2010 07:11:42AM	DATE -	CHECKED -	REVISED -		SCALE:	SHEET NO. 3 OF 3 SHEETS	STA.	TO STA.	CONTRACT NO. 72886			
									ILLINOIS FED. AID PROJECT			