

STRIPING SCHEDULE

LOCATION	THERMOPLASTIC PAVEMENT MARKING					URETHANE PAVEMENT MARKING				PERFORMED PLASTIC PAVEMENT MARKING				
	SOLID WHITE 5"	SOLID YELLOW 5"	DOUBLE YELLOW 5"	SOLID WHITE 12"	SOLID YELLOW 12"	SOLID WHITE 5"	SOLID YELLOW 5"	DOUBLE YELLOW 5"	SOLID YELLOW 12"	TYPE B - INLAID 5" SKIP-DASH YELLOW	TYPE B - INLAID 6" SKIP-DASH WHITE	TYPE B - INLAID LINE - 6" SOLID WHITE	TYPE B - INLAID LINE - 24" WHITE STOP BAR	TYPE B - INLAID - LETTERS AND SYMBOLS
	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	FT	SO FT
IL RTE 4														
299+64.59 TO 323+99.89						4650	356	2800		354	32			
323+99.89 TO 330+06.71														
45+43.22 TO 0+00.00	685	670	2567	38	80					880	104	396	55	
97+81.50 TO 129+84.55														
129+84.55 TO 129+99.83						8122	790	4254	124	604	23		25	248
0+00.00 TO 41+40.34														
PRAIRIETOWN RD.								68					10	
SIDE ROAD (BASELINE 2)													14	
W. EIGHTH ST.													10	
W. SEVENTH ST.												55	10	
W. DAWSON ST.												67	14	
W. SIXTH ST. (EAST)												52	13	
W. SIXTH ST. (WEST)												54	13	
W. FIFTH ST.												51	10	
SPRING ST. (WEST)												50	10	
SPRING ST. (EAST)												58	10	
PAGE ST.												54	10	
W. HENRY ST. (EAST)												46	10	
W. HENRY ST. (WEST)												46	9	
MILL ST.												75	10	
PEARL ST.												55	14	
BLUFFS RD.												58	14	
S. FRANKLIN ST.												51	10	
HUSTON ST.												58	13	
S. HIBBARD ST.												62	15	
W. PEARL ST.												73	14	
MAIN ST. (WEST)								38				91	14	
MAIN ST. (EAST)								20				144	23	
NORTH ST. (WEST)													10	
NORTH ST. (EAST)												54	14	
MACOUPIN ST. (WEST)												55	10	
MACOUPIN ST. (EAST)												53	13	
W. OLIVE ST. (WEST)												48	12	
W. OLIVE ST. (EAST)												72	18	
W. PENNSYLVANIA ST. (WEST)												48	10	
W. PENNSYLVANIA ST. (EAST)												69	16	
W. LAFAYETTE (WEST)												54	10	
W. LAFAYETTE (EAST)												51	10	
CEDAR LANE												53	10	
W. PRAIRIE ST. (WEST)												50	10	
W. PRAIRIE ST. (EAST)												45	10	
PHILLIPS ST.												54	12	
BUNKER HILL RD.													14	
STAUNTON BUNKER HILL RD.	270		154			270		154					21	
(TRI875E)													15	
TOTALS		4346			118		21522		124	1838	2460		563	248

FILE NAME = c:\pwworking\vw\DOT\LAUGHLIN\LAUGHLIN\071789\0672018-sht-schedule.dgn

USER NAME = laughlinr1	DESIGNED -	REVISED -
	DRAWN -	REVISED -
PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -
PLOT DATE = Apr-14-2010 07:56:23AM	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: N.T.S. SHEET NO. 3 OF 3 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8139	(30,JRS-3)	MACOUPIN	45	7
CONTRACT NO. 72C18			ILLINOIS FED. AID PROJECT	