



MATCH LINE 323+00.00

URETHANE PAVEMENT MARKING
5" SOLID DOUBLE YELLOW

URETHANE PAVEMENT MARKING
5" WHITE SOLID (TYP)

STA 323+99.89
END URETHANE PAVEMENT MARKINGS
BEGIN THERMOPLASYIC PAVEMENT MARKINGS

SEC 31, 17N, R6W, 31-D PM

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B INLAID
5" YELLOW SKIP-DASH

THERMOPLASTIC PAVEMENT MARKING
5" SOLID DOUBLE YELLOW

THERMOPLASTIC PAVEMENT MARKING
5" SOLID YELLOW - LEFT

EXIST. CURVE 13
PI STA. = 325+72.83
 $\Delta = 89^\circ 23' 16''$ (LT)
D = 76° 24' 46"
R = 74.98'
T = 74.19'
L = 116.98'
E = 30.50'
@ = MATCH EXISTING
T.R. = N.A.
S.E. RUN = N.A.
P.C. STA. = 324+98.64
P.T. STA. = 326+15.62

TWO-WAY AMBER MARKER (TYP)

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B INLAID
5" YELLOW SKIP-DASH, RIGHT

MATCH LINE 330+00.00

FILE NAME = c:\pawork\pawdot\l\ajgh\inrl\dl17189\0672018-hrt-st-tping.dgn

USER NAME = laughlinr1	DESIGNED -	REVISED -
DRAWN -	REVISED -	
PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -
PLOT DATE = Apr-14-2010 09:56:04AM	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKING PLAN

SCALE: 1"=20' SHEET NO. 4 OF 25 SHEETS STA. 323+00.00 TO STA. 330+00.00

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8139	(30,JRS-3	MACOUPIN	45	29
CONTRACT NO. 72C18				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				