

CODE NO.	ITEM	UNIT	CONSTRUCTION CODE: 1000 FUNDING: 100% STATE			
			URBAN	FAP 658	FAP 662	FAP 666
			TOTAL	SECTION "A" OLD IL 29	SECTION "B" IL 4	SECTION "C" PEORIA RD.
81021590	CONDUIT, AUGERED 4" DIA., PVC	FOOT	291	--	291	--
81400100	HANDHOLE	EACH	3	--	3	--
81500120	GULFBOX JUNCTION, COMPOSITE CONCRETE	EACH	1	1	--	--
81500130	GULFBOX JUNCTION REMOVAL	EACH	1	1	--	--
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	113	--	113	--
86200200	UNINTERRUPTIBLE POWER SUPPLY, STANDARD	EACH	1	--	1	--
87100110	FIBER OPTIC CABLE IN CONDUIT, NO: 62.5/125, 6F	FOOT	3,598	1,799	1,799	--
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2,149	50	2,099	--
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	853	--	853	--
87301265	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 9C	FOOT	853	--	853	--
87502700	TRAFFIC SIGNAL POST, ALUMINUM 16 FT.	EACH	2	1	1	--
87702950	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 44 FT.	EACH	2	1	1	--
87703000	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 55 FT.	EACH	1	--	1	--
87703040	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 62 FT.	EACH	1	--	1	--
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6	3	3	--
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	41	41	--	--
87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	21	--	21	--
87900200	DRILL EXISTING HANDHOLE	EACH	3	--	3	--
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	26	20	6	--
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1	1	--	--
88040230	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1	1	--	--
88040270	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3 SECTION, 1-5 SECTION, BRACKET MOUNTED (SPECIAL)	EACH	3	3	--	--
88040310	SIGNAL HEAD, POLYCARBONATE, LED, 3-FACE, 1-3-SECTION, 2-5-SECTION, BRACKET MOUNTED	EACH	4	4	--	--
88200100	TRAFFIC SIGNAL BACKPLATE	EACH	94	41	53	--
88600100	DETECTOR LOOP, TYPE I	FOOT	12,625	5,940	6,685	--

\* SPECIALTY ITEM

FILE NAME =	USER NAME = laughlrr1	DESIGNED -	REVISED -
c:\pwwork\p\1001\LAUGH\INRL\dms47710\72C35-sht-500.dgn		DRAWN -	REVISED -
PLOT SCALE = 40.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = Apr-30-2010 09:13:18AM		DATE -	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

F.A.P. RTE. 658	SECTION *	COUNTY SANGAMON	TOTAL SHEETS 206	SHEET NO. 8
SCALE:			CONTRACT NO. 72C35	
SHEET NO. 5 OF 6 SHEETS		STA. TO STA.	ILLINOIS FED. AID PROJECT	