

SECTION "A" (OLD IL 29 / J. DAVID JONES / WALNUT) PATCHING						
CLASS D - 12"						
NORTH BOUND						
STATION	LOCATION	LENGTH (FT)	WIDTH (FT)	TY II, 12" (SQ YD)	TY III, 12" (SQ YD)	TY IV, 12" (SQ YD)
26+00	DL	10	11	12.22		
21+25	DL	6	11	7.33		
21+25	PL	6	11	7.33		
8+75	DL	25	11			30.56
8+75	PL	25	11			30.56
632+60	DL	5	11	6.11		
632+60	Parking Lane	5	9	5.00		
630+00	DL	20	11		24.44	
630+00	Parking Lane	20	9		20.00	
629+50	DL	5	11	6.11		
629+50	Parking Lane	5	9	5.00		
626+90	DL	6	11	7.33		
626+90	Parking Lane	6	9	6.00		
TOTALS				62	44	61
MEDIAN TURN LANE						
STATION	LOCATION	LENGTH (FT)	WIDTH (FT)	TY II, 12" (SQ YD)		
21+25	MTL	6	11	7.33		
11+40	MTL	6	11	7.33		
TOTALS				15		
SOUTH BOUND						
STATION	LOCATION	LENGTH (FT)	WIDTH (FT)	TY II, 12" (SQ YD)	TY III, 12" (SQ YD)	TY IV, 12" (SQ YD)
22+80	DL	15	11		18.33	
21+90	DL	50	11			61.11
21+25	DL	6	11	7.33		
21+25	PL	6	11	7.33		
11+40	DL	6	11	7.33		
11+40	PL	6	11	7.33		
632+60	DL	5	11	6.11		
632+60	Parking Lane	5	9	5.00		
626+90	DL	6	11	7.33		
626+90	Parking Lane	6	9	6.00		
TOTALS				54	18	61

SECTION "B" (IL 4 / VETERANS PKWY) PATCHING									
CLASS A - 8"									
SOUTH BOUND									
STATION	LOCATION	LENGTH (FT)	WIDTH (FT)	PATCH REINF. (SQ YD)	SAW CUTS (FT)	TIE BARS (EACH)	TY II, 8" (SQ YD)	TY IV, 8" (SQ YD)	
109+60	PL	20	12	26.67	76	10		26.67	
110+20	DL	10	12	13.33	56		13.33		
110+20	PL	30	12	40.00	96	15		40.00	
111+25	PL	20	12	26.67	76	10		26.67	
TOTALS				107	304	35	13	93	
STATION	LOCATION	LENGTH (FT)	WIDTH (FT)	PATCH REINF. (SQ YD)	SAW CUTS (FT)	TIE BARS (EACH)	TY II, 11" (SQ YD)	TY III, 11" (SQ YD)	TY IV, 11" (SQ YD)
103+00	NB LTL	8	12	10.67	52		10.67		
103+80	NB LTL	22	12	29.33	80	11			29.33
104+00	NB LTL	14	12	18.67	64			18.67	
104+70	NB DL	6	12	8.00	48		8.00		
106+30	NB PL	6	12	8.00	48		8.00		
TOTALS				74	292	11	27	19	29