

ENTRANCE & SIDE ROAD RESURFACING SCHEDULE WITH INCIDENTAL MIX										
DESCRIPTION	STATION TO STATION		LENGTH	AVG. PAVT. WIDTH	PAVEMENT AREA	PREP. OF BASE	BUTT JOINT	BIT MAT PRIMECOAT	AGG PRIMECOAT	INCIDENTAL BIT. SURF
			(FT)	(FT)	(SQYD)	(SQYD)	(SQYD)	(TON)	(TON)	(TON)
HMA / CE	558+43	558+90	20	39	86	86	86	0.1	0.2	12
HMA / CE	583+00	583+32	20	23	50	50	50	0.1	0.1	7
HMA / CE	595+65	596+30	20	55	121	121	121	0.1	0.2	17
YATES AVE										
EAST	10+33	10+53	20	41	91	91	91	0.1	0.2	13
WEST	9+56	9+66	10	36	40	40	40	0.1	0.1	6
MAPLE AVE										
MAIN LINE	10+34	10+54	20	53	118	118	118	0.1	0.2	16
ELLIOT AVE.										
EAST	10+20	10+40	20	38	84	84	84	0.1	0.2	12
WEST	9+60	9+80	20	38	84	84	84	0.1	0.2	12
CALHOUN ST.										
EAST	100+20	100+40	20	53	117	117	117	0.1	0.2	16
WEST	99+60	99+80	20	40	89	89	89	0.1	0.2	12
HAY ST.										
MAIN LINE	100+20	100+40	20	40	89	89	89	0.1	0.2	12
DORLAN AVE										
MAIN LINE	100+20	100+40	20	42	93	93	93	0.1	0.2	13
HERNDON ST										
MAIN LINE	100+20	100+40	20	31	69	69	69	0.1	0.1	10
MILLER ST.										
EAST	100+20	100+42	56	26	159	159	159	0.1	0.3	22
WEST	100+20	100+46	45	28	138	138	138	0.1	0.3	19
REYNOLDS ST.										
MAIN LINE	100+25	100+55	30	42	140	140	140	0.1	0.3	20
CARPENTER ST.										
WEST	99+46	99+74	28	42	131	131	131	0.1	0.3	18
SIDE ROAD RESURFACING SCHEDULE WITH INCIDENTAL MIX TOTALS						1,698	1,698	2	3	238

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
et:\pwork\pwork\LAUGHLINRL\dms47710\0672C35-sht-schedule.dgn		DRAWN -	REVISED -
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = Apr-30-2010 09:16:34AM	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES
SECTION "A" (IL 29)**

SCALE: SHEET NO. 4 OF 7 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
658	•	SANGAMON	206	23
			CONTRACT NO. 72C35	
ILLINOIS FED. AID PROJECT				