

SECTION "C" PEORIA RD. PAVEMENT MARKING SCHEDULE

DESCRIPTION	STATION TO STATION	LENGTH (FT)	5" WHITE EDGE LINE	5" YELLOW EDGE LINE	5" YELLOW EDGE LINE	5" YELLOW SKIP DASH	24" WHITE STOP BARS	LETTERS & SYMBOLS	2'x6'x6" SKIP DASH	5" WHITE SKIP DASH	RAISED REFL. PAVT MARKERS	RAISED REFL. PAVT MARKER	CENTERLINE	EDGE OF PAVEMENT	24" STOP BAR	EDGE OF PAVEMENT	
SOUTHBOUND LANES																	
MAIN LINE	412+17	412+27	10	10	--	--	--	--	--	3	1	1	1	9	--	2	
MAIN LINE	406+90	412+17	527	527	--	--	--	--	--	132	7	7	53	50	--	17	
MAIN LINE	404+19	406+90	271	271	271	--	--	--	--	68	3	3	27	30	--	9	
MAIN LINE	400+40	404+19	379	249	--	--	--	--	--	95	5	5	38	28	--	11	
MAIN LINE	398+95	400+40	145	89	--	--	--	--	--	36	2	2	15	--	--	2	
MAIN LINE	398+20	398+95	75	--	--	--	--	24	--	19	1	1	8	--	144	25	
MAIN LINE	154+90	156+03	113	113	88	--	--	--	--	28	1	1	11	--	--	2	
MAIN LINE	151+34	154+90	356	356	366	--	--	--	--	89	4	4	36	--	--	6	
MAIN LINE	144+00	151+34	734	--	--	744	144	--	--	184	18	18	73	--	--	12	
STA. EQN 15+17.25BK = 144+00.00AH																	
MAIN LINE	14+50	15+17	67	--	--	67	--	--	--	17	2	2	7	--	--	1	
MAIN LINE	1+57	14+50	1293	--	--	1293	--	--	--	323	32	32	129	--	--	22	
STA. EQN 78+45.12BK = 1+56.70AH																	
MAIN LINE	52+55	78+45	2590	--	--	2590	--	--	--	648	65	65	259	--	--	43	
MAIN LINE	52+50	52+55	5	--	--	5	--	--	--	1	4	4	1	--	--	1	
MAIN LINE	52+40	52+50	10	--	--	10	--	--	--	3	4	4	1	--	--	1	
PEORIA RD. / WATERWORKS RD. TURN LANES																	
LEFT TURN	409+45	411+70	225	--	300	--	--	--	68	--	--	--	--	--	--	--	
LEFT TURN	407+86	409+45	159	--	159	--	--	31	--	--	--	--	--	--	--	--	
LEFT TURN	407+34	407+86	52	--	--	--	--	--	--	--	--	--	--	--	--	--	
PEORIA RD. / IL 4/VETERANS AVE. TURN LANES																	
RIGHT TURN	497+76	498+07	52	82	--	--	--	18	16	--	1	1	--	--	108	18	
RIGHT TURN	399+87	401+75	185	185	--	--	--	--	46	--	2	2	--	--	--	--	
RIGHT TURN	398+37	399+87	150	166	--	--	--	20	31	--	--	--	--	--	120	20	
LEFT TURN	401+19	404+15	296	--	--	--	--	--	78	--	4	4	--	--	--	--	
LEFT TURN	401+19	404+15	296	--	296	--	--	--	--	--	4	4	--	--	--	--	
LEFT TURN	398+38	401+19	281	281	--	--	--	16.3	62	--	4	4	--	--	98	16	
LEFT TURN	398+38	401+19	281	281	281	--	--	12	62	27	4	4	--	--	72	12	
SOUTHBOUND TOTALS				2610	1761	4710	144	90	203	219	1644	168	168	658	117	542	220
SIDEROADS																	
TAINTOR RD. (WEST)	13+10	14+79	20	--	--	--	--	31	--	--	--	--	--	--	185	--	
WATERWORKS RD.	407+00	407+90	16	--	--	--	--	37	--	--	--	--	--	--	222	--	
COLORPLANT RD.																	
SOUTHBOUND LANES																	
MAIN LINE	310+12	311+44	132	--	92	--	--	12	26	--	--	--	--	--	72	--	
NORTHBOUND LANES																	
MAIN LINE	310+12	311+44	132	--	92	--	--	--	--	--	--	--	--	--	--	--	
PEORIA RD. / COLORPLANT RD TURN LANES																	
RIGHT TURN	310+12	311+44	132	51	--	--	--	18	--	--	--	--	--	--	108	--	
TOTALS				5578	3628	9419	287	224	510	317	3216	330	330	1366	862	1345	482

ISLAND PAVEMENT MARKINGS	URETHANE			
	STATION TO STATION		8" WHITE	12" WHITE
PEORIA RD/TAINTOR RD (w)	9+25	9+85	130	29
PEORIA RD/VETERANS VETERANS AVE. (sw)	155+30	155+96	225	162
PEORIA RD/VETERANS VETERANS AVE. (se)	155+51	156+17	165	52
PEORIA RD/VETERANS COLORPLANT RD (nw)	310+08	310+64	187	86
PEORIA RD/VETERANS COLORPLANT RD (ne)	310+14	310+85	224	152
TOTALS			931	480

MEDIAN/GORE AREA PVT MKG	URETHANE					
	STATION TO STATION		5" YELLOW	8" WHITE	12" WHITE	12" YELLOW
PEORIA RD	155+70	155+85	41	--	--	14
PEORIA RD	498+40	500+86	214	--	--	67
PEORIA RD	398+36	400+41	210	--	--	74
PEORIA RD	400+41	401+15	--	154	17	--
PEORIA RD	505+84	507+80	--	395	45	--
PEORIA RD	407+57	409+19	--	333	27	--
TOTALS			465	882	89	155

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
et:\pwwork\pwidot\LAUGHLINRL\dms47710\672C35-sht-schedule.dgn		DRAWN -	REVISED -
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = Apr-30-2010 11:14:43AM	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
PAVEMENT MARKING - SECTION "C" (PEORIA RD.)			
SCALE:	SHEET NO. 2 OF 2 SHEETS	STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
658	*	SANGAMON	206	38
CONTRACT NO.			72C35	
ILLINOIS FED. AID PROJECT				