



STA 222+19.10 IL 4(VET1) =  
STA 18+48.87 BROWNING\_RD

EXIST. CURVE 84  
PI STA. = 16+60.16  
Δ = 42° 03' 33" (RT)  
D = 5° 00' 00"  
R = 1,145.93'  
T = 440.56'  
L = 841.19'  
E = 81.77'  
e = 6.0%  
T.R. = 40'  
S.E. RUN = 160'  
P.C. STA. = 12+19.60  
P.T. STA. = 20+60.79

EXIST. CURVE 11  
PI STA. = 224+54.24  
Δ = 13° 36' 00" (RT)  
D = 1° 20' 00"  
R = 4,297.20'  
T = 512.41'  
L = 1,020.00'  
E = 30.44'  
e = 3.6%  
T.R. = 67'  
S.E. RUN = 160'  
P.C. STA. = 219+41.83  
P.T. STA. = 229+61.84

**LEGEND**

- |                            |   |
|----------------------------|---|
| ① URETHANE- 5" YELLOW      | ⑨ THERMOPLASTIC- 12" YELLOW                             |
| ② URETHANE- 5" WHITE       | ⑩ THERMOPLASTIC- 12" WHITE                              |
| ③ URETHANE- 8" WHITE       | ⑪ PREFORMED PLASTIC TYPE B- INLAID- LETTERS AND SYMBOLS |
| ④ URETHANE- 12" YELLOW     | ⑫ PREFORMED PLASTIC TYPE B- INLAID - 5" YELLOW          |
| ⑤ URETHANE-12" WHITE       | ⑬ PREFORMED PLASTIC TYPE B- INLAID - 5" WHITE           |
| ⑥ THERMOPLASTIC- 5" YELLOW | ⑭ PREFORMED PLASTIC TYPE B- INLAID - 6" WHITE           |
| ⑦ THERMOPLASTIC- 5" WHITE  | ⑮ PREFORMED PLASTIC TYPE B- INLAID - 24" WHITE          |
| ⑧ THERMOPLASTIC- 8" WHITE  |   |

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
et:\pw\work\PWIDOT\LAUGHLINRL\dms47710\672C35-shp1en-14.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**PLAN VIEW - SECTION "B" (IL 4 / VETERANS PKWY)**

SCALE:      SHEET NO. 8 OF 20 SHEETS      STA.      TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
658	.	SANGAMON	206	92
CONTRACT NO. 72C35				
ILLINOIS FED. AID PROJECT				

• 1-1(RS,TS-127RS-6)79Z&102RS-4