



EXIST. CURVE 13  
 PI STA. = 267+36.92  
 $\Delta = 34^\circ 00' 00''$  (RT)  
 $D = 1^\circ 28' 00''$   
 $R = 3,906.54'$   
 $T = 1,194.35'$   
 $L = 2,318.19'$   
 $E = 178.50'$   
 $e = 3.6\%$   
 $T.R. = 66.67'$   
 $S.E. RUN = 160'$   
 $P.C. STA. = 255+42.57$   
 $P.T. STA. = 278+60.76$

**LEGEND**

- |                            |   |
|----------------------------|---|
| ① URETHANE- 5" YELLOW      | ⑨ THERMOPLASTIC- 12" YELLOW                             |
| ② URETHANE- 5" WHITE       | ⑩ THERMOPLASTIC- 12" WHITE                              |
| ③ URETHANE- 8" WHITE       | ⑪ PREFORMED PLASTIC TYPE B- INLAID- LETTERS AND SYMBOLS |
| ④ URETHANE- 12" YELLOW     | ⑫ PREFORMED PLASTIC TYPE B- INLAID - 5" YELLOW          |
| ⑤ URETHANE-12" WHITE       | ⑬ PREFORMED PLASTIC TYPE B- INLAID - 5" WHITE           |
| ⑥ THERMOPLASTIC- 5" YELLOW | ⑭ PREFORMED PLASTIC TYPE B- INLAID - 6" WHITE           |
| ⑦ THERMOPLASTIC- 5" WHITE  | ⑮ PREFORMED PLASTIC TYPE B- INLAID - 24" WHITE          |
| ⑧ THERMOPLASTIC- 8" WHITE  |   |

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
et:\pwork\pwidot\LAUGHLINRL\dms47710\672C35-shp1en-14.dgn		DRAWN -	REVISED -
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = Apr-30-2010 02:33:34PM	DATE -	REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**PLAN VIEW - SECTION "B" (IL 4 /VETERANS PKWY)**  
 SCALE: SHEET NO. 14 OF 20 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
658	.	SANGAMON	206	98
ILLINOIS FED. AID PROJECT			CONTRACT NO. 72C35	

\* 1-1(RS,TS-1027RS-6)79Z&102RS-4