



- 1 EXISTING CONTROLLER AND CABINET SHALL BE USED FOR TEMPORARY TRAFFIC SIGNAL INSTALLATION. EXISTING DETECTOR RACKS AND INDUCTIVE LOOP DETECTORS SHALL BE REMOVED FROM CABINET AND THE PROPOSED VIDEO VEHICLE DETECTION SYSTEM INSTALLED PRIOR TO PLACING THE TEMPORARY TRAFFIC SIGNAL INSTALLATION IN TO OPERATION.
- 2 EXISTING CONTROL CABINET ANCHOR BOLTS SHALL BE LOOSENED AND CABINET BLOCKED TO ALLOW TEMPORARY SIGNAL CABLES ACCESS TO THE CONTROL PANEL. BLOCKING AND PROTECTION FROM RODENTS AND WEATHER AROUND THE CABINET BASE SHALL BE TO THE SATISFACTION OF THE ENGINEER.
- 3 TEMPORARY SIGNALS SHALL BE OPERATIONAL PRIOR TO REMOVAL OF EXISTING SIGNALS.
- 4 POLES SHALL BE GUYED OR ANCHORED TO THE SATISFACTION OF THE ENGINEER. ANY ADJUSTMENTS SHALL BE CONSIDERED PART OF THE PAY ITEM FOR TEMPORARY TRAFFIC SIGNAL INSTALLATION.
- 5 POLES USED FOR TEMPORARY SIGNAL INSTALLATION SHALL PROVIDE FOR A MINIMUM 35 FT. MOUNTING HEIGHT FOR THE VIDEO CAMERAS.
- 6 EXISTING SERVICE TO BE UTILIZED FOR TEMPORARY AND PROPOSED SIGNALS.
- 7 ALL SIGNAL AND DETECTOR CABLE SHALL BE REMOVED BETWEEN CONTROLLER AND DOUBLE HANDHOLE AND DOUBLE HANDHOLE AND NEXT EXISTING HANDHOLE. CABLE BETWEEN HANDHOLE IN SE ISLAND AND SE CORNER SHALL BE REMOVED. THE REMAINING CABLE MAY BE ABANDONED IN PLACE.
- 8 EXISTING INTERCONNECT CABLE TO BE REMOVED COMPLETELY TO BROWNING ROAD NORTH AND BROWNING ROAD EAST.
- 9 VIDEO DETECTION SYSTEM CAMERAS WILL BE REUSED IN THE PROPOSED TRAFFIC SIGNAL INSTALLATION. INSTALLING AND PLACING INTO OPERATION DURING TEMPORARY SIGNAL INSTALLATION STAGE WILL BE INCLUDED IN "TEMPORARY TRAFFIC SIGNAL INSTALLATION" PAY ITEM. RELOCATING AND PLACING INTO OPERATION FOR PROPOSED SIGNAL INSTALLATION WILL BE INCLUDED IN "VIDEO VEHICLE DETECTION SYSTEM" PAY ITEM.

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
et:\pw\work\PWIDOT\LAUGHLINRL\0203328\0672C35.sht.ts_29.dgn		DRAWN -	REVISED -
	PLOT SCALE = 40.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = Apr-29-2010 03:00:48PM	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**PROPOSED TEMPORARY SIGNALS PLAN
IL 29 (J. DAVID JONES PKWY.) & IL 4 (VETERANS PKWY.)**

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
* 1-1RS,TS-1, 2TRS-6, 102RS-4		SANGAMON	206	195
* FAP 666 (IL-55), FAP 662 (IL 4)		CONTRACT NO. 72C35		
* FAP 658 (IL 29)		ILLINOIS FED. AID PROJECT		

SCALE: SHEET NO. 25 OF 33 SHEETS STA. TO STA.