

DRAINAGE SCHEDULE													
LOCATION	GUTTER REMOVAL	CONCRETE GUTTER TYPE A	TRENCH BACKFILL SPECIAL	PIPE CULVERT CLASS A TYPE 1			PRC FLARED END SECTION			STONE DUMPED RIPRAP CLASS A4 SPECIAL	RIPRAP SLURRY	MANHOLES TYPE A 4' DIAMETER W/MED. INLET (604101)	INSERTION CULVERT LINER 42"
				24"	30"	36"	24"	30"	36"				
ILLINOIS 107:	FOOT	FOOT	CU YD	FOOT			EACH			TON	SQ YD	EACH	FOOT
STA. 186+80			60			60			2	23	46		
STA. 307+20										50	100		152
STA. 406+55	40	40	52	67			1			26	53	1	
STA. 407+92	40	40	37	60			1			37	76	1	
STA. 514+30			67		60			2		32	62		
TOTAL =	80	80	216	127	60	60	2	2	2	168	337	2	152

GUARDRAIL SCHEDULE				
LOCATION	SPBGR TYPE A 9' POST	TBT TYPE 1 (SPECIAL) TANGENT	REMOVAL AND REPLACEMENT OF SPBGR RAIL ELEMENT	GUARDRAIL REMOVAL
ILLINOIS 107:	FOOT	EACH	FOOT	FOOT
RT. STA. 283+65 TO RT. STA. 285+65		2		100
LT. STA. 284+45 TO LT. STA. 286+45		2		100
RT. STA. 292+60 TO RT. STA. 295+60		2		100
LT. STA. 293+25 TO LT. STA. 295+25		2		100
RT. STA. 305+70 TO RT. STA. 307+20	50	2		150
LT. STA. 306+00 TO LT. STA. 308+00	100	2		200
RT. STA. 356+25 TO RT. STA. 361+75		2	12.5	100
LT. STA. 359+50 TO LT. STA. 361+50		2		100
RT. STA. 382+55			25	
LT. STA. 399+22 TO LT. STA. 400+72		2		100
RT. STA. 415+50 TO RT. STA. 417+75	125	2		225
TOTAL =	275	20	37.5	1275