

LOCATION	TEMPORARY PAVEMENT MARKING- LINES 5"			TEMPORARY PM - LINE 8"	TEMPORARY PAVEMENT MARKING - LINES 12"		
	SOLID WHITE FOOT	SOLID YELLOW FOOT	SKIP DASH YELLOW FOOT		WHITE FOOT	WHITE FOOT	YELLOW FOOT
	US 54						
STA 51+66.96 TO STA 60+11.65	0	1,709	363	0	0	45	
STA 60+11.65 TO STA 69+11.40	0	1,743	223	0	0	0	
STA 69+11.40 TO STA 75+56.70	0	1,336	197	0	0	49	
STA 75+56.70 TO STA 98+90.28	0	4,464	1,116	0	0	0	
STA 98+90.28 TO STA 133+91.52	0	7,003	1,554	0	0	49	
STA 133+91.52 TO STA 140+00.00	1,217	2,014	0	0	0	0	
STA 140+00.00 TO STA 204+83.11	12,966	1,342	1,621	0	0	0	
STA 204+83.11 TO STA 210+64.36	1,163	2,024	0	0	0	152	
STA 210+64.36 TO STA 219+00.00	1,671	2,690	0	0	0	139	
STA EQN: 219+00.00 (BK) = STA 809+70.99 (AH) Note Stationing is reversed. STA 809+70.99 TO STA 761+52.00	9,638	5,692	805	0	0	0	
SHETLAND DR ISLAND	0	0	0	104	32	0	
IL 106							
STA 10+59.00 TO STA 17+58.09	1,398	1,398	0	0	0	0	
STA EQN: 17+58.09 (BK) = STA 215+53.38 (AH) STA 215+53.38 TO STA 216+30.00	153	153	0	0	0	0	
US 54 IL 106 NE QUAD ISLAND	0	0	0	179	77	0	
US 54 IL 106 SW QUAD ISLAND	0	0	0	169	68	0	
COLUMN TOTALS	28,206	31,569	5,878	452	177	434	
TOTALS	65,653			452	611		

LOCATION	THERMOPLASTIC PAVEMENT MARKING- LINES 5"			THERMO PM - LINE 8"	THERMOPLASTIC PAVEMENT MARKING - LINES 12"		
	SOLID WHITE FOOT	SOLID YELLOW FOOT	SKIP DASH YELLOW FOOT		WHITE FOOT	WHITE FOOT	YELLOW FOOT
	US 54						
STA 51+66.96 TO STA 60+11.65	0	1,709	363	0	0	45	
STA 60+11.65 TO STA 69+11.40	0	1,743	223	0	0	0	
STA 69+11.40 TO STA 75+56.70	0	1,336	197	0	0	49	
STA 75+56.70 TO STA 98+90.28	0	4,464	1,116	0	0	0	
STA 98+90.28 TO STA 133+91.52	0	7,003	1,554	0	0	49	
STA 133+91.52 TO STA 140+00.00	1,217	2,014	0	0	0	0	
STA 140+00.00 TO STA 204+83.11	1,163	2,024	0	0	0	152	
STA 204+83.11 TO STA 210+64.36	1,671	2,690	0	0	0	139	
STA 210+64.36 TO STA 219+00.00							
IL 106							
STA 10+59.00 TO STA 17+58.09	1,398	1,398	0	0	0	0	
STA EQN: 17+58.09 (BK) = STA 215+53.38 (AH) STA 215+53.38 TO STA 216+30.00	153	153	0	0	0	0	
SHETLAND DR ISLAND	0	0	0	104	32	0	
US 54 IL 106 NE QUAD ISLAND	0	0	0	179	77	0	
US 54 IL 106 SW QUAD ISLAND	0	0	0	169	68	0	
COLUMN TOTALS	5,602	24,535	3,452	452	177	434	
TOTALS	33,589			452	611		

TEMPORARY PAVEMENT MARKING - LINE 6"		LENGTH (FOOT)
LOCATION		
WHITE TURN LANES		
US 54		
STA 60+40 TO STA 61+55	115.00	
STA 61+55 TO STA 62+64	27.25	
STA 73+54 TO STA 74+04	12.50	
STA 74+04 TO STA 75+04	100.00	
STA 99+35 TO STA 100+35	100.00	
STA 132+42 TO STA 133+42	100.00	
STA 134+42 TO STA 135+17	75.00	
STA 204+83 TO STA 206+87	50.97	
STA 206+87 TO STA 209+96	309.00	
STA 211+08 TO STA 212+08	100.00	
STA 212+08 TO STA 213+88	45.00	
TOTAL	1,035	

TEMPORARY PAVEMENT MARKING - LINE 24"		LENGTH (FOOT)
LOCATION		
WHITE STOP BARS		
US 54		
STA 68+61	24.00	
STA 69+31	31.00	
IL 106		
STA 10+25	12.00	
STA 10+59	18.00	
SHETLAND DR		
STA 0+28	18.00	
STA 0+31	14.00	
VALLEY VIEW DR		
STA 0+40	18.00	
TOTAL	135	

PAINT PAVEMENT MARKING - LINE 5"				FOOT
LOCATION				
US 54				
WHITE EDGE LINE				
RT STA 140+00 TO STA 191+41	5,141			
STA 191+41 TO STA 204+83	1,342			
STA 809+71 TO STA 785+20	2,451			
STA 785+20 TO STA 761+52	2,368			
WHITE EDGE LINE				
LT STA 140+00 TO STA 191+41	5,141			
STA 191+41 TO STA 204+83	1,342			
STA 809+71 TO STA 785+20	2,451			
STA 785+20 TO STA 761+52	2,368			
YELLOW NO PASSING ZONE				
RT STA 191+41 TO STA 204+83	1,342			
STA 795+64 TO STA 770+11	2,553			
LT STA 809+71 TO STA 802+28	743			
STA 785+78 TO STA 761+82	2,396			
YELLOW SKIP DASH				
STA 140+00 TO STA 204+83	1,621			
STA 809+71 TO STA 785+78	598			
STA 770+11 TO STA 761+82	207			
TOTAL	32,065			

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6"		LENGTH (FOOT)
LOCATION		
WHITE TURN LANES		
US 54		
STA 60+40 TO STA 61+55	115.00	
STA 61+55 TO STA 62+64	27.25	
STA 73+54 TO STA 74+04	12.50	
STA 74+04 TO STA 75+04	100.00	
STA 99+35 TO STA 100+35	100.00	
STA 132+42 TO STA 133+42	100.00	
STA 134+42 TO STA 135+17	75.00	
STA 204+83 TO STA 206+87	50.97	
STA 206+87 TO STA 209+96	309.00	
STA 211+08 TO STA 212+08	100.00	
STA 212+08 TO STA 213+88	45.00	
TOTAL	1,035	

HOT-MIX ASPHALT SURFACE REMOVAL 2"	LENGTH (FOOT)	PAV' T/ SHLDR WIDTH (FOOT)	AREA (SQ YD)
LOCATION			
US 54			
RT STA 51+66.96 TO RT STA 134+51.00	8284.04	18	16,568.1
LT STA 51+66.96 TO LT STA 134+60.00	8293.04	18	16,586.1
RT STA 134+51.00 TO RT STA 136+00.00	149.00	18	298.0
RT STA 136+00.00 TO RT STA 139+50.00	350.00	21	680.6
RT STA 139+50.00 TO RT STA 140+00.00	50.00	14	77.8
LT STA 134+60.00 TO LT STA 136+00.00	140.00	18	280.0
LT STA 136+00.00 TO LT STA 139+50.00	350.00	21	680.6
LT STA 139+50.00 TO LT STA 140+00.00	50.00	14	77.8
RT STA 801+00.00 TO RT STA 796+31.00	469.00	16	833.8
LT STA 801+00.00 TO LT STA 796+55.00	445.00	16	791.1
RT STA 796+31.00 TO RT STA 789+55.00	676.00	13	976.4
LT STA 796+55.00 TO LT STA 790+75.00	580.00	13	837.8
RT STA 789+55.00 TO RT STA 781+24.00	831.00	16	1,477.3
LT STA 790+75.00 TO LT STA 781+24.00	951.00	16	1,690.7
SHETLAND DR			
STA 0+18.00 TO STA 0+68.00		CADD	398.7
VALLEY VIEW			
STA 0+18.00 TO STA 0+48.00		CADD	123.2
TOTAL			42,378

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"		LENGTH (FOOT)
LOCATION		
WHITE STOP BARS		
US 54		
STA 68+61	24.00	
STA 69+31	31.00	
IL 106		
STA 10+25	12.00	
STA 10+59	18.00	
SHETLAND DR		
STA 0+30	18.00	
STA 0+46	14.00	
VALLEY VIEW DR		
STA 0+40	18.00	
TOTAL	135	

SEE ENTRANCE DETAIL FOR ENTRANCE SCHEDULES

SEE TRAFFIC SIGNAL PLANS FOR DETECTOR LOOP QUANTITIES

FILE NAME =	USER NAME = coxte	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES (FAP) 321 US 54				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
es:\pwork\p\WIDOT\COXTE\dms62291\sh-t-schedule.dgn		DRAWN -	REVISED -		321	106RS-5, 18RS-11	PIKE	41	16				
PLOT SCALE = 100.0000' / IN.		CHECKED -	REVISED -		CONTRACT NO. 72C43				ILLINOIS FED. AID PROJECT				
PLOT DATE = Mar-11-2010 09:50:51AM		DATE -	REVISED -		SCALE:	SHEET NO.	OF SHEETS	STA.	TO STA.				