

INCIDENTAL HOT-MIX ASPHALT SURFACING, 2" DEPTH FOR SIDEROADS

LOCATION (SIDEROADS)	SURFACE AREA (BY CADD) (SQUARE FOOT)	SURFACE AREA (SQUARE YARD)	INCIDENTAL HMA SURFACE COURSE, 2" (TON)	AGGREGATE PRIME COAT (TON)	BITUMINOUS PRIME COAT (TON)
IL RTE. 16 / IL RTE. 127					
WOOD STREET (EAST)	937.6	104.2	11.7	0.21	0.04
WOOD STREET (EAST)	812.2	90.2	10.1	0.18	0.03
TILSON STREET	1,411.9	156.9	17.6	0.31	0.06
MILL STREET	682.5	75.8	8.5	0.15	0.03
PLEASANT STREET	610.4	67.8	7.6	0.14	0.03
SUB-TOTALS =	4,454.6	495.0	55.4	0.99	0.19
IL RTE. 16					
ROUNTREE STREET (NORTH)	996.1	110.7	12.4	0.22	0.04
ROUNTREE STREET (SOUTH)	899.0	99.9	11.2	0.20	0.04
CHASE STREET	867.6	96.4	10.8	0.19	0.04
LAKEVIEW DRIVE	216.0	24.0	2.7	0.05	0.01
CRITTENDEN STREET	NO WORK	0.0	0.0	0.00	0.00
PRESTON STREET	673.7	74.9	8.4	0.15	0.03
ECCLES STREET (NORTH)	NO WORK	0.0	0.0	0.00	0.00
ECCLES STREET (SOUTH)	778.4	86.5	9.7	0.17	0.03
LEVA STREET	783.9	87.1	9.8	0.17	0.03
ANNA STREET	834.8	92.8	10.4	0.19	0.04
VIRGINIA STREET (NORTH)	265.2	29.5	3.3	0.06	0.01
VIRGINIA STREET (SOUTH)	836.1	92.9	10.4	0.19	0.04
ALLEY	97.8	10.9	1.2	0.02	0.00
PARK STREET	1,018.8	113.2	12.7	0.23	0.04
CENTRE STREET	861.1	95.7	10.7	0.19	0.04
SUB-TOTALS =	9,128.5	1,014.3	113.6	2.03	0.39
IL RTE. 127					
EAST TREMONT STREET	1,485.9	165.1	18.5	0.33	0.06
WEST TREMONT STREET	1,075.0	119.4	13.4	0.24	0.05
SUMMER STREET (EAST)	1,293.6	143.7	16.1	0.29	0.05
SUMMER STREET (WEST)	1,291.8	143.5	16.1	0.29	0.05
JEFFERSON LANE	859.6	95.5	10.7	0.19	0.04
EAST FAIRGROUNDS AVENUE	2,598.7	288.7	32.3	0.58	0.11
WEST FAIRGROUNDS AVENUE	2,736.1	304.0	34.0	0.61	0.12
VANDALIA STREET	1,201.2	133.5	14.9	0.27	0.05
ROUNTREE STREET	2,314.2	257.1	28.8	0.51	0.10
EAST MECHANIC STREET	2,320.4	257.8	28.9	0.52	0.10
HILLTOP ROAD	986.1	109.6	12.3	0.22	0.04
IDA STREET	644.0	71.6	8.0	0.14	0.03
HUBER STREET	665.3	73.9	8.3	0.15	0.03
FIRST STREET	1,508.5	167.6	18.8	0.34	0.06
EAST WILLOW AVENUE	2,590.8	287.9	32.2	0.58	0.11
SENATOR MILLER DRIVE	3,136.9	348.5	39.0	0.70	0.13
SUB-TOTALS =	26,708.1	2,967.6	332.4	5.94	1.13
GRAND TOTALS =	40,291.2 SQ FT	4,476.8 SQ YD	501.4 TONS	8.95 TONS	1.70 TONS

TEMPORARY RAMPS

LOCATION	RAMP LENGTH (FOOT)	SURFACE AREA, 7.0' APPRON (BY CADD) (SQUARE FOOT)	SURFACE AREA (SQUARE YARD)
IL RTE. 16 / IL RTE. 127			
BEGINNING OF PROJECT	27	189.0	21.0
WOOD ST. (EAST)	30	210.0	23.3
WOOD ST. (WEST)	20	140.0	15.6
TILSON STREET	18	126.0	14.0
MAIN STREET	30	210.0	23.3
MILL STREET	19	133.0	14.8
PLEASANT STREET	28	196.0	21.8
SUB-TOTALS =	172	1,204.0	133.8
IL RTE. 16			
ROUNTREE STREET (NORTH)	28	196.0	21.8
ROUNTREE STREET (SOUTH)	30	210.0	23.3
CHASE STREET	27	189.0	21.0
LAKEVIEW DRIVE	11	77.0	8.6
WEST SIDE OF STRUCTURE	29	203.0	22.6
EAST SIDE OF STRUCTURE	29	203.0	22.6
CRITTENDEN STREET	0	0.0	0.0
PRESTON STREET	27	189.0	21.0
ECCLES STREET (NORTH)	0	0.0	0.0
ECCLES STREET (SOUTH)	25	175.0	19.4
LEVA STREET	30	210.0	23.3
ANNA STREET	28	196.0	21.8
VIRGINIA STREET (NORTH)	24	168.0	18.7
VIRGINIA STREET (SOUTH)	25	175.0	19.4
ALLEY	11	77.0	8.6
PARK STREET	36	252.0	28.0
CENTRE STREET	25	175.0	19.4
END OF PROJECT	29	203.0	22.6
SUB-TOTALS =	414	2,898.0	322.0
IL RTE. 127			
EAST TREMONT STREET	32	224.0	24.9
WEST TREMONT STREET	20	140.0	15.5
SUMMER STREET (EAST)	24	168.0	18.7
SUMMER STREET (WEST)	24	168.0	18.7
JEFFERSON LANE	18	126.0	14.0
EAST FAIRGROUNDS AVENUE	24	168.0	18.7
WEST FAIRGROUNDS AVENUE	24	168.0	18.7
VANDALIA STREET	13	91.0	10.1
ROUNTREE STREET	32	224.0	24.9
EAST MECHANIC STREET	24	168.0	18.7
HILLTOP ROAD	27	189.0	21.0
IDA STREET	34	238.0	26.4
HUBER STREET	36	252.0	28.0
FIRST STREET	25	175.0	19.4
EAST WILLOW AVENUE	29	203.0	22.6
SENATOR MILLER DRIVE	42	294.0	32.7
END OF PROJECT	23	161.0	17.9
SUB-TOTALS =	451	3,157.0	350.8
GRAND TOTALS=	1,037 FEET	7,259.0 SQ FT	806.6 SQ YD

*-20RS-7, 21RS-6, 104RS, 105RS-4
**-325, 42

FILE NAME =	USER NAME = laughlinr1	DESIGNED - RTS	REVISED -
es:\pwork\PWIDOT\LAUGHLINRL\10105356\1072C52-ah-schedule.dgn		DRAWN - RTS	REVISED -
PLOT SCALE = 100.0000' / IN.		CHECKED - RTS	REVISED -
PLOT DATE = Mar-26-2010 11:59:20AM		DATE - 3-10-10	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES

SCALE: SHEET NO. 4 OF 8 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
**	*	MONTGOMERY	60	17
CONTRACT NO. 72C52			ILLINOIS FED. AID PROJECT	