SUMMARY OF QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	QUANTITY	100% STATE ROADWAY IDOT	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	27	27	
40600300	AGGREGATE (PRIME COAT)	TON	144	144	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	276	276	
40600990	TEMPORARY RAMP	SQ YD	116	116	
40603310	HOT - MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	5,887	5,887	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	148	148	
44000155	HOT - MIX ASPHALT SURFACE REMOVAL, 1-1/2"	SQ YD	71,556	71,556	
44200156	PAVEMENT PATCHING, TYPE II, 13 INCH	SQ YD	80	80	
44200160	PAVEMENT PATCHING, TYPE III, 13 INCH	SQ YD	40	40	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1,058	1,058	
48203029	HOT - MIX ASPHALT SHOULDERS, 8"	SQ YD	1513	1513	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12	
67100100	MOBILIZATION	L SUM	1	1	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5,289	5,289	
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	66,803	66,803	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ. FT.	881	881	
* 78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	66,803	66,803	
* 78004240	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 8"	FOOT	117	117	
* 78004250	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 12"	FOOT	812	812	
* 78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	94	94	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	268	268	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	268	268	

* SPECIALTY ITEM

FILE NAME = c:\pw_work\PWIDOT\LAUGHLINRL\d0198500\D72C55-sht-S00.dgn	USER NAME = loughlinrl	DESIGNED - TCG	REVISED -
		DRAWN - JJS	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED - MTM	REVISED -
	PLOT DATE = Apr-07-2010 09:36:04AM	DATE - FEBRUARY 2010	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.T.S | SHEET NO. 1 OF 1 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
506	123RS-5	HANCOCK	14	3

CONTRACT NO. 72C55

ILLINOIS FED. AID PROJECT