ENTRANCE IMPROVEMENT SCHEDULE FOR RURAL / URBAN "PPP" PROJECTS

LOCATION	TYPE OF ENTRANCE	EX MATERIAL TYPE	WIDTH (Mainline)	RT OFFSET	LT OFFSET	LENGTH (FROM EDGE OF PVT/) BIT SHLD TO LIMITS OF IMPROVEMENT)	PR BIT. CONCRETE THICKNESS	BIT. SURF. REM. -BUTT JOINT	P.C.C. SURF. REM. -BUTT JOINT	PREP OF BASE	AGG. BASE REPAIR	AGG. SURF. CSE. TY-B	BIT (P.C.)	AGG (P.C.)	INCIDENTAL BIT. SURF.	Left Wedge Width	Right Wedge Width	Area	AGG WEDGE AVG. THICKNESS	AGG WEDGE Length
			FOOT	FOOT	FOOT	FOOT	INCH	SQ. YD.	SQ. YD.	SQ. YD.	TON	TON	TON	TON	TON	FT	FT	SQ YD	INCH	FOOT
STA 141+50.00 LT	PE / RURAL	AGG	20.0			8.0	1.5	31.1				0.7	0.1	0.1	2.6	15.0	15.0	31.1	0.75	7.0
STA 145+75.14 RT	CE / RURAL	BIT	30.0			10.0	1.5	50.0					0.1	0.1	4.2	15.0	15.0	50.0		
STA 147+33.54 LT	PE / RURAL	BIT	15.0			8.0	1.5	26.7					0.1	0.1	2.2	15.0	15.0	26.7		
STA 150+50.34 RT	CE / RURAL	AGG	20.0			10.0	1.5	38.9				0.5	0.1	0.1	3.3	15.0	15.0	38.9	0.75	5.0
STA 152+08.74 RT	CE / RURAL	AGG	20.0			10.0	1.5	38.9				0.5	0.1	0.1	3.3	15.0	15.0	38.9	0.75	5.0
STA 153+67.14 LT	PE / RURAL	BIT	20.0			8.0	1.5	31.1					0.1	0.1	2.6	15.0	15.0	31.1		
STA 157+36.74 LT	PE / RURAL	BIT	20.0			8.0	1.5	31.1					0.1	0.1	2.6	15.0	15.0	31.1		
STA 181+65.54 LT	PE / RURAL	AGG	20.0			8.0	1.5	31.1				0.7	0.1	0.1	2.6	15.0	15.0	31.1	0.75	7.0
STA 184+82.34 RT	PE / RURAL	BIT	20.0			8.0	1.5	31.1					0.1	0.1	2.6	15.0	15.0	31.1		
STA 194+85.54 ST	PE / RURAL	AGG	15.0			8.0	1.5	26.7				0.5	0.1	0.1	2.2	15.0	15.0	26.7	0.75	7.0
STA 195+91.14 LT	PE / RURAL	AGG	15.0			8.0	1.5	26.7				0.5	0.1	0.1	2.2	15.0	15.0	26.7	0.75	7.0
STA 199+60.74 LT	PE / RURAL	AGG	20.0			8.0	1.5	31.1				0.7	0.1	0.1	2.6	15.0	15.0	31.1	0.75	7.0
STA 202+77.54 LT	CE / RURAL	AGG	20.0			10.0	1.5	38.9				0.5	0.1	0.1	3.3	15.0	15.0	38.9	0.75	5.0
STA 203+83.14 RT	PE / RURAL	AGG	20.0			8.0	1.5	31.1				0.7	0.1	0.1	2.6	15.0	15.0	31.1	0.75	7.0
STA 204+35.94 RT	PE / RURAL	AGG	20.0			8.0	1.5	31.1				0.7	0.1	0.1	2.6	15.0	15.0	31.1	0.75	7.0
STA 206+99.94 LT	CE / RURAL	AGG	40.0			10.0	1.5	61.1				0.9	0.1	0.2	5.1	15.0	15.0	61.1	0.75	5.0
STA 227+31.17 RT	SIDE ROAD / RURAL	BIT.	18.0			10.0	1.5	36.7					0.1	0.1	3.1	15.0	15.0	36.7		
STA 227+34.59 RT	SIDE ROAD / RURAL	BIT.	20.0			10.0	1.5	38.9					0.1	0.1	3.3	15.0	15.0	38.9		
STA 230+23.14 RT	CE / RURAL	AGG	30.0			10.0	1.5	50.0				0.7	0.1	0.1	4.2	15.0	15.0	50.0	0.75	5.0
STA 252+93.54 LT	PE / RURAL	BIT	20.0			8.0	1.5	31.1					0.1	0.1	2.6	15.0	15.0	31.1		
STA 281+17.09 LT.	SIDE ROAD	BIT.	30.0			10.0	1.5	50.0					0.1	0.1	4.2	15.0	15.0	50.0		
STA 281+17.09 RT	SIDE ROAD	BIT.	30.0			10.0	1.5	50.0					0.1	0.1	4.2	15.0	15.0	50.0		
STA 328+43.94 RT	CE / URBAN	AGG	20.0			10.0	1.5	38.9				0.5	0.1	0.1	3.3	15.0	15.0	38.9	0.75	5.0
STA 330+55.14 LT	PE / URBAN	AGG	20.0			8.0	1.5	31.1				0.7	0.1	0.1	2.6	15.0	15.0	31.1	0.75	7.0
STA 334+24.74 LT	PE / URBAN	AGG	20.0			8.0	1.5	31.1				0.7	0.1	0.1	2.6	15.0	15.0	31.1	0.75	7.0
STA 334+73.18 LT	SIDE ROAD / URBAN	BIT.	20.0			10.0	1.5	38.9					0.1	0.1	3.3	15.0	15.0	38.9		
STA 334+73.18 LT	SIDE ROAD / URBAN	BIT.	20.0			10.0	1.5	38.9					0.1	0.1	3.3	15.0	15.0	38.9		
STA 334+77.54 LT	PE / URBAN	AGG	20.0			8.0	1.5	31.1				0.7	0.1	0.1	2.6	15.0	15.0	31.1	0.75	7.0
STA 339+37.67 LT	SIDE ROAD / URBAN	BIT.	21.0			10.0	1.5	40.0					0.1	0.1	3.4	15.0	15.0	40.0		
STA 339+37.67 RT	SIDE ROAD / URBAN	BIT.	20.0			10.0	1.5	38.9					0.1	0.1	3.3	15.0	15.0	38.9		
STA 341+11.44 LT	CE / URBAN	PCC	30.0			10.0	1.5		50.0				0.1	0.1	4.2	15.0	15.0	50.0		
STA 342+16.74 RT	PE / URBAN	BIT	20.0			8.0	1.5	31.1					0.1	0.1	2.6	15.0	15.0	31.1		
STA 344+08.20 LT	SIDE ROAD / URBAN	BIT.	20.0			10.0	1.5	38.9					0.1	0.1	3.3	15.0	15.0	38.9		
STA 344+08.20 RT	SIDE ROAD / URBAN	BIT.	20.0			10.0	1.5	38.9					0.1	0.1	3.3	15.0	15.0	38.9		
STA 344+80.74 LT	PE / URBAN	BIT	30.0			8.0	1.5	40.0					0.1	0.1	3.4	15.0	15.0	40.0		
STA 346+39.14 RT	PE / URBAN	BIT	20.0			8.0	1.5	31.1					0.1	0.1	2.6	15.0	15.0	31.1		
STA 348+73.27 LT	SIDE ROAD / URBAN	BIT.	20.0			10.0	1.5	38.9					0.1	0.1	3.3	15.0	15.0	38.9		
STA 348+73.27 RT	SIDE ROAD / URBAN	BIT.	20.0			10.0	1.5	38.9					0.1	0.1	3.3	15.0	15.0	38.9		
STA 349+03.14 LT	PE / URBAN	BIT	20.0			8.0	1.5	31.1					0.1	0.1	2.6	15.0	15.0	31.1		
STA 350+61.54 LT	PE / URBAN	BIT	20.0			8.0	1.5	31.1					0.1	0.1	2.6	15.0	15.0	31.1		
STA 353+23.89 LT	SIDE ROAD / URBAN	BIT.	20.0			10.0	1.5	38.9					0.1	0.1	3.3	15.0	15.0	38.9		
STA 353+23.89 RT	SIDE ROAD / URBAN	BIT.	20.0			10.0	1.5	38.9					0.1	0.1	3.3	15.0	15.0	38.9		
STA 379+65.54 LT	PE / URBAN	AGG	20.0			8.0	1.5	31.1				0.7	0.1	0.1	2.6	15.0	15.0	31.1	0.75	7.0
STA 382+29.54 LT	PE / URBAN	AGG	20.0			8.0	1.5	31.1				0.7	0.1	0.1	2.6	15.0	15.0	31.1	0.75	7.0
STA 385+46.34 LT	PE / URBAN	AGG	20.0			8.0	1.5	31.1				0.7	0.1	0.1	2.6	15.0	15.0	31.1	0.75	7.0
STA 401+83.14 LT	CE / RURAL	AGG	20.0			10.0	1.5	38.9				0.5	0.1	0.1	3.3	15.0	15.0	38.9	0.75	5.0
STA 407+30.10 RT	SIDE ROAD / RURAL	AGG	30.0			10.0	1.5	50.0				0.7	0.1	0.1	4.2	15.0	15.0	50.0	0.75	5.0
STA 435+45.39 LT	SIDE ROAD / RURAL	AGG	30.0			10.0	1.5	50.0				0.7	0.1	0.1	4.2	15.0	15.0	50.0	0.75	5.0
STA 437+20.74 RT	PE / RURAL	AGG	20.0			8.0	1.5	31.1				0.7	0.1	0.1	2.6	15.0	15.0	31.1	0.75	7.0
STA 444+59.94 LT	PE / RURAL	AGG	20.0			8.0	1.5	31.1				0.7	0.1	0.1	2.6	15.0	15.0	31.1	0.75	7.0
STA 447+76.74 LT	PE / RURAL	AGG	20.0			8.0	1.5	31.1				0.7	0.1	0.1	2.6	15.0	15.0	31.1	0.75	7.0
STA 462+55.14 RT	PE / RURAL	AGG	20.0			8.0	1.5	31.1					0.1	0.1	2.6	15.0	15.0	31.1		
STA 491+02.35 LT	PE / RURAL	AGG	30.0			10.0	1.5	50.0					0.1	0.1	4.2	15.0	15.0	50.0		
STA 491+59.14 LT	PE / RURAL	BIT	30.0			10.0	1.5	50.0					0.1	0.1	4.2	15.0	15.0	50.0		
STA 496+87.14 LT	PE / RURAL	AGG	20.0			8.0	1.5	31.1					0.1	0.1	2.6	15.0	15.0	31.1		
SUB-TOTAL =								1987.8	50.0			15.8	5.5	5.6	171.2			2037.8		