

SUMMARY OF QUANTITIES				100% STATE	
CODE NUMBER	PAY ITEM	UNIT	QUANTITY	ROADWAY 1000	
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	203	203	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	100	
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	166	166	
28200200	FILTER FABRIC	SQ YD	166	166	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	129	129	
40600300	AGGREGATE (PRIME COAT)	TON	680	680	
40600895	CONSTRUCTION TEST STRIP	EACH	1	1	
40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	791	791	
40600990	TEMPORARY RAMP	SQ YD	328	328	
40603540	POLYMERIZED HOT - MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	24,687	24,687	
40800050	INCIDENTAL HOT MIX ASPHALT SURFACING	TON	2,458	2,458	
44000157	HOT - MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	340,218	340,218	
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	50	50	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	5,230	5,230	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	13,417	13,417	
60100946	PIPE DRAINS 12"	FOOT	30	30	
60265505	MEDIAN INLET (604101) TO BE RECONSTRUCTED	EACH	2	2	
63500105	DELINEATORS	EACH	257	257	
64200105	SHOULDER RUMBLE STRIP	FOOT	116,432	116,432	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12	
67100100	MOBILIZATION	L SUM	1	1	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4	4	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1	
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L. SUM	1	1	
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L. SUM	1	1	
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L. SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	13,600	13,600	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2,267	2,267	

SUMMARY OF QUANTITIES				100% STATE	
CODE NUMBER	PAY ITEM	UNIT	QUANTITY	ROADWAY 1000	
78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SQ FT	1,594	1,594	
78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	14,197	14,197	
78004230	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID-LINE 6"	FOOT	2,221	2,221	
78004240	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID-LINE 8"	FOOT	2,554	2,554	
78004250	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID-LINE 12"	FOOT	320	320	
78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID-LINE 24"	FOOT	212	212	
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,116	1,116	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,116	1,116	
X0322279	OUTLET MARKER	EACH	305	305	
X0322729	MATERIAL TRANSFER DEVICE	TON	20,309	20,309	
X0323586	PIPE DRAIN REMOVAL	FOOT	30	30	
X0326351	CONCRETE APRON FOR MEDIAN INLET	EACH	21	21	
X2503000	MAINTENANCE MOWING	ACRE	80.4	80.4	
X7800620	URETHANE PAVEMENT MARKING - LINE 5"	FOOT	148,615	148,615	
X7800630	URETHANE PAVEMENT MARKING - LINE 6"	FOOT	5,321	5,321	

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
a:\pwwork\K\PI\DOT\LAUGHLINRL\02001201\0372014_shl_500.dgn		DRAWN - JJS	REVISED -
		CHECKED - MTM	REVISED -
		DATE - DECEMBER 2009	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
302	1-7(RS)	ADAMS	38	3
CONTRACT NO. 72014				
ILLINOIS FED. AID PROJECT				