

6' INSIDE SHOULDER RESURFACING SCHEDULE						
STATION TO STATION	WIDTH	HMA SURFACE REMOVAL	HMA SURFACE MIX "C", NSO 2"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	AGGREGATE SHOULDERS TYPE B. (WEDGE)
		2"				
		SQ. YDS.	TON			
TR 170						
164+67.63 TO 169+01.30	6.00	204.30	22.9	0.08	0.41	11.3
170+59.38 TO 171+21.63	6.00	31.67	3.5	0.01	0.06	1.50
171+21.63 TO 188+34.00	6.00	1,141.58	127.9	0.43	2.28	65.0
PE						
188+34.00 TO 192+86.99	6.00	207.29	23.2	0.08	0.41	11.4
193+12.98 TO 193+30.99	6.00	15.74	1.8	0.01	0.03	0.70
193+30.99 TO 207+15.63	6.00	923.09	103.4	0.35	1.85	52.6
PE						
207+15.63 TO 213+72.93	6.00	299.85	33.6	0.11	0.6	16.0
214+45.94 TO 215+01.55	6.00	31.20	3.5	0.01	0.06	1.5
215+01.55 TO 235+34.08	6.00	1,355.02	151.8	0.51	2.71	77.2
PE						
235+34.08 TO 239+87.13	6.00	212.53	23.8	0.08	0.43	11.8
240+22.97 TO 240+40.99	6.00	15.72	1.8	0.01	0.03	0.7
240+40.99 TO 251+20.93	6.00	719.96	80.6	0.27	1.44	41.0
PE						
251+20.93 TO 255+74.02	6.00	206.91	23.2	0.08	0.41	11.4
255+99.97 TO 256+17.99	6.00	15.72	1.8	0.01	0.03	0.7
256+17.99 TO 288+31.74	6.00	2,142.50	240.0	0.81	4.29	122.0
TR 147						
288+31.74 TO 293+10.46	6.00	216.32	24.2	0.08	0.43	11.9
293+94.54 TO 294+37.48	6.00	30.90	3.5	0.01	0.06	1.50
294+37.48 TO 344+00	6.00	3,308.35	370.5	1.26	6.62	188.4
TOTAL						
	6.00	42,549.82	4,765.58	16.17	85.1	2,413.70
USE						
	6.00	42,550	4,766	16	85	2,414

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
e:\pwwork\PWIDOT\LAUGHLINRL\0200120\0672014_sht_schedu1.dgn		DRAWN - STM	REVISED -
		CHECKED - MTM	REVISED -
		DATE - JANUARY 2010	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES			
SCALE: 1"=50'	SHEET NO. 8 OF 14 SHEETS	STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
302	1-7(RS)	ADAMS	38	11
CONTRACT NO. 72D14				
ILLINOIS FED. AID PROJECT				