

SUMMARY OF QUANTITIES

| CODE NO.   | ITEM  | Unit    | Total Quantity | CONST. TYPE CODE<br>1000 (100% STATE) |
|------------|---|---------|----------------|---------------------------------------|
| 20200600   | EXCAVATING AND GRADING EXISTING SHOULDER              | UNIT    | 1353           | 1353                                  |
| 40200800   | AGGREGATE SURFACE COURSE, TYPE B                      | TON     | 42             | 42                                    |
| 40600200   | BITUMINOUS MATERIALS (PRIME COAT)                     | TON     | 0.4            | 0.4                                   |
| 40600300   | AGGREGATE (PRIME COAT)                                | TON     | 2              | 2                                     |
| 40600982   | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT          | SQ YD   | 749            | 749                                   |
| 40600985   | PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT | SQ YD   | 183            | 183                                   |
| 40800050   | INCIDENTAL HOT-MIX ASPHALT SURFACING                  | TON     | 166            | 166                                   |
| 44200972   | CLASS B PATCHES, TYPE II, 10 1/2 INCH                 | SQ. YD. | 44             | 44                                    |
| 44200994   | CLASS B PATCHES, TYPE II, 12 INCH                     | SQ. YD. | 392            | 392                                   |
| 44200998   | CLASS B PATCHES, TYPE III, 12 INCH                    | SQ. YD. | 25             | 25                                    |
| 44201000   | CLASS B PATCHES, TYPE IV, 12 INCH                     | SQ. YD. | 31             | 31                                    |
| 44201785   | CLASS D PATCHES, TYPE I, 12 INCH                      | SQ YD   | 5              | 5                                     |
| 44201789   | CLASS D PATCHES, TYPE II, 12 INCH                     | SQ YD   | 490            | 490                                   |
| 44201794   | CLASS D PATCHES, TYPE III, 12 INCH                    | SQ YD   | 124            | 124                                   |
| 44201796   | CLASS D PATCHES, TYPE IV, 12 INCH                     | SQ YD   | 681            | 681                                   |
| 44213100   | PAVEMENT FABRIC                                       | SQ YD   | 56             | 56                                    |
| 44213200   | SAW CUTS  | FOOT    | 2782           | 2782                                  |
| 48101200   | AGGREGATE SHOULDERS, TYPE B                           | TON     | 5321           | 5321                                  |
| 48203029   | HOT-MIX ASPHALT SHOULDERS, 8"                         | SQ YD   | 60,132         | 60,132                                |
| 64200105   | SHOULDER RUMBLE STRIP                                 | FOOT    | 131,490        | 131,490                               |
| 67100100   | MOBILIZATION  | L SUM   | 1              | 1                                     |
| 70100450   | TRAFFIC CONTROL AND PROTECTION, STANDARD 701201       | L SUM   | 1              | 1                                     |
| 70100460   | TRAFFIC CONTROL AND PROTECTION, STANDARD 701306       | L SUM   | 1              | 1                                     |
| 70100500   | TRAFFIC CONTROL AND PROTECTION, STANDARD 701326       | L SUM   | 1              | 1                                     |
| 70103815   | TRAFFIC CONTROL SURVEILLANCE                          | CAL DA  | 20             | 20                                    |
| 70300230   | TEMPORARY PAVEMENT MARKING - LINE 5"                  | FOOT    | 140,134        | 140,134                               |
| 78300100   | PAVEMENT MARKING REMOVAL                              | SQ FT   | 68,147         | 68,147                                |
| * X7800620 | URETHANE PAVEMENT MARKING - LINE 5"                   | FOOT    | 163,552        | 163,552                               |
| Z0017100   | DOWEL BARS  | EACH    | 1200           | 1200                                  |
| Z0075300   | TIE BARS  | EACH    | 12             | 12                                    |

\* SPECIALTY Item

|             |             |                |           |   |                              |                         |      |         |   |                |          |              |           |
|-------------|-------------|----------------|-----------|---|------------------------------|-------------------------|------|---------|---|----------------|----------|--------------|-----------|
| FILE NAME : | USER NAME : | DESIGNED - KCM | REVISED - | <b>STATE OF ILLINOIS<br/>DEPARTMENT OF TRANSPORTATION</b> | <b>SUMMARY OF QUANTITIES</b> |                         |      |         | F.A.P. RTE.                                   | SECTION        | COUNTY   | TOTAL SHEETS | SHEET NO. |
|             |             | DRAWN - RNH    | REVISED - |   | SCALE: NTS                   | SHEET NO. 1 OF 1 SHEETS | STA. | TO STA. | 662   | (D, DX, E, FI) | MACOUPIN | 20           | 3         |
|             |             | CHECKED - TMM  | REVISED - |   |                              |                         |      |         | CONTRACT NO. 72D39                            |                |          |              |           |
|             |             | DATE - 3-26-10 | REVISED - |   |                              |                         |      |         | FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT |                |          |              |           |