

HOT MIX ASPHALT SHOULDER 8"	
LOCATION *	SQ YD
STA. 43+92.50 TO STA. 502+56.67	40768.2
STA. 506+20.84 TO STA. 650+69.37	12843.1
STA. 2191+15.89 TO STA. 2221+57.00	2703.2
STA. 2221+57.00 TO STA. 2223+50.00	85.8 LT ONLY
STA. 2233+19.14 TO STA. 2248+42.00	1353.7
STA. 6+22.20 TO STA. 32+98.00	2378.5
TOTAL	60132.4

AGGREGATE SHOULDERS, TYPE B (ASSUMES 2" AVERAGE THICKNESS)	
LOCATION *	TON
STA. 43+92.50 TO STA. 502+56.67	3483.0
STA. 506+20.84 TO STA. 650+69.37	1097.2
STA. 2191+15.89 TO STA. 2221+57.00	230.9
STA. 2221+57.00 TO STA. 2223+50.00	7.3 LT ONLY
STA. 2233+19.14 TO STA. 2248+42.00	115.6
STA. 6+22.20 TO STA. 32+98.00	203.2
TOTAL	5321.0

EXCAVATING & GRADING EXISTING SHOULDER	
LOCATION *	UNIT
STA. 43+92.50 TO STA. 502+56.67	917.3
STA. 506+20.84 TO STA. 650+69.37	289.0
STA. 2191+15.89 TO STA. 2221+57.00	60.8
STA. 2221+57.00 TO STA. 2223+50.00	1.9 LT ONLY
STA. 2233+19.14 TO STA. 2248+42.00	30.5
STA. 6+22.20 TO STA. 32+98.00	53.5
TOTAL	1353.0

PAVEMENT MARKING SCHEDULE			
LOCATION	DESCRIPTION	URETHANE PAVEMENT MARKING LINE - 5" FOOT	PAVEMENT MARKING REMOVAL SQUARE FOOT
STA. 34+04.00 TO STA. 650+69.37	LEFT EDGE LINE - WHITE	61,665.4	25693.9
STA. 2191+15.89 TO STA. 2248+42.00	LEFT EDGE LINE - WHITE	5726.1	2385.9
STA. 6+22.20 TO STA. 32+98.00	LEFT EDGE LINE - WHITE	2675.8	1114.9
STA. 34+04.00 TO STA. 650+69.37	RIGHT EDGE LINE - WHITE	61,665.4	25693.9
STA. 2191+15.89 TO STA. 2248+42.00	RIGHT EDGE LINE - WHITE	5726.1	2385.9
STA. 6+22.20 TO STA. 32+98.00	RIGHT EDGE LINE - WHITE	2675.8	1114.9
STA. 34+04.00 TO STA. 650+69.37	30' SKIP / 10' DASH CENTERLINE - YELLOW	15,416.4	6423.5
STA. 2191+15.89 TO STA. 2248+42.00	30' SKIP / 10' DASH CENTERLINE - YELLOW	1431.5	596.5
STA. 6+22.20 TO STA. 31+75.00	30' SKIP / 10' DASH CENTERLINE - YELLOW	638.2	265.9
STA. 171+00.00 TO STA. 174+30.00	S. B NO PASSING LINE - YELLOW	330.0	137.5
STA. 487+05.00 TO STA. 494+10.00	S. B NO PASSING LINE - YELLOW	705.0	293.8
STA. 2212+00.00 TO STA. 2220+20.00	S. B NO PASSING LINE - YELLOW	820.0	341.7
STA. 21+10.00 TO STA. 32+98.00	S. B NO PASSING LINE - YELLOW	1188.0	495.0
STA. 175+20.00 TO STA. 189+50.00	N. B NO PASSING LINE - YELLOW	1430.0	595.9
STA. 497+50.00 TO STA. 501+60.00	N. B NO PASSING LINE - YELLOW	410.0	170.8
STA. 2221+60.00 TO STA. 2230+90.00	N. B NO PASSING LINE - YELLOW	930.0	387.5
STA. 31+80.00 TO STA. 32+98.00	N. B NO PASSING LINE - YELLOW	118.0	49.2
TOTAL		163,551.7	68,146.7

SHOULDER RUMBLE STRIP	
LOCATION *	FOOT
STA. 55+00.00 TO STA. 213+00.00	31,600.0
STA. 233+00.00 TO STA. 650+69.37	83,538.7
STA. 2191+15.89 TO STA. 2221+57.00	6082.2
STA. 2221+57.00 TO STA. 2223+50.00	193.0 LT ONLY
STA. 2223+50.00 TO STA. 2227+82.00	864.0
STA. 2229+12.00 TO STA. 2248+42.00	3860.0
STA. 6+22.20 TO STA. 32+98.00	5351.6
TOTAL	131,489.5

* NOTE: WORK IS ON RIGHT AND LEFT UNLESS NOTED OTHERWISE