ENTRANCE IMPROVEMENT SCHEDULE FOR RURAL / URBAN "PPP" PROJECTS

LOCATION	TYPE OF ENTRANCE	EX MATERIAL TYPE	WIDTH	WIDTH AT MAILBOX	LT OFFSET (NOT USED)	LENGTH (FROM EDGE OF PVT/ BIT SHLD TO LIMITS OF IMPROVEMENT)	PR HMA CONC. THICKNESS	HMA SURF. REM. - BUTT JOINT	P.C.C. SURF. REM. - BUTT JOINT	PREP OF BASE	AGG. BASE REPAIR	AGGREGATE SURFACE COURSE TY - B	BIT (PRIME COAT)	AGG (PRIME COAT)	INCIDENTAL HMA SURF.
(LT / RT) (STA) (+)	(FE / PE / CE / MB) (RURAL / URBAN)	(EARTH / AGG. / BIT. / P.C.C.)	FOOT	FOOT	FOOT	FOOT	INCH	SQ. YD.	SQ. YD.	SQ. YD.	TON	TON	TON	TON	TON
(LT) STA. 2229+35	CE	BIT.	32.0			4.0	1.5	16					0.0061	0.0228	1.34
(RT) STA. 2233+50	CE	PCC	55.0			4.0	1.5		26				0.0100	0.0374	2.20
(LT) STA. 2234+20	CE	BIT.	34.0			4.0	1.5	17					0.0064	0.0241	1.42
(RT) STA. 2236+10	CE	PCC	56.0			4.0	1.5		26				0.0100	0.0374	2.20
(LT) STA. 2238+10	CE	PCC	60.0			4.0	1.5		28				0.0108	0.0405	2.39
(RT) STA. 2240+90	PE	BIT.	18.0			4.0	1.5	10					0.0037	0.0139	0.82
(LT) STA. 2241+00	MB	BIT.		20.0		4.0	6.0								4.48
(RT) STA. 2242+90	CE	BIT.	60.0			4.0	1.5	28					0.0108	0.0405	2.39
(LT) STA. 2243+20	CE	BIT.	24.0			4.0	1.5	12					0.0047	0.0177	1.05
(RT) STA. 2245+45	CE	PCC	44.0			4.0	1.5		21				0.0081	0.0304	1.79
(RT) STA. 2246+85	CE	PCC	50.0			4.0	1.5		24				0.0091	0.0342	2.02
(LT) STA. 7+20	CE	BIT.	60.0			4.0	1.5	28					0.0108	0.0405	2.39
(RT) STA. 9+78.80	SR	BIT.	44.0			4.0	1.5	21					0.0081	0.0304	1.79
(LT) STA. 9+78.80	SR	BIT.	66.0			4.0	1.5	31					0.0118	0.0443	2.61
(RT & LT) STA. 23+00	FE/RURAL	EARTH	*												
(LT) STA. 31+75	FE/RURAL	EARTH	*												
(RT) STA. 32+41.62	SR	BIT.	70.0			4.0	1.5	33					0.0125	0.0469	2.76
TOTAL THIS SHEET=								196	125				0.0921	0.3457	31.65
GRAND TOTAL =								749	183			6.0	0.3544	1.3294	165.42

NOTES:

*** FIELD ENTRANCES SHOWN FOR INFORMATIONAL PURPOSES ONLY. PROPOSED AGGREGATE SHOULDER, TYPE B TO CONTINUE THROUGH FIELD ENTRANCES.**

**** SIDEROADS WITH EXISTING SHOULDER RADII. SEE DETAIL.**

FILE NAME = c:\pw_work\PWIDOT\LAUGHLINRL\d0194809\D8-72D39-017-019-entrance_details.dgn	USER NAME = laughlinrl	DESIGNED - KCM	REVISED -
	PLOT SCALE = 40.000 ' / IN.	DRAWN - RNH	REVISED -
	PLOT DATE = Mar-30-2010 09:52:02AM	CHECKED - TMM	REVISED -
		DATE - 3-26-10	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

DETAILS FOR RURAL/URBAN ENT., MAILBOX TURNOUT & SIDEROADS

SCALE: | SHEET NO. 4 OF 4 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
662	(D, DX, E, FI	MACOUPIN	20	19
			CONTRACT NO. 72D39	
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		