

PAY CODE	ITEM	UNIT	TOTAL	STA 502+00	STA 285+00	BRIDGE	BRIDGE
				to	to	REPAIRS	REPAIRS
				STA 695+65	STA 502+00	URBAN	RURAL
				URBAN	RURAL	URBAN	RURAL
				100% STATE	100% STATE	100% STATE	100% STATE
				I000	I000	SFTY-2A	SFTY-2A
44004250	PAVED SHOULDER REMOVAL	SQ YD	18,403			6,499	11,904
44200966	CLASS B PATCHES, TYPE I, 10 INCH	SQ YD	14		14		
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	63		63		
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	16		16		
44201027	CLASS B PATCHES, TYPE I, 15 INCH	SQ YD	221	221			
44201031	CLASS B PATCHES, TYPE II, 15 INCH	SQ YD	4,359	2,852	1,507		
44201035	CLASS B PATCHES, TYPE III, 15 INCH	SQ YD	1,336	831	505		
44201037	CLASS B PATCHES, TYPE IV, 15 INCH	SQ YD	5,670	2,538	3,132		
44213100	PAVEMENT FABRIC	SQ YD	5,670	2,538	3,132		
44213200	SAW CUTS	FOOT	42,287	24,985	17,302		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	7,236	3,915	3,321		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	2,035.5	1,713.3			322.2
48203100	HOT-MIX ASPHALT SHOULDERS	TON	17,818	8,807	9,011		
50102400	CONCRETE REMOVAL	CU YD	191.1			102.3	88.8
50104650	SLOPE WALL REMOVAL	SQ YD	81			7	74.0
50157300	PROTECTIVE SHIELD	SQ YD	36				36
50300255	CONCRETE SUPERSTRUCTURE	CU YD	193.3			103.1	90.2