

FAI-55 (I-55)
Class B Patching Survey - North Bound

Station	Lane (DL/PL)	Length (ft)	Width (ft)	Saw Cuts (ft)	Tie Bars (EA)	Dowel Bars (EA)	CI B, Ty I (SQ YD)	CI B, Ty II (SQ YD)	CI B, Ty III (SQ YD)	CI B, Ty IV (SQ YD)	PVT FABRIC (SQ YD)
692+00	PL	6	12	48		20		8.00			
692+00	DL	6	12	48		20		8.00			
691+25	PL	6	12	48		20		8.00			
691+25	DL	6	12	48		20		8.00			
691+00	DL	6	12	48		20		8.00			
689+20	PL	6	12	48		20		8.00			
689+20	DL	6	12	48		20		8.00			
687+60	DL	6	12	48		20		8.00			
685+50	DL	14	12	64		20			18.67		
684+50	DL	12	12	60		20			16.00		
683+50	DL	8	12	52		20		10.67			
683+10	DL	6	12	48		20		8.00			
682+80	DL	6	12	48		20		8.00			
682+30	DL	6	12	48		20		8.00			
677+65	DL	6	12	48		20		8.00			
676+90	PL	8	12	52		20		10.67			
676+90	DL	8	12	52		20		10.67			
674+80	DL	14	12	64		20			18.67		
673+90	DL	16	12	68		20			21.33		
669+90	DL	6	12	48		20	8.00				
668+10	DL	32	12	100	16	20				42.67	42.67
667+60	DL	6	12	48		20	8.00				
667+00	DL	14	12	64		20			18.67		
666+45	DL	12	12	60		20			16.00		
665+95	DL	6	12	48		20	8.00				
664+90	DL	6	12	48		20	8.00				
664+70	DL	6	12	48		20	8.00				
664+00	DL	14	12	64		20			18.67		
653+00	DL	14	12	64		20			18.67		
652+30	DL	32	12	100	16	20				42.67	42.67
652+00	DL	6	12	48		20	8.00				
651+80	DL	6	12	48		20	8.00				
651+10	DL	30	12	96	15	20				40.00	40.00
650+00	DL	6	12	48		20	8.00				
649+80	DL	6	12	48		20	8.00				
649+35	DL	6	12	48		20	8.00				
648+90	DL	24	12	84	12	20				32.00	32.00
657+00	DL	12	12	60		20			16.00		
651+50	PL	6	12	48		20	8.00				
651+50	DL	6	12	48		20	8.00				
650+50	PL	6	12	48		20	8.00				
650+50	DL	6	12	48		20	8.00				
649+90	DL	10	12	56		20	13.33				
645+55	PL	8	12	52		20	10.67				
645+55	DL	8	12	52		20	10.67				
644+50	DL	6	12	48		20	8.00				
643+50	PL	14	12	64		20			18.67		
643+50	DL	20	12	76	10	20				26.67	26.67
643+20	DL	12	12	60		20			16.00		
642+50	PL	6	12	48		20	8.00				
642+50	DL	10	12	56		20	13.33				
638+90	DL	6	12	48		20	8.00				
URBAN Subtotal 1 =				2,912	69	1,040	0.00	312.00	197.33	184.00	184.00

I-55 - NORTH BOUND

Station	Lane (DL/PL)	Length (ft)	Width (ft)	Saw Cuts (ft)	Tie Bars (EA)	Dowel Bars (EA)	CI B, Ty I (SQ YD)	CI B, Ty II (SQ YD)	CI B, Ty III (SQ YD)	CI B, Ty IV (SQ YD)	PVT FABRIC (SQ YD)
638+40	DL	6	12	48		20		8.00			
637+90	DL	6	12	48		20		8.00			
637+60	DL	22	12	80	11	20				29.33	29.33
637+40	DL	12	12	60		20			16.00		
636+40	DL	120	12	276	60	20				160.00	160.00
635+00	PL	6	12	48		20		8.00			
635+00	DL	6	12	48		20		8.00			
631+00	DL	14	12	64		20			18.67		
629+50	DL	6	12	48		20		8.00			
628+80	DL	16	12	68		20			21.33		
628+50	DL	6	12	48		20		8.00			
628+15	DL	27	12	90	14	20				36.00	36.00
627+90	DL	12	12	60		20			16.00		
627+70	PL	8	12	52		20		10.67			
627+50	DL	14	12	64		20			18.67		
625+20	DL	12	12	60		20			16.00		
624+90	DL	12	12	60		20			16.00		
624+60	DL	6	12	48		20		8.00			
624+20	PL	6	12	48		20		8.00			
623+20	DL	12	12	60		20			16.00		
619+00	DL	10	12	56		20		13.33			
617+90	DL	20	12	76	10	20				26.67	26.67
617+65	PL	8	12	52		20		10.67			
617+65	DL	8	12	52		20		10.67			
614+95	DL	6	12	48		20		8.00			
614+40	DL	6	12	48		20		8.00			
614+00	PL	6	12	48		20		8.00			
614+00	DL	6	12	48		20		8.00			
613+70	PL	6	12	48		20		8.00			
613+70	DL	12	12	60		20			16.00		
612+00	DL	8	12	52		20		10.67			
603+10	DL	6	12	48		20		8.00			
587+60	PL	6	12	48		20		8.00			
587+60	DL	6	12	48		20		8.00			
587+00	DL	6	12	48		20		8.00			
588+50	PL	6	12	48		20		8.00			
588+50	DL	6	12	48		20		8.00			
588+00	DL	6	12	48		20		8.00			
586+60	PL	6	12	48		20		8.00			
586+60	DL	6	12	48		20		8.00			
584+95	DL	8	12	52		20		10.67			
584+00	DL	6	12	48		20		8.00			
583+70	DL	6	12	48		20		8.00			
582+00	DL	12	12	60		20			16.00		
581+35	DL	6	12	48		20		8.00			
580+95	DL	14	12	64		20			18.67		
580+00	DL	12	12	60		20			16.00		
568+20	DL	6	12	48		20		8.00			
564+90	DL	6	12	48		20		8.00			
563+90	DL	20	12	76	10	20				26.67	26.67
559+60	DL	10	12	56		20		13.33			
558+60	DL	6	12	48		20		8.00			
558+10	DL	6	12	48		20		8.00			
557+50	DL	6	12	48		20		8.00			
556+80	DL	6	12	48		20		8.00			
URBAN Subtotal 2 =				3,198	105	1,100	0.00	328.00	205.33	278.67	278.67

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
et:\pw\work\PWIDOT\LAUGHLINRL\0176540\0672043-sht-schedule2.dgn		DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = Apr-29-2010 07:37:31AM	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	84-2(RS-3)	SANGAMON	156	13
CONTRACT NO. 72D43				
ILLINOIS FED. AID PROJECT				