

Sangamon Ave. - Contract # 72D43  
 Class B Patching - West Bound

Station	Lane (DL/PL)	Length (ft)	Width (ft)	Saw Cuts (ft)	Tie Bars (EA)	Dowel Bars (EA)	CI B, Ty I (SQ YD)	CI B, Ty II (SQ YD)	CI B, Ty III (SQ YD)	CI B, Ty IV (SQ YD)	PVT FABRIC (SQ YD)
62+00	RT DL	6	12	48		20		8.00			
62+00	RT PL	6	12	48		20		8.00			
60+70	RT DL	6	12	48		20		8.00			
59+80	LT DL	6	12	48		20		8.00			
59+80	LT PL	6	12	48		20		8.00			
59+80	RT DL	6	12	48		20		8.00			
59+00	LT PL	6	12	48		20		8.00			
59+00	LT DL	6	12	48		20		8.00			
58+70	LT PL	6	12	48		20		8.00			
58+70	LT DL	6	12	48		20		8.00			
58+70	RT PL	6	12	48		20		8.00			
58+70	RT DL	6	12	48		20		8.00			
56+50	LT PL	6	12	48		20		8.00			
56+50	LT DL	6	12	48		20		8.00			
56+50	RT PL	6	12	48		20		8.00			
56+50	RT DL	8	12	52		20		10.67			
55+20	LT PL	6	12	48		20		8.00			
55+20	LT DL	6	12	48		20		8.00			
53+00	PL	6	12	48		20		8.00			
53+00	DL	6	12	48		20		8.00			
52+40	PL	6	12	48		20		8.00			
52+40	DL	6	12	48		20		8.00			
51+90	PL	6	12	48		20		8.00			
51+90	DL	6	12	48		20		8.00			
50+40	PL	6	12	48		20		8.00			
50+40	DL	6	12	48		20		8.00			
49+60	PL	6	12	48		20		8.00			
49+60	DL	6	12	48		20		8.00			
48+80	PL	6	12	48		20		8.00			
48+80	DL	6	12	48		20		8.00			
45+60	PL	6	12	48		20		8.00			
45+60	DL	6	12	48		20		8.00			
34+50	PL	6	12	48		20		8.00	(pipe under drain exist patch)		
34+50	DL	6	12	48		20		8.00	(pipe under drain exist patch)		
24+85	PL	6	12	48		20		8.00	(pipe under drain exist patch)		
24+85	DL	6	12	48		20		8.00	(pipe under drain exist patch)		
22+90	PL	10	12	56		20		13.33			
22+90	DL	6	12	48		20		8.00			
21+50	PL	10	12	56		20		13.33			
21+50	DL	10	12	56		20		13.33			
20+50	PL	6	12	48		20		8.00			
20+30	PL	6	12	48		20		8.00			
20+20	PL	6	12	48		20		8.00			
20+20	DL	6	12	48		20		8.00			
19+80	PL	6	12	48		20		8.00			
19+80	DL	6	12	48		20		8.00			
19+40	PL	6	12	48		20		8.00			
19+40	DL	6	12	48		20		8.00			
19+10	PL	15	12	66		20			20.00		
19+10	DL	10	12	56		20		13.33			
18+50	DL	6	12	48		20		8.00			
16+00	DL	15	12	66					20.00		
WB SANGAMON AVE Total =				2,568	0	1,020	0.00	424.00	40.00	0.00	0.00
URBAN TOTAL =				2,568	0	1,020	0	424	40	0	0

FAI-55 (I-55) - Contract # 72D43  
 Class B Patching - Ramps

Sherman South Bound Exit Ramp - (16' Lane Patched at 9' & 7')

Station	Length (ft)	Width (ft)	Saw Cuts (ft)	Tie Bars (EA)	Dowel Bars (EA)	CI B, Ty I (SQ YD)	CI B, Ty II (SQ YD)	CI B, Ty III (SQ YD)	CI B, Ty IV (SQ YD)	PVT FABRIC (SQ YD)	
6+00	6	22	78	3	30		14.67	(Ramp and gore area)			
6+75	6	16	60	3	28	4.67	6.00				
7+50	6	16	60	3	28	4.67	6.00				
9+05	16	16	80	8	28		12.44	16.00			
9+75	10	16	68	5	28		17.78				
11+00	6	16	60	3	28	4.67	6.00				
Total			406	25	170	14.01	62.89	16.00	0.00		
RURAL			406	25	170	14	63	16	0	0	

SANGAMON AVE RAMPS

South Bound Exit Ramp to West Bound Sangamon Ave. - (16' Lane Patched at 9' & 7')

Station	Length (ft)	Width (ft)	Saw Cuts (ft)	Tie Bars (EA)	Dowel Bars (EA)	CI B, Ty I (SQ YD)	CI B, Ty II (SQ YD)	CI B, Ty III (SQ YD)	CI B, Ty IV (SQ YD)	PVT FABRIC (SQ YD)
6+50	6	16	60	3	28	4.67	6.00			
11+00	6	16	60	3	28	4.67	6.00			
12+50	6	16	60	3	28	4.67	6.00			
15+25	8	16	64	4	28		14.22			
Total			244	13	112	14.01	32.22	0.00	0.00	
URBAN			244	13	112	14	32	0	0	0

South Bound Entrance Ramp from West Bound Sangamon Ave. - (16' Lane Patched at 9' & 7')

Station	Length (ft)	Width (ft)	Saw Cuts (ft)	Tie Bars (EA)	Dowel Bars (EA)	CI B, Ty I (SQ YD)	CI B, Ty II (SQ YD)	CI B, Ty III (SQ YD)	CI B, Ty IV (SQ YD)	PVT FABRIC (SQ YD)
1+00	15	16	78	8	28		11.67	15.00		
2+00	10	16	68	5	28		17.78			
4+50	6	16	60	3	28	4.67	6.00			
5+00	6	16	60	3	28	4.67	6.00			
8+00	6	16	60	3	28	4.67	6.00			
Total			326	22	140	14.01	47.45	15.00	0.00	
URBAN			326	22	140	14	47	15	0	0

South Bound Exit Ramp to East Bound Sangamon Ave. - (16' Lane Patched at 9' & 7')

Station	Length (ft)	Width (ft)	Saw Cuts (ft)	Tie Bars (EA)	Dowel Bars (EA)	CI B, Ty I (SQ YD)	CI B, Ty II (SQ YD)	CI B, Ty III (SQ YD)	CI B, Ty IV (SQ YD)	PVT FABRIC (SQ YD)
6+00	6	16	60	3	28	4.67	6.00			
6+30	6	16	60	3	28	4.67	6.00			
10+00	6	16	60	3	28	4.67	6.00			
15+50	12	16	72	6	28		21.33			
16+00	20	16	88	10	28			35.56		35.56
16+50	6	16	60	3	28	4.67	6.00			
16+70	6	16	60	3	28	4.67	6.00			
Total			460	31	196	23.35	51.33	35.56	0.00	35.56
URBAN			460	31	196	23	51	36	0	36