

MAINLINE RUMBLE STRIPS

NB sta equ: 292+80.89bk=292+58.35 ah

			LENGTH
			(FT)
NB - OUTSIDE			
285+00.	to	290+71.	571
292+22.	to	292+80.89	59
292+58.35	to	336+72.	4414
348+37.	to	456+62.	10825
481+79.	to	494+79.	1300
501+61.	to	502+00.	39
RURAL =			17208
502+00.		586+28.	8428
599+91.	to	604+66.	475
612+29.	to	619+24.	695
627+13.	to	695+65.	6852
URBAN =			16450
NB - MEDIAN			
285+00.	to	290+71.	571
292+22.	to	292+80.89	59
292+58.35	to	344+75.	5217
348+37.	to	456+62.	10825
467+87.	to	502+00.	3413
RURAL =			20085
502+00.	to	582+65.	8065
618+50.	to	695+65.	7715
URBAN =			15780

NB & SB RURAL TOTAL =	73549
NB & SB URBAN TOTAL =	64665
JOB TOTAL =	138214

SB sta equ: 292+36.81 bk = 292+58.35 ah

			LENGTH
			(FT)
SB - OUTSIDE			
285+00.	to	290+17.	517
291+68.	to	292+36.81	69
292+58.35	to	320+37.	2779
334+11.	to	339+70.	559
349+11.	to	392+40.	4329
399+22.	to	412+34.	1312
424+24.	to	456+62.	3238
467+87.	to	502+00.	3413
RURAL =			16215
502+00.	to	592+51.	9051
599+34.	to	606+20.	686
613+84.	to	618+55.	471
631+18.	to	695+65.	6447
URBAN =			16655
SB - MEDIAN			
285+00.	to	290+17.	517
291+68.	to	292+36.81	69
292+58.35	to	345+49.	5291
349+10.	to	456+62.	10752
467+87.	to	502+00.	3413
RURAL =			20041
502+00.	to	582+65.	8065
618+50.	to	695+65.	7715
URBAN =			15780

HMA Shoulder / Widening Schedule

Location	Length ft	Width ft	Earth Ex Cu Yd	Paved Shoulder Removal Sq Yd	8" HMA Shoulder Sq Yd	12" HMA Base Course Sq Yd	HMA Shoulder Rem. & Repl. Sq Yd	Rural/ Urban
<i>Sangamon Ave</i>								
Sta 14+40 to Sta 23+20 LT	820	8	162.0		728.9			U
Sta 12+85 to Sta 23+40 RT	900	8	177.8		800.0			U
Sta 66+85 to Sta 71+00 LT	415	4	41.0		184.4			U
<i>Interstate Repair</i>								
as needed								
<i>SN 084-0088</i>								
NE Quadrant	90	4	8.9		40.0			R
SE Quadrant	200	4	19.8		88.9			R
SW Quadrant	200	4	19.8		88.9			R
NW Quadrant	235	4	23.2		104.4			R
<i>SN 084-0014 to SN 084-0017</i>				6,499		6,499		U
<i>SN 084-0018 and SN 084-0019</i>				4,872		4,872		R
<i>SN 084-0022 and SN 084-0023</i>				4,915		4,915		R
<i>SN 084-0021</i>				2,117		2,117		R
		Urban	380.7	6499.0	1713.3	6499.0	1000.0	
		Rural	71.6	11904.0	322.2	11904.0	1000.0	
		Total	452.3	18403.0	2035.6	18403.0	2000.0	