

SUMMARY OF QUANTITIES					100% STATE	0 % FEDERAL 100 % STATE CONSTRUCTION AND SAFETY TYPE CODE			
CODE NO.	ITEM	SP. PROV.	UNIT	TOTAL QUANTITIES	SFTY-2A ROADWAY & BRIDGE				
X0301424	SILICONE JOINT SEALER	Y	FOOT	92	92				
X0320887	POLYMER CONCRETE	Y	CU FT	12.4	12.4				
X0322469	PLUG EXISTING FLOOR DRAINS	Y	EACH	13	13				
XZ193500	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"	Y	SQ YD	663	663				
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	Y	SQ YD	438	438				
Z0006225	BRIDGE DECK HYDRO-SCARIFICATION 2 1/2"	Y	SQ YD	235	235				
20200500	EARTH EXCAVATION (WIDENING)	Y	CU YD	46	46				
35600712	HOT-MIX ASPHALT BASE COURSE WIDENING, 9"		SQ YD	185	185				
40600200	BITUMINOUS MATERIALS (PRIME COAT)		TON	0.7	0.7				
40600300	AGGREGATE (PRIME COAT)		TON	4	4				
40600625	LEVELING BINDER (MACHINE METHOD), N50		TON	64	64				
40600990	TEMPORARY RAMP		SQ YD	193	193				
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50		TON	156	156				
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"		SQ YD	1905	1905				
50300100	FLOOR DRAINS		EACH	10	10				
50300260	BRIDGE DECK GROOVING		SQ YD	639	639				
50300300	PROTECTIVE COAT		SQ YD	734	734				
67100100	MOBILIZATION		L SUM	1	1				
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306		L SUM	1	1				
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326		L SUM	1	1				
70103815	TRAFFIC CONTROL SURVEILLANCE		CAL DA	4	4				
70104005	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316, LOCATION 1	Y	EACH	1	1				
70104010	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316, LOCATION 2	Y	EACH	1	1				
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS		EACH	2	2				
70106700	TEMPORARY RUMBLE STRIP		EACH	12	12				
70300100	SHORT-TERM PAVEMENT MARKING		FOOT	312	312				
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"		FOOT	1516	1516				
70300530	PAVEMENT MARKING TAPE, TYPE III 5"		FOOT	3227	3227				
70300570	PAVEMENT MARKING TAPE, TYPE III 24"		FOOT	59	59				

FILE NAME =	USER NAME = coxte	DESIGNED -	REVISED -
c:\pwwork\FW1007\COXTE\d0183107\0672048-ahc-S00.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: NONE      SHEET NO. 1 OF 2 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
751	D6 BRIDGE REPAIR 2009	PIKE	22	3
CONTRACT NO. 72D44				
FED. ROAD DIST. NO.    ILLINOIS FED. AID PROJECT				