

**EARTH EXCAVATION (WIDENING) SCHEDULE**

LOCATION		20200500 VOLUME (CU YD)	
FAP 751 (IL 96) - SN 075-0004	22+190.00 TO 22+273.75	LT	11.6
		RT	11.6
	22+321.93 TO 22+405.00	LT	11.5
		RT	11.5
<b>TOTAL</b>			<b>46</b>

**PAVING SCHEDULE**

LOCATION			35600712 HMA BASE COURSE WIDENING 9" (SQ YD)	40600200 BITUMINOUS MATERIALS (PRIME COAT) (TON)	40600300 AGGREGATE (PRIME COAT) (TON)	40600625 LEVELING BINDER (MM), N50 (TON)	40603310 HMA SURFACE COURSE, MIX C, N50 (TON)	44000155 HMA SURFACE REMOVAL 1 1/2" (TON)
FAP 751 (IL 96) - SN 075-0024	294+17.00 TO 295+75.36	LT		0.13	0.66	16.2	27.8	331.3
		RT		0.13	0.69	16.9	29.0	345.8
	296+64.45 TO 298+15.00	LT		0.12	0.62	15.2	26.0	309.3
		RT		0.12	0.64	15.8	27.0	321.6
FAP 751 (IL 96) - SN 075-0004	22+190.00 TO 22+273.75	LT	46.5	0.06	0.30		11.5	149.8
		RT	46.5	0.06	0.30		11.5	149.8
	22+321.93 TO 22+405.00	LT	46.1	0.06	0.30		11.4	148.6
		RT	46.1	0.06	0.30		11.4	148.6
<b>TOTAL</b>			<b>185</b>	<b>0.7</b>	<b>4</b>	<b>64</b>	<b>156</b>	<b>1905</b>

**TEMPORARY RAMP SCHEDULE**

LOCATION		40600990 AREA (SQ YD)	
FAP 751 (IL 96) - SN 075-0024	294+17.00		17.8
	295+75.36		48.2
	296+64.45		48.2
	298+15.00		13.4
FAP 751 (IL 96) - SN 075-0004	221+90.00		17.8
	222+74.25		14.9
	223+21.43		14.9
	224+05.00		17.8
<b>TOTAL</b>		<b>193</b>	

**SHORT-TERM PAVEMENT MARKING SCHEDULE**

LOCATION			70300100 LENGTH (FOOT)	
			NUMBER	
FAP 751 (IL 96) - SN 075-0024	294+17.00 TO 298+15.00	CENTERLINE	3	120
		EDGE LINE	3	96
FAP 751 (IL 96) - SN 075-0004	221+90.00 TO 224+05.00	CENTERLINE	2	48
		EDGE LINE	2	48
<b>TOTAL</b>				<b>312</b>

**PAVEMENT MARKING SCHEDULE**

LOCATION				70300230 TEMPORARY 5" (FOOT)	78001120 PAINT 5" (FOOT)	78100100 RAISED REFL MKR (EACH)
FAP 751 (IL 96) - SN 075-0024	293+42 TO 299+03	CENTERLINE	YELLOW SKIP DASH	150	150	8
	294+17 TO 298+15	RT EDGE LINE	WHITE SOLID	398	398	
	294+17 TO 298+15	LT EDGE LINE	WHITE SOLID	398	398	
FAP 751 (IL 96) - SN 075-0004	220+37 TO 225+58	CENTERLINE	YELLOW SKIP DASH	140	140	7
	221+90 TO 224+05	LT EDGE LINE	WHITE SOLID	215	215	
	221+90 TO 224+05	RT EDGE LINE	WHITE SOLID	215	215	
<b>TOTAL</b>				<b>1516</b>	<b>1516</b>	<b>15</b>

FILE NAME =	USER NAME = coxte	DESIGNED -	REVISED -
e:\pwork\pwork\DOT\COXTE\183107\0672044\sh-t-schedule.dgn		DRAWN -	REVISED -
PLOT SCALE = 2.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = Feb-10-2010 01:52:13PM		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: NONE SHEET NO. 1 OF \* SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
751	D6 BRIDGE REPAIR 2009	PIKE	22	6
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 72D44	